

Famulus Notebook

A teaching book: writing, running, checking, annotating, sharing and publishing scholarly notebooks

Gerd Graßhoff 

Humboldt-Universität zu Berlin, Deutsches Museum
gerd.grasshoff@hu-berlin.de

2026-09-24

ABSTRACT

Famulus Notebook is a document form for scholarly questions put to a research system. A notebook is ordinary text with executable *blocks*. A block states its scope and its plan in a short preamble and asks its question in ordinary language; running it leaves a result, the declared artefacts, and a *verdict* that compares the result with an expectation determined independently of the run. Notebooks live in *projects*; every artefact has a *reference name*, a version and a checksum, so that one block can build on another, in the same project, in another project, or on another machine, and a project can be brought up to date by re-running exactly what has become stale. This book teaches the whole cycle in the manner of a language manual: a first notebook in the first chapter, one extension per chapter after that, and a complete reference manual at the end. The reader learns to write and run blocks, to read and check their results, to name and version artefacts, to annotate and revise the text with a Lektor, to work with coauthors and commentators across machines, and to publish a notebook with its generated artefacts as HTML and PDF. Every example is a block of a companion project that was run for this book; its source and its result are printed side by side, and its reference name lets the reader open the same block in the viewer. A casebook of six research projects (Pirckheimer, Schöner, Kepler twice, Kármán, and an LWgrammar check of a damaged paper) shows the notebook at work, including the disagreements it made visible. Boxes marked “For famuli” state the exact grammar and the machine consequence of each rule for the second audience of the book: the software agents that read and write notebooks themselves. Appendices give the reference manual, the command line, the HTTP interface, the setup of a second machine, a measured baseline of the query pipeline, the collected rules for famuli, and solutions to all exercises.

KEYWORDS Famulus · notebook · literate computing · reproducible research · oracle · versioned artefacts · annotation · scholarly publishing · digital humanities · PDAI

Table of contents

Preface	5
0.1 Two audiences	5
0.2 Conventions	6
0.3 What you need	6
Part I · Getting started	7
1 A first notebook	7
1.1 A question and a block	7
1.2 Running it	8
1.3 Reading the result	8
1.4 Unchecked is not passed	9
1.5 A second block	10
1.6 The file and its project	10
2 The block	11
2.1 Fence, preamble, instruction	11
2.2 The groups of keys	11
2.3 Placeholders	13

2.4 Two forms of plan	13
2.5 Errors before the run	14
3 Results and their display	15
3.1 Artefact kinds and display forms	15
3.2 A table	16
3.3 Key figures	16
3.4 A grouped table	17
3.5 A network	18
3.6 Evidence and text	19
3.7 Overriding the display	20
3.8 Results in prose	21
4 Checking an answer	21
4.1 An oracle	21
4.2 The four verdicts	22
4.3 A golden	23
4.4 Following a disagreement	24
4.5 Counter-checks	25
Part II · Carrying on	27
5 Projects and chapters	27
5.1 The parts of a project	27
5.2 The settings file	28
5.3 Which setting wins	28
5.4 The integrating notebook	29
5.5 Making a project	29
5.6 Old packages	30
6 Names and references	31
6.1 The full name	31
6.2 Short forms	31
6.3 Short names	32
6.4 Reading another project	32
6.5 Choosing a version	33
6.6 Renaming a block	34
6.7 Names on other machines	35
6.8 When a reference does not resolve	35
7 Versions and smart refresh	36
7.1 The header of an artefact	36
7.2 When a version is made	37
7.3 The four states	39
7.4 Following and staying	39
7.5 Refresh	40
7.6 The lock	41
8 Scope and data	42
8.1 Collections and years	42
8.2 Data files	43
8.3 Two languages in one collection	43
8.4 What identifies a sentence	44
8.5 Counting lemmata	44
Part III · Working with others	46
9 Editing and annotating	46
9.1 The viewer	46
9.2 Choosing a paragraph	47

9.3 Writing an instruction	48
9.4 The review card	48
9.5 The formulation check	49
9.6 A second round	50
9.7 Deciding	50
9.8 What reaches the file	51
10 Refining and correcting	52
10.1 What a run did	52
10.2 Correcting a block	54
10.3 Running a block again	54
10.4 Telling the next run	54
10.5 From a correction to a rule	57
11 Coauthors and readers	57
11.1 Owner and commentator	57
11.2 Peers	58
11.3 Tokens	59
11.4 Three ways to use a peer	60
11.5 Two machines at work	61
Part IV · Publishing	62
12 From notebook to publication	62
12.1 One source, a shadow copy	62
12.2 Rendering	64
12.3 The site	64
12.4 Citing a result	65
12.5 How this book was made	65
12.6 Handing on a project	65
13 A casebook of six projects	67
13.1 Pirckheimer's correspondents	67
13.2 Schöner and the <i>saphea</i>	69
13.3 Kepler: <i>lex</i> and <i>natura</i>	70
13.4 Kepler: from <i>anima</i> to <i>vis</i>	72
13.5 Kármán's correspondence and manuscripts	74
13.6 Checking the checker: LWgrammar on a damaged paper	76
13.7 What the six projects show	78
Part V · Beneath the surface	79
14 How a block is executed	79
14.1 From a project to its blocks	79
14.2 Whether a block runs	79
14.3 Where a block runs	80
14.4 What a block executes	81
14.5 The harness and the order of binding	81
14.6 Judging and writing	82
15 When something goes wrong	83
15.1 Where a message appears	83
15.2 Projects, notebooks and files	84
15.3 The preamble	85
15.4 References and dependencies	85
15.5 Reading data	86
15.6 Peers and remote runs	86
15.7 The engine and the Partitur	87
15.8 The formulation guard	87

15.9 The server	88
16 Design decisions, related work, limits	88
16.1 A declared preamble instead of code	88
16.2 A store beside the notebook	89
16.3 Versions by content, not by run	89
16.4 No kernel	89
16.5 Peers instead of copies	89
16.6 A token in a file, passed once	89
16.7 A pass without oracle is not a pass	89
16.8 Related work	90
16.9 Limits	90
16.10 Open gaps	90
Appendices	91
Appendix A: Reference manual	91
A.1 Files of a project	91
A.2 A notebook	92
A.3 The project file	92
A.4 The preamble	93
A.5 Rules the runner enforces	94
A.6 The lock	95
A.7 The store	95
A.8 The envelope	95
A.9 Peers	96
A.10 The grammar of references	96
A.11 Environment variables	97
Appendix B: The command line	97
Installing	97
Running	98
Checking	98
Projects	98
Building	99
Peers	99
Serving	99
Appendix C: The HTTP interface	99
C.1 Admission	99
C.2 Notebooks and projects	100
C.3 State and running	100
C.4 Artefacts by reference	100
C.5 Collections	100
C.6 Running a block for a peer	101
C.7 Neighbours	101
Appendix D: Setting up a second machine	101
D.1 The machine that serves	101
D.2 The machine that calls	102
D.3 The checks before the first run	102
D.4 The test notebook	103
D.5 What the test found	103
Appendix E: A baseline of the query pipeline	104
What the numbers say	105
How the baseline is repeated	105
Appendix F: For famuli	106

F.1 Rules of conduct	106
F.2 Verdicts	106
F.3 The preamble	106
F.4 Reading data	107
F.5 Results and versions	107
F.6 References	107
F.7 Annotation	107
F.8 Rendering and running	107
Appendix G: Solutions to the exercises	108
Chapter 1	108
Chapter 2	108
Chapter 3	108
Chapter 4	109
Chapter 5	109
Chapter 6	109
Chapter 7	110
Chapter 8	110
Chapter 9	110
Chapter 10	110
Chapter 11	110
Chapter 12	111
Chapter 13	111
Chapter 14	111
Chapter 15	111
Index	112
Bibliography	114

■ Preface

A question put to a research system has three parts that belong together: the question, the answer, and the grounds on which the answer can be accepted. In a chat window only the first two survive, and only until the window is closed. Famulus Notebook keeps all three in one document. The document is ordinary text with embedded questions; each question carries its own scope and plan and, where one is known, the answer expected of it. Running the document writes, beside it, what every question produced and how that product compares with the expectation. The document can be read like an article, run again like a program, handed on like a folder, and published like a paper.

This book teaches that document form from the first block to the published project. It follows the plan of Leslie Lamport's manual for LaTeX [**citation gap**: the bibliographic entry for Lamport's LaTeX manual is not yet in the bibliography and awaits the author's confirmation]: it begins with a complete small example, adds one feature per chapter, shows every feature at work in an example, and ends with a reference manual in which each rule is stated once and completely. The reader who works through Part I can write and run a notebook and read its results. Part II adds what a longer piece of work needs: projects with chapters, names for results, versions, and refreshing what has become stale. Part III is about other people: annotating a text, revising it with a Lektor, and working with coauthors, commentators and other machines. Part IV turns a notebook into a publication and presents six research projects as a casebook. Part V explains what happens beneath the surface, lists the messages a reader may meet when something goes wrong, and states the design decisions and the limits of the system.

■ 0.1 Two audiences

The book is written for two kinds of reader. The first is a scholar, an editor or a student who wants to put questions to an edited corpus, keep the answers with their grounds, and publish them. No programming is

assumed beyond reading a short SQL statement, and even that is optional: most questions can be asked in ordinary language.

The second kind of reader is a *famulus*, a software agent that reads and writes notebooks itself. A famulus needs what a human reader does without: the exact grammar of a reference, the file in which a result is kept, the consequence of each rule for what a machine is allowed to do. This information stands in boxes marked **For famuli**. A human reader may skip them. Appendix F collects them in one place.

0.2 Conventions

Every example in this book is a block of the companion project `lehrbuch`, or of one of the six case projects, and every example was run for this book. An example is printed as a pair: the source of the block on the left (or above), the result that the run produced on the right (or below). The caption gives the *reference name* of the block, the version of its result, and the verdict. The reference name is the address under which you open the same block in the viewer, run it again, or use it in another block; Chapter 6 explains it. A preamble key that an example leaves out to save space is shown as `key: ...`; the full text is in the project.

```
SOURCE
```{famulus}

id: first-count
display: kennzahl
duckdb: ...
partiturs:
 - id: duckdb-read
 input:
 sql: |
 WITH l AS (
 SELECT CASE WHEN sender_id =
 'ent_pirckheimer'
 THEN recipient_id ELSE
 sender_id END AS
 partner,
 TRY_CAST(left(date_when, 4) AS
 INTEGER) AS year
 FROM letters_resolved
)
 SELECT count(DISTINCT partner) AS
 n_correspondents,
 count(*) AS n_letters
 FROM l
 WHERE year BETWEEN 1520 AND 1530
 artefacts: ...

How many correspondents did Pirckheimer have
between 1520 and 1530, and how many letters do
they share?
```
```

RESULT

77 n_correspondents
354 n_letters

Example P.1. fam:lehrbuch/ch01/first-count · v1 · unchecked

The viewer of Famulus Notebook speaks German, and so do the messages of the command line. The book quotes them as they appear and translates them at first use. The notebooks of the companion project are written in English; some case projects are German.

At the end of each chapter a box **In short** repeats what the chapter taught, and a set of exercises follows. Solutions are in Appendix G. Numbers in the text come from the runs of the projects on 23 and 24 September 2026; where a number was checked against the register of a collection, the text says so.

0.3 What you need

To read the book you need nothing. To run its examples you need an installation of Famulus Notebook (Appendix B lists the commands), the companion project, and access to the PDAI collections that the examples read; the Pirckheimer, Kepler and Kármán collections are enough for Parts I and II. Blocks that play a Partitur of the query pipeline also need the agent orchestrator and ai-query; blocks that read a database directly do not.

PART I

Getting started

1 A first notebook

This chapter walks through one small notebook from the question to the verdict. It introduces the words that the rest of the book uses, but defines none of them completely; that is the work of the following chapters.

1.1 A question and a block

Willibald Pirckheimer, the Nuremberg humanist, left a large correspondence. Its edition is a PDAI collection: page images, text, and a register of letters, the table `letters_resolved`, in which every letter is one row with its sender, its recipient and its date. Sender and recipient are not names but *entity ids* such as `ent_pirckheimer`; a second table, `ent_canonical`, gives each id its canonical name. Every letter in the register has Pirckheimer on one side; the other side is his correspondent.

Suppose you want to know how many correspondents Pirckheimer had between 1520 and 1530, and how many letters they share. In a notebook you write the question as a block:

```
SOURCE
```{famulus}

id: first-count
display: kennzahl
duckdb:
 - alias: main
 path:
 $PDAI_COLLECTIONS/pirckheimer/
 pirckheimer.duckdb
 read_only: true
partiturs:
 - id: duckdb-read
 input:
 sql: |
 WITH l AS (
 SELECT CASE WHEN sender_id =
 'ent_pirckheimer'
 THEN recipient_id ELSE
 sender_id END AS
 partner,
 TRY_CAST(left(date_when, 4) AS
 INTEGER) AS year
 FROM letters_resolved
)
 SELECT count(DISTINCT partner) AS
 n_correspondents,
 count(*) AS n_letters
 FROM l
 WHERE year BETWEEN 1520 AND 1530
artefacts:
 - name: count
 kind: table
 file: count.json

How many correspondents did Pirckheimer have
between 1520 and 1530, and how many letters do
they share?
```
```

RESULT

77 n_correspondents
354 n_letters

Example 1.1. fam:lehrbuch/ch01/first-count · v1 · unchecked

The block begins with a line ````{famulus}` and ends with a line `````. Between the two lines `---` stands the preamble, a short list of keys and values in YAML. After the second `---` comes the instruction: the question in ordinary language.

The preamble of this block says four things.

- `id: first-count` names the block. Every block of a notebook has a name of its own, and the name is how everything else refers to it.
- `duckdb` attaches the register database of the Pirckheimer collection, read-only. `$PDAI_COLLECTIONS` stands for the folder in which the collections lie on this machine.
- `partiturs` is the *plan*: here a single step, `duckdb-read`, which runs one SQL statement against the attached database.
- `artefacts` declares what the run is to keep: one artefact named `count`, a table, in the file `count.json`.
- `display: kennzahl` asks for the result to be shown as figures (*Kennzahl* is German for a key figure). Chapter 3 lists the other display forms.

The instruction is not decoration. It says what the block is for, it appears as the title of the result, and when a block asks a question through the query pipeline instead of through SQL (Chapter 2), the instruction is what the pipeline answers.

1.2 Running it

You run a notebook from the command line or from the viewer. On the command line, `famulus-notebook run` takes a notebook file or a project folder:

Specimen · The first run of a block, forced

```
$ famulus-notebook run kapitel/ch01.fam --block first-count --force
How many correspondents did Pirckheimer have between 1520 and 1530, – wartet
How many correspondents did Pirckheimer have between 1520 and 1530, – läuft
How many correspondents did Pirckheimer have between 1520 and 1530, – ohne Oracle, v1
unverändert
{"blocks": {"first-count": "pass"}}
```

Each line is one event: the block is waiting (*wartet*), it runs (*läuft*), it has finished. The last event says two things. *Ohne Oracle*, “without oracle”, means that nothing was there to compare the result with; we return to this in a moment. *v1 unverändert*, “v1 unchanged”, means that this run produced the same result as the previous one, so the result keeps its version number 1. The option `--force` made the block run although nothing had changed. Without it, the command takes the result over from the last run:

Specimen · The same command without `--force`

```
$ famulus-notebook run kapitel/ch01.fam
How many correspondents did Pirckheimer have between 1520 and 1530, – wartet
List Pirckheimer's correspondents between 1520 and 1530 with the number... – wartet
How many correspondents did Pirckheimer have between 1520 and 1530, – aus dem letzten
Lauf
List Pirckheimer's correspondents between 1520 and 1530 with the number... – aus dem
letzten Lauf
{"blocks": {"first-count": "pass", "first-list": "pass"}}
```

Aus dem letzten Lauf, “from the last run”, is the normal case. A block runs again only when something it depends on has changed: its preamble, its instruction, a file it reads, or the result of a block it builds on. Chapter 7 explains how the notebook finds out.

1.3 Reading the result

The run wrote the result into the folder `_famulus` of the project, which belongs to the runner; you never edit it by hand. For the block `first-count` it now contains:

Specimen · What a run leaves behind (ch01)

```
_famulus/store/ch01/first-count/current.json
_famulus/store/ch01/first-count/v0001/artefacts/count.json
_famulus/store/ch01/first-count/v0001/manifest.json
_famulus/store/ch01/first-count/v0001/report.json
_famulus/store/ch01/first-count/v0001/result.json
_famulus/store/ch01/first-count/v0001/verdict.json
```

`v0001` is the folder of version 1; `current.json` says which version is the current one. The four files have four tasks. The manifest records the run: when it started, the hash of its inputs, how often the block has run (`runs`), and the artefacts it wrote. The verdict (`verdict.json`) records what was observed and how it compares with the expectation. The result (`result.json`) is what the viewer shows: the question, a one-sentence answer, the measured values, and the display form. The report keeps what the plan returned. The artefact itself, `count.json`, holds the table the SQL statement produced, wrapped in a header that names where it came from; Chapter 7 shows that header.

In the viewer the same result looks like this:

The screenshot shows the Famulus Notebook viewer interface. On the left is a sidebar with a list of chapters. The main content area displays two blocks: 'first-count' and 'first-list'. Each block shows its state (aktuell), version (v1), a question, a result, and two buttons: 'Neu ausführen' and 'Anmerken'.

Block 1: first-count

How many people wrote to or from Pirckheimer?

The register `letters_resolved` of the Pirckheimer edition lists one letter per row, with the sender and the recipient as entity ids. Every letter has Pirckheimer on one side. The other side is his correspondent.

aktuell v1

How many correspondents did Pirckheimer have between 1520 and 1530, and how many letters do they share?

Partitur

77 Briefpartner, 354 Briefe.

ohne Oracle

| | Zahl |
|-----------------|------------|
| 77 Briefpartner | 354 Briefe |

Neu ausführen Anmerken

Diagnose

Block 2: first-list

Who were they?

aktuell v1

List Pirckheimer's correspondents between 1520 and 1530 with the number of letters each shares with him, the most frequent first.

Partitur

ohne Oracle

| Name | Zahl |
|---|------|
| Donatuswörth, Bürgermeister und Rat von | 127 |
| Erasmus, Desiderius | 21 |
| Pirckheimer, Klara | 20 |
| (unbekannt) | 19 |
| Schöner, Johann | 11 |
| Pirckheimer, Sabina | 10 |

Figure 1 The block `first-count` and the list `first-list` in the viewer. Each block shows its state chip (*aktuell*, current), its version (`v1`), the instruction, a collapsed Partitur, the result, and two buttons.

The viewer is started with `famulus-notebook serve` and listens on port 5118; the address of this chapter is `http://127.0.0.1:5118/notebook?nb=lehrbuch/ch01`. The left column lists the notebooks, the middle column shows the chosen notebook, and the right edge holds the annotation panel of Part III. A block in the viewer shows only what the next step needs: the state and version, the question, the result, and two buttons, *Neu ausführen* (“run again”) and *Anmerken* (“add a note”). The preamble is folded away under *Partitur*, the diagnostics under *Diagnose*.

1.4 Unchecked is not passed

Look again at the event `ohne Oracle`. The command line reports the block as `pass`, but the result says `"urteil": "unchecked"`. This is deliberate. The run passed in the sense that it did what it was asked: it read the register and returned a non-empty table. Whether 77 is the right number, the run cannot know, because nobody told it what to expect. An expected value that was determined independently of the run is called an

oracle. A block without an oracle is unchecked, and the viewer says so with the chip *ohne Oracle* in place of *bestanden* (“passed”). Chapter 4 adds an oracle to this very question and shows what happens when the oracle and the register disagree.

</> For famuli

verdict.json field status is one of pass, fail, gap, error. result.json field urteil equals status, except that status: pass with an empty or missing oracle becomes urteil: unchecked. A famulus reporting a result must report urteil, not status: a block with urteil: unchecked has not been checked, and saying “passed” of it is false.

1.5 A second block

A notebook usually asks more than one question, and later questions build on earlier ones. The second block of the chapter lists the correspondents:

```
SOURCE
```{famulus}

id: first-list
depends_on: [first-count]
display: tabelle
duckdb: ...
partiturs:
 - id: duckdb-read
 input:
 sql: |
 WITH l AS (
 SELECT CASE WHEN sender_id =
 'ent_pirckheimer'
 THEN recipient_id ELSE
 sender_id END AS
 partner,
 TRY_CAST(left(date_when, 4) AS
 INTEGER) AS year
 FROM letters_resolved
)
 SELECT e.canonical AS name, count(*) AS
 count
 FROM l JOIN ent_canonical AS e ON
 e.ent_id = l.partner
 WHERE year BETWEEN 1520 AND 1530
 GROUP BY e.canonical
 ORDER BY count DESC, name
 artefacts: ...

List Pirckheimer's correspondents between 1520
and 1530 with the number of letters each shares
with him, the most frequent first.
```
```

RESULT

| name | count |
|---------------------------------------|-------|
| Donauwörth, Bürgermeister und Rat von | 127 |
| Erasmus, Desiderius | 21 |
| Pirckheimer, Klara | 20 |
| (unbekannt) | 19 |
| Schöner, Johann | 11 |
| Pirckheimer, Sabina | 10 |
| Grieninger, Johann | 9 |
| Pirckheimer, Katharina d. J. | 9 |

... 69 more rows

Example 1.2. fam:lehrbuch/ch01/first-list · v1 · unchecked

The key `depends_on: [first-count]` says that this block comes after `first-count`. The table shows the first eight of 77 rows. The list is worth reading closely. Its fourth line is a correspondent called “(unbekannt)”, unknown, with 19 letters. We shall meet it again in Chapter 4, where it explains a disagreement.

1.6 The file and its project

The two blocks live in a file `kapitel/ch01.fam`. A `.fam` file is a Quarto document: a YAML header, prose in Markdown, and blocks. It belongs to a project, a folder with a file `famulus.yml` that names the project and the settings its notebooks share. The companion project of this book has the id `lehrbuch`; its chapter notebooks are `ch01`, `ch02`, and so on. The complete name of the first block is therefore `fam:lehrbuch/ch01/first-count`, and the complete name of its artefact is `fam:lehrbuch/ch01/first-count.count`. Chapter 5 is about projects, Chapter 6 about names.

In short

- A notebook is a text with blocks. A block has a preamble (keys between two `---` lines) and an instruction (the question).
- `famulus-notebook run` executes the blocks; a block whose inputs have not changed is taken over from the last run.
- A run leaves a result, a verdict, a manifest and the declared artefacts in `_famulus/store/<notebook>/<block>/v<N>/`.
- A result without an oracle is *unchecked* (*ohne Oracle*), never *passed*.

✎ Exercise 1.1

Change the years in `first-count` to 1522–1524 and run the notebook. Which of the two blocks gets a new version, and why does the other one not? (Chapter 7 gives the full answer; guess it now.)

✎ Exercise 1.2

Add `LIMIT 10` to the SQL statement of `first-list`. What does the viewer show, and what does the table in `partners.json` contain?

✎ Exercise 1.3

Open `result.json` of `first-count` and name the key that says the result is unchecked. Which key would change if the block had an oracle?

2 The block

Chapter 1 showed a block at work. This chapter takes it apart: the fence that marks it, the keys of its preamble and the groups they fall into, the two forms of plan, and the placeholders by which an instruction names an earlier result.

2.1 Fence, preamble, instruction

A block is a fenced code block whose language is `famulus`:

```
```{famulus}

id: my-block
...more keys...

The question, in ordinary language.
```
```

Everything between the two lines `---` is the preamble; it must be a YAML mapping. Everything after the second `---` is the instruction. A notebook may contain any number of blocks, with prose between them. Prose is for the human reader; the runner ignores it. The runner reads only the blocks, in the order in which they stand in the file, and sorts them further by their dependencies.

The preamble obeys one rule above all others, the rule of completeness: a block reads no context that neither its preamble nor the defaults of its project name. There is no current collection of a window, no earlier question of a chat that silently narrows the next one. If a block reads Kepler, its preamble or its project says so.

2.2 The groups of keys

Every preamble key belongs to one of eight groups. The following block uses a key from nearly every group:

```

SOURCE
```{famulus}

id: anatomy
depends_on: [ch01/first-list]
rerun: if-stale
collections: [pirckheimer]
years: {from: 1520, to: 1530}
display: tabelle
duckdb:
 - alias: main
 path:
 $PDAI_COLLECTIONS/pirckheimer/
 pirckheimer.duckdb
 read_only: true
partiturs:
 - id: duckdb-read
 input:
 sql: |
 SELECT r.name, r.count
 FROM
 read_json_auto('{{ref:ch01/first-
list.partners}}')
 AS f,
 unnest(f.data.data.rows) AS t(r)
 WHERE r.count >= 10
 ORDER BY r.count DESC, r.name
artefacts:
 - name: frequent
 kind: table
 file: frequent.json

From the list in
{{ref:ch01/first-list.partners}}, keep the
correspondents with at least ten letters.
```

```

RESULT

| name | count |
|---------------------------------------|-------|
| Donauwörth, Bürgermeister und Rat von | 127 |
| Erasmus, Desiderius | 21 |
| Pirckheimer, Klara | 20 |
| (unbekannt) | 19 |
| Schöner, Johann | 11 |
| Pirckheimer, Sabina | 10 |

Example 2.1. fam:lehrbuch/ch02/anatomy · v1 · unchecked

Read it group by group.

Identity

`id` names the block; it must be unique in the notebook.

Order

`depends_on` lists blocks that must run first, here a block of another chapter notebook, `ch01/first-list`. `rerun` says when the block runs again: `if-stale` (the default) when something it depends on has changed, always on every run, `never` only if it has no result yet. The older spelling `if-missing` means the same as `if-stale`.

Scope

`collections` names the collections the block may read, `years` a range of years. Further scope keys are `locked`, `reading_doc`, `evidence`, `language`, `persons`, `lemmata` and `counting_mode`; Chapter 8 treats them.

Data

`duckdb` attaches databases, each under an `alias`, read-only.

Plan

`partiturs` (a chain of steps) or `subtask` (a question for the query pipeline); exactly one of the two.

Artefacts

`artefacts` declares the files the run keeps, each with a `name`, a `kind` and a `file`.

Display

`display` chooses how the result is shown (Chapter 3).

Checking

`oracle` states the expected result, `golden` names the golden it was taken from (Chapter 4), `guard` asks for a formulation check (Chapter 10).

A key that the preamble does not set is taken from the defaults of the project, if the project sets it. A list in the preamble replaces the list of the defaults; the two are not joined.

</> For famuli

Precedence for every scope key: block preamble, then `defaults` in `famulus.yml`, then nothing. There is no fourth source; in particular no key is inferred from the instruction. The instruction becomes `goal`, `inputs.instruction` and `inputs.raw_query` of the run request; `years` becomes `inputs.year_from`, `inputs.year_to` and `inputs.years`.

2.3 Placeholders

The instruction and the SQL of `anatomy` both contain the text `{ref:ch01/first-list.partners}`. This is a placeholder: a reference to the artefact `partners` of the block `first-list` in the notebook `ch01`. Before the plan is played, the runner replaces every placeholder, in the SQL and in the instruction it hands to the plan, by the path of the artefact file, so that `read_json_auto` can open it. The question shown with the result keeps the reference as text, so the reader still sees where the input comes from.

A placeholder makes the block depend on the artefact. When `first-list` produces a new version of `partners`, `anatomy` becomes stale and runs again at the next refresh. A placeholder that cannot be resolved is an error of the block, never an empty input. The full grammar of references, with versions and names across projects, is the subject of Chapter 6.

Artefact files are JSON with a header and a payload (Chapter 7). A table's rows lie at `data.data.rows` of the file, which is why the SQL reads `unnest(f.data.data.rows)`.

2.4 Two forms of plan

A block carries exactly one of two keys that name its plan.

The first form, `partiturs`, is a chain of steps. Each step has an `id`, and optionally an `input` and a `setting`. An `id` is either the name of a Partitur in the register of plans, or one of two local steps that Famulus Notebook performs itself:

- `duckdb-read` runs one read-only SQL statement against the databases named under `duckdb` and returns the rows;
- `artifact:<kind>` builds an artefact of the given kind, for example a network from a list (Chapter 3).

The chain stops at the first step that does not reach its goal. The later steps do not run, and the result names the gap. Local steps need neither a language model nor the agent orchestrator; they are what the first four chapters mostly use, because their results can be checked line by line.

The second form, `subtask`, sends the question to the query pipeline of the Famulus platform, the Partitur `ai-query-phase1`. The instruction becomes the goal of that Partitur, and the subtask names the kind of question:

SOURCE

```
```{famulus}

id: subtask-count
years: {from: 1520, to: 1530}
subtask: correspondence-count
golden: golden-c782fab71c
display: kennzahl
oracle:
 n_correspondents: 75
duckdb: ...
artefacts:
 - name: report
 kind: report
 file: report.json

How many correspondents did Pirckheimer have
between 1520 and 1530? Count distinct persons
in letters_resolved, resolved through
ent_canonical.
```
```

RESULT

75

n_correspondents

expected = 75

Example 2.2. fam:lehrbuch/ch02/subtask-count · v1 · passed

This is the same question as `first-count`, asked the other way. The block names the subtask `correspondence-count` and an oracle of 75 correspondents, taken from a golden (Chapter 4). The pipeline’s answer, 75, matches, and the verdict is *passed*. That the register reading of Chapter 1 gave 77 is not a contradiction in the notebook; it is a finding, and Chapter 4 resolves it.

The subtasks the pipeline accepts are listed in Appendix A. A subtask block needs the agent orchestrator and ai-query on the machine that runs it; a chain of local steps does not.

</> For famuli

```
subtask values accepted: correspondence-count, correspondence-roster, letter-subject,
mention-in-letters, terminology-find, concept-statements, statement-mention,
source-attestation, sentence-mention, cooccurrence, manuscript-inventory, register-inventory,
entity-mention-count. Any other value is refused before the run with unbekannter subtask '<value>'.
```

2.5 Errors before the run

Some mistakes are found before anything runs. The runner checks every block first and refuses it with a message that names the cause:

Table 1 Messages before a run. The messages are German; *genau eines von* means “exactly one of”, *fehlt* “is missing”.

| The preamble ... | The message says |
|--|---|
| has no id | Präambel ohne id |
| has both subtask and partiturs, or neither | <id>: genau eines von subtask und partiturs |
| names a subtask the pipeline does not know | <id>: unbekannter subtask '<name>' |
| counts lemmata without counting_mode | <id>: counting_mode fehlt bei der Lemma-Zählung |

A refused block has the verdict `error`, writes no artefact, and blocks that depend on it wait. Chapter 15 lists every message the runner can give.

In short

- A block is a `{famulus}` fence with a YAML preamble and an instruction.
- The preamble is complete: nothing outside it and the project defaults shapes the run.
- Keys fall into eight groups: identity, order, scope, data, plan, artefacts, display, checking.
- `{ref:...}` names an earlier artefact and makes the block depend on it.
- The plan is either a chain of `partiturs` (local steps or registered Partituren) or one `subtask` of the query pipeline.

Exercise 2.1

Name the group of each key in `subtask-count`.

Exercise 2.2

Write a block that counts Pirckheimer's letters of the year 1522 only, with a `duckdb-read` step. Which keys can you leave out if the project defaults already name the collection?

Exercise 2.3

A block has a preamble without `id`. What does the runner report, and what happens to a block that names it in `depends_on`?

3 Results and their display

A run produces data; the viewer and the published page show it. Between the two stands the display: a short specification in `result.json` that says in which form the data are shown. This chapter introduces the seven display forms, the defaults that choose one of them, and the keys that override the choice. It ends with the shortcode that puts a result into running prose.

3.1 Artefact kinds and display forms

What a run keeps is declared under `artefacts`, each with a kind. The kind says what the data are: a table, a list of persons, a list of passages, a network, a report, a text. The display says how they are shown. Every kind has a default form:

Table 2 Default display by kind of artefact.

| Kind of artefact | Default display |
|--|--|
| <code>table</code> | <code>tabelle</code> , a table |
| <code>report</code> | <code>kennzahl</code> , key figures |
| <code>roster-table</code> | <code>liste</code> , or <code>tabelle</code> beyond 12 rows, or <code>hierarchische-tabelle</code> if the rows fall into several kinds |
| <code>kwic</code> , <code>citation-list</code> | <code>belegliste</code> , a list of passages with their places |
| <code>markdown</code> , <code>timeline</code> | <code>textkarten</code> , text cards |
| <code>d3-graph</code> | <code>netz</code> , a network |

The display forms carry German names because the viewer is German: *Kennzahl* (key figure), *Liste* (list), *Tabelle* (table), *hierarchische Tabelle* (grouped table), *Belegliste* (list of evidence), *Textkarten* (text cards) and *Netz* (network). The rest of this chapter shows each at work.

3.2 A table

The simplest display is a table of rows and columns, as a SQL statement returns them:

```
SOURCE
```{famulus}

id: letters-by-year
display: tabelle
duckdb: ...
partiturs:
- id: duckdb-read
 input:
 sql: |
 SELECT TRY_CAST(left(date_when, 4) AS INTEGER) AS year,
 count(*) AS letters,
 count(*) FILTER (WHERE direction = 'X_to_P') AS to_pirckheimer,
 count(*) FILTER (WHERE direction = 'P_to_X') AS from_pirckheimer
 FROM letters_resolved
 GROUP BY year
 ORDER BY year
artefacts: ...

How many letters does the register date to each year, and in which direction did
they travel?
```
```

RESULT

| year | letters | to_pirckheimer | from_pirckheimer |
|------|---------|----------------|------------------|
| 1520 | 1 | 0 | 1 |
| 1522 | 13 | 7 | 6 |
| 1523 | 29 | 22 | 7 |
| 1524 | 89 | 82 | 7 |
| 1525 | 105 | 95 | 10 |
| 1526 | 59 | 54 | 5 |
| 1527 | 58 | 49 | 9 |

Example 3.1. fam:lehrbuch/ch03/letters-by-year · v1 · unchecked

The register dates letters from 1520 to 1527 only; no letter falls into 1521 or into 1528–1530. The reason is recorded with the golden of Chapter 4: the register was built from volumes 5 and 6 of the edition, and volume 7 is not yet in the corpus. The table shows at most twelve rows unless the display says otherwise (zeilen_sichtbar, “rows visible”); the viewer offers the rest behind a button.

3.3 Key figures

A result of one row is a set of figures. Each numeric column of the row is shown as a figure, and an oracle can check each of them (Chapter 4):

```

SOURCE
```{famulus}

id: peak-year
depends_on: [letters-by-year]
display: kennzahl
partiturs:
- id: duckdb-read
 input:
 sql: |
 SELECT r.year AS peak_year, r.letters
 AS peak_letters
 FROM
 read_json_auto('{{ref:letters-by-
 year.years}}')
 AS f,
 unnest(f.data.data.rows) AS t(r)
 ORDER BY r.letters DESC
 LIMIT 1
artefacts: ...

Which year has the most letters in
{{ref:letters-by-year.years}}?
```

```

RESULT

1525 peak_year
105 peak_letters

Example 3.2. fam:lehrbuch/ch03/peak-year · v1 · unchecked

The block reads the table of the previous block through a placeholder and asks for its largest row. The year 1525 has 105 letters. The labels under the figures are the column names, `peak_year` and `peak_letters`; a column named `n_correspondents` or `n_letters` gets a German label (*Briefpartner, Briefe*) from a short list of known names.

3.4 A grouped table

When rows fall into groups, a grouped table shows each group under its own heading. The display names the column that forms the groups (*gruppe*) and the columns to show (*spalten*), each with a label and, for numbers, `art: zahl` (“kind: number”), which aligns them to the right:

```

SOURCE
```{famulus}

id: places
display:
 format: hierarchische-tabelle
 gruppe: kind
 spalten:
 - {feld: name, label: Place}
 - {feld: count, label: Letters, art: zahl}
 zeilen_sichtbar: 12
duckdb: ...
partiturs:
- id: duckdb-read
 input:
 sql: |
 SELECT CASE direction WHEN 'X_to_P' THEN 'to Pirkheimer'
 ELSE 'from Pirkheimer' END AS kind,
 coalesce(place, 'unknown') AS name,
 count(*) AS count
 FROM letters_resolved
 GROUP BY kind, name
 HAVING count(*) >= 5
 ORDER BY kind, count DESC
artefacts: ...

From which places were letters written, grouped by the direction of the letter?
Places with fewer than five letters are left out.
```

```

RESULT

from Pirkheimer

| Place | Letters |
|----------|---------|
| Nürnberg | 44 |

to Pirkheimer

| Place | Letters |
|----------------|---------|
| Nürnberg | 69 |
| Kloster | 45 |
| Basel | 26 |
| Herford | 14 |
| Augsburg | 12 |
| Kirchehrenbach | 11 |
| Leipzig | 10 |
| Bamberg | 9 |
| Straßburg | 9 |
| Wien | 7 |
| Innsbruck | 7 |
| Stuttgart | 5 |
| Eichstätt | 5 |

Example 3.3. fam:lehrbuch/ch03/places · v3 · unchecked

Only one place, Nürnberg, has five or more letters *from* Pirckheimer in the register; the letters *to* him come from eight places above that threshold. The asymmetry is a fact about the register: by the table of letters-by-year it holds 309 letters to Pirckheimer and 45 from him.

3.5 A network

A local step `artifact:<kind>` turns an earlier artefact into a new one. The following block draws the correspondents of the Pirckheimer project as a star, reading the roster of another project through its short name `pirck` (Chapter 6 explains short names):

```
SOURCE
```{famulus}

id: star
display: netz
partiturs:
- id: artifact:d3-graph
 input:
 center: Pirckheimer
 roster:
 ref: pirck/briefpartner-roster.roster
 artefact: star
artefacts:
- name: star
 kind: d3-graph
 file: star.json

Draw Pirckheimer's correspondents from
{{ref:pirck/briefpartner-roster.roster}} as a
star. Pirckheimer stands in the centre; the
weight of an edge is the number of letters.
```
```

RESULT

A graph of 61 nodes and 60 edges.

60 von 75 Briefpartnern. Stern um Pirckheimer. Die Kantenstärke ist die Briefzahl. 60 Briefpartner.

Example 3.4. fam:lehrbuch/ch03/star · v2 · unchecked




Figure 2 The network of `star` in the viewer: Pirckheimer in the centre, one node per correspondent, the edge weight given by the number of letters.

The answer of the block states that it draws 60 of 75 correspondents. The builder of the star keeps the first 60 rows of its input and says so in its note; nothing is dropped silently.

3.6 Evidence and text

Passages from a corpus are shown as a list of evidence: each row a sentence with its place, the document, page and sentence number.

```
SOURCE
```{famulus}

id: kepler-evidence
collections: [kepler-prim]
display: belegliste
partiturs:
 - id: duckdb-read
 input:
 sql: |
 SELECT r.doc_id, r.pidx, r.sent_idx, r.text
 FROM read_json_auto('{{ref:kepler/lex-natura-gegenprobe:gegenprobe}}') AS f,
 unnest(f.data.data.rows) AS t(r)
 ORDER BY r.doc_id, r.pidx, r.sent_idx
 LIMIT 3
 artefacts:
 - name: evidence
 kind: kwic
 file: evidence.json

Show the first three Latin sentences in which Kepler uses lex and natura together,
from {{ref:kepler/lex-natura-gegenprobe:gegenprobe}}.
```
```

RESULT

kgw-01 · 190 · 0

illam facio, quàm par est; nec si primi authores legem quandam suis ratiocinijs arbitrarijs à rerum natura sunt mutuati, propterea vicissim tota reliqua coelestium natura sese subiecit his eorum ratiocinijs; ut hortulanus ad quinarium numerum floribus familia...

kgw-01 · 263 · 4

Qui hoc affirmant, pars naturae coelorum consulentes, lege circulari hoc factum esse pronunciant: ut ita causa sit, cur ex descensu, nexus, et quodammodo prognatus fuerit contrarius ascensus.

kgw-01 · 288 · 6

Moderator itaque totius naturae non in hoc Solem et Lunam ciet, ut deliquium jungat aequinoctio; sed ne Solem Lunamque non cieat, suà quemlibet lege: non refugit deliquium jungere aequinoctio.

Example 3.5. `fam:lehrbuch/ch03/kepler-evidence · v1 · unchecked`

The block reads the sentences of the Kepler counter-check, a block of the Kepler project, and keeps the first three. The place `kgw-01 · 190 · 0` is document `kgw-01`, page index 190, sentence 0 of that page.

Text cards are for prose that a plan wrote, for example the synthesis of a question about the subject of letters. The Schöner project asks what Johann Schöner's letters to Pirckheimer are about:

```
SOURCE
```{famulus}

id: schoener-gegenstand
years: {from: 1520, to: 1527}
subtask: letter-subject
golden: golden-b4544be016
display: textkarten
guard: {task: synthesize-answer, lang: de}
oracle:
 n_letters: 11
 subject_contains: saphea
duckdb: ...
artefacts:
 - name: gegenstand
 kind: markdown
 file: gegenstand.md

Was ist der Gegenstand der Briefe von Schöner an Pirckheimer zwischen 1520 und 1527?
Gib eine zusammenhängende Darstellung und die Briefzahl.
```
```

RESULT

These correspondence excerpts primarily feature letters from Schöner to an influential patron and magistrate (addressed as “herrlichkeit,” and identified elsewhere as Willibald Pirckheimer), alongside related monastic and personal communications. A central topic is Schöner’s ongoing pursuit of a church benefice permutation involving Heroldsberg, Erenpach, and Bamberg, accompanied by expressions of anxiety over bureaucratic delays, gossip, and negotiations with local peasants and collators. Schöner also frequently discusses the acquisition, casting, and correction of astronomical and mathematical instrument matrices—specifically concerning a device called a “saphea” and work with Johann Stüchs—as well as the dispatch of related treatises (*canones cylindri* and *Canones Sapheae*). In addition, the letters touch upon scholarly praise for Pirckheimer’s translation of Ptolemy and his civic virtue, personal financial or living arrangements, and concerns regarding religious and monastic hardships during the period, including the plight of nuns at St. Clare and local weather damage to crops.

Example 3.6. `fam:schoener-saphea/saphea/schoener-gegenstand · v1 · passed`

The answer is prose written by the query pipeline; its first two cards are shown here. The block passes because its oracle asks for two things, eleven letters and the word *saphea* in the answer, and the run supplies both.

3.7 Overriding the display

The key `display` accepts either the name of a form or a mapping:

```
display: liste # a form by name
display: # or a mapping
  format: hierarchische-tabelle
  gruppe: kind # column that forms the groups
  spalten: # columns shown, in order
    - {feld: name, label: Place}
    - {feld: count, label: Letters, art: zahl}
  sortierung: {feld: count, richtung: ab} # sort by count, descending
  zeilen_sichtbar: 12 # rows shown before "more"
```

A key given in the mapping replaces the default; keys not given keep it. `richtung` is `auf` (ascending) or `ab` (descending).

</> For famuli

`result.json.display` is always a mapping with at least `format`. Valid formats: `kennzahl`, `liste`, `tabelle`, `hierarchische-tabelle`, `belegliste`, `textkarten`, `netz`. Rows are read from `data.entries` or `data.rows` of the artefact payload. For `kennzahl`, `result.json.messwerte` lists one entry per figure with `name`, `label`, `beobachtet` (observed) and `erwartet` (expected; empty when no oracle names the figure).

3.8 Results in prose

A published notebook often wants a result in the middle of a paragraph or after it, not only in the block. The shortcode `famulus` does this in any page of the Quarto site:

The register dates the letters as follows:

```
{{< famulus letters-by-year.years >}}
```

The shortcode takes a reference to an artefact (Chapter 6) and inserts it: a table as a table, a text as text. The reference is resolved when the site is built (Chapter 12), so the page always shows the version that the build found; a reference that cannot be resolved is printed as a visible message, never as an empty place.

In short

- An artefact has a kind; a result has a display form. Each kind has a default form.
- Seven forms: `Kennzahl`, `Liste`, `Tabelle`, `hierarchische Tabelle`, `Belegliste`, `Textkarten`, `Netz`.
- `display` overrides the form, the columns, the grouping, the sorting and the number of rows.
- `{{< famulus <ref> >}}` puts a result into prose.

✍ Exercise 3.1

Show `ch01/first-list` as a `liste` with the columns `name` and `count`, labelled “Correspondent” and “Letters”. What happens to the row limit?

✍ Exercise 3.2

Change the display of `places` so that the groups are the places and the rows the two directions. Which column must the SQL return for that?

✍ Exercise 3.3

Write a paragraph for a Quarto page that names the busiest year and inserts the table of `letters-by-year` after it.

4 Checking an answer

A result that nobody checked is a claim. This chapter adds the check: an oracle in the preamble, the rule by which the run’s result is compared with it, and the four words in which the comparison is reported. It then follows one disagreement, between a register count and a golden, to its cause.

4.1 An oracle

An oracle is an expected result, stated in the preamble, that was determined independently of the run: counted by hand, taken from a published register, or fixed in a golden. The block of Chapter 1 gets one:

SOURCE

```{famulus}

---

id: count-checked

display: kennzahl

oracle:

n\_correspondents: 77

n\_letters: {min: 350}

duckdb: ...

partiturs:

- id: duckdb-read

input:

sql: |

WITH l AS (

SELECT CASE WHEN sender\_id =

'ent\_pirckheimer'

THEN recipient\_id ELSE

sender\_id END AS

partner,

TRY\_CAST(left(date\_when, 4) AS

INTEGER) AS year

FROM letters\_resolved

)

SELECT count(DISTINCT partner) AS

n\_correspondents,

count(\*) AS n\_letters

FROM l

WHERE year BETWEEN 1520 AND 1530

artefacts: ...

---

Count Pirckheimer's correspondents and letters

between 1520 and 1530 and check both figures

against the register.

RESULT

77 n\_correspondents

354 n\_letters

Example 4.1. fam:lehrbuch/ch04/count-checked · v1 · passed

The oracle states two expectations. `n_correspondents: 77` is an equality; `n_letters: {min: 350}` is a range with a lower bound only. Each is compared with the value of the same name that the run observed, here the two columns of the one-row table. Both hold, and the verdict is *passed* (*bestanden*). The figures show the expectation beside the observation, so the reader sees what was checked.

An oracle may take four forms:

Table 3 The four forms of an oracle.

| Form      | Example                                                                                                               | Holds when                                             |
|-----------|-----------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------|
| number    | <code>n_correspondents: 77</code>                                                                                     | the observed value equals it                           |
| range     | <code>n_letters: {min: 350},</code><br><code>          {max: 20},</code><br><code>          {min: 10, max: 20}</code> | the observed value lies in the range                   |
| substring | <code>subject_contains: saphea</code>                                                                                 | the observed value of that name contains the string    |
| list      | <code>terms: [saphea, horologium]</code>                                                                              | every item is found in the observed value of that name |

4.2 The four verdicts

Every run ends with one of four verdicts, and the viewer shows a fifth word for the case that Chapter 1 introduced:

**Table 4** Verdicts.

| Status in verdict.json             | Viewer                         | Meaning                                                                      |
|------------------------------------|--------------------------------|------------------------------------------------------------------------------|
| <code>pass</code> , with oracle    | <i>bestanden</i> (passed)      | every expectation of the oracle holds                                        |
| <code>pass</code> , without oracle | <i>ohne Oracle</i> (unchecked) | the run returned a non-empty result; nothing was there to compare it with    |
| <code>fail</code>                  | <i>abweichend</i> (deviates)   | at least one expectation does not hold                                       |
| <code>gap</code>                   | <i>Lücke</i> (gap)             | the question cannot be answered with the available data, and the run says so |
| <code>error</code>                 | <i>Fehler</i> (error)          | the run was aborted; the diagnostics name the reason                         |

Two rules make these words trustworthy. First, an unchecked result never reads as passed, as Chapter 1 showed. Second, an empty result is never a pass: a run that returns nothing where something was asked for ends as an error (“silent empty result”), not as an unchecked success. A pass on an empty artefact is a bug of the notebook. One such bug is open: a `duckdb-read` without an oracle that returns no rows still ends as *ohne Oracle*, because its result carries the names of the columns and a row count of 0, and these count as something observed (Chapter 15). Until it is closed, give every reading an oracle with a lower bound, such as `n_sentences: {min: 1}`.

#### ⟨⟩ For famuli

A `fail` writes no artefact files; the manifest’s `artefacts` list is empty, and a block that reads the artefact through a placeholder waits (*hängt an <ref>, dort liegt noch keine Version*, “depends on, which has no version yet”). A `gap` is an answer, not an error: it states that the data cannot answer the question. Do not retry a `gap` with a different model; retry an `error` only after the cause named in `verdict.json` is removed.

### 4.3 A golden

A golden is a question of the query pipeline with a known answer, kept in the pipeline’s agent memory, table `golden_ground`, and used to test the pipeline [1]. The key `golden` of a block names the golden its oracle was taken from; it does not load anything. The golden `golden-c782fab71c` asks: “How many correspondents did Pirckheimer have between 1520 and 1530?” and expects `n_unique_correspondents: 75`. Its record carries a note: the register was built from volumes 5 and 6 of the edition, about 1520–1527, and the golden is a *candidate* that awaits inspection by the author.

Chapter 2 asked the pipeline this question through the subtask `correspondence-count`, and the pipeline answered 75: *passed*. Chapter 1 counted the register and found 77. Put the golden’s number on the register reading, and the verdict turns:

```

SOURCE
```{famulus}
---
id: count-golden
display: kennzahl
golden: golden-c782fab71c
oracle:
  n_correspondents: 75
duckdb: ...
partiturs:
  - id: duckdb-read
    input:
      sql: |
        WITH l AS (
          SELECT CASE WHEN sender_id =
            'ent_pirckheimer'
              THEN recipient_id ELSE
              sender_id END AS
              partner,
              TRY_CAST(left(date_when, 4) AS
              INTEGER) AS year
          FROM letters_resolved
        )
        SELECT count(DISTINCT partner) AS
          n_correspondents
        FROM l
        WHERE year BETWEEN 1520 AND 1530
    artefacts: ...
  ---
  Count Pirckheimer's correspondents between 1520
  and 1530 and compare the figure with the
  expectation of golden-c782fab71c.
  ```

```

## RESULT

**77** n\_correspondents expected = 75

**Example 4.2.** fam:lehrbuch/ch04/count-golden · v1 · deviates

The screenshot shows the Famulus Notebook interface. On the left is a sidebar with a table of contents. The main content area displays Chapter 4: Checking an answer. It includes an oracle that the register confirms, a diagnostic section, and a section where the golden's figure is checked against the same reading. The right sidebar contains a vertical list of items.

**Table of Contents (Left Sidebar):**

| Item                                                              |
|-------------------------------------------------------------------|
| Käsmän: Korrespondenz und Manuskripte                             |
| Kepler: von der anima motrix zur vis motrix                       |
| Kepler: lex und natura                                            |
| Famulus Notebook: the examples of the book                        |
| Chapter 1: A first notebook                                       |
| Chapter 2: The block                                              |
| Chapter 3: Results and their display                              |
| Chapter 4: Checking an answer                                     |
| Chapter 6: Names and references                                   |
| Chapter 7: Versions and smart refresh                             |
| Chapter 8: Scope and data                                         |
| LWigrammar: die Formulierungsprüfung am Aufsatz famulus-plattform |
| Pirckheimers Briefpartner 1520-1530                               |
| Schönen: Saphia und Sonnenuhr                                     |
| Goldens                                                           |
| Journal                                                           |
| Neue Frage                                                        |
| Lernen                                                            |

**Main Content Area:**

**Chapter 4: Checking an answer**

An oracle that the register confirms

Count Pirckheimer's correspondents and letters between 1520 and 1530 and check both figures against the register.

Partitur

77 Briefpartner, 354 Briefe.

77 354

Briefpartner erwartet = 77 Briefe erwartet mindestens 350

Neu ausführen Anmerken

Diagnose

**The golden's figure, checked against the same reading**

Count Pirckheimer's correspondents between 1520 and 1530 and compare the figure with the expectation of golden-c782fab71c.

Partitur

77 Briefpartner.

77

Briefpartner erwartet = 75

Neu ausführen Anmerken

Diagnose

**Where the two come from**

The list of Chapter 1 contains a partner called "(unbekannt)". The register keeps two placeholder ids for letters whose correspondent the edition does not name. This block

**Figure 3** Chapter 4 in the viewer: the same register reading passes against the oracle 77 and deviates against the golden's 75.

## 4.4 Following a disagreement

A notebook does not settle a disagreement; it makes it visible and keeps the evidence together. Here the evidence is already on the page. The list of Chapter 1 has a correspondent "(unbekannt)" with 19 letters. The register uses placeholder ids for letters whose correspondent the edition does not name, and a count of distinct ids counts each placeholder as a person. One more block counts again without them:

SOURCE

```{famulus}

id: count-named
display: kennzahl
golden: golden-c782fab71c
oracle:
 n_correspondents: 75
duckdb: ...
partiturs:
 - id: duckdb-read
 input:
 sql: |
 WITH l AS (
 SELECT CASE WHEN sender_id =
 'ent_pirckheimer'
 THEN recipient_id ELSE
 sender_id END AS
 partner,
 TRY_CAST(left(date_when, 4) AS
 INTEGER) AS year
 FROM letters_resolved
)
 SELECT count(DISTINCT partner) AS
 n_correspondents,
 count(*) AS n_letters
 FROM l
 WHERE year BETWEEN 1520 AND 1530
 AND partner NOT LIKE 'ent_unbekannt%'
 artefacts: ...

Count the named correspondents between 1520 and
1530, leaving out the register's placeholder
ids for unnamed correspondents.
```

RESULT

75 n\_correspondents
334 n\_letters

Example 4.3. fam:lehrbuch/ch04/count-named · v1 · passed

Without the two placeholder ids, `ent_unbekannt_2` (19 letters) and `ent_unbekannt` (1 letter), there are 75 named correspondents with 334 letters, and the golden’s figure holds. The difference of two is explained. One figure is still open. The pipeline’s report for the same question says 200 letters, while the register holds 334 letters with named correspondents and 354 in all. The notebook records the three numbers; which reading the pipeline’s 200 corresponds to is not established here. Chapter 13 returns to it and finds that 200 is a limit on rows, not a count.

Specimen · Three readings of one question

Reading	Correspondents	Letters	Block
all partner ids	77	354	fam:lehrbuch/ch04/count-checked
named partners only	75	334	fam:lehrbuch/ch04/count-named
query pipeline	75	200	fam:lehrbuch/ch02/subtask-count

4.5 Counter-checks

The block `count-named` is a counter-check: a second reading of the same data by a different route, designed to confirm or refute a first one. A good counter-check changes one thing at a time. Here it changed the treatment of placeholder ids and nothing else, which is why its result can be read as the explanation of the difference.

The case projects of Chapter 13 use counter-checks throughout. The Kepler project, for example, counts sentences with *lex* and *natura* both through the query pipeline and directly in the lemma index, and reports both.

The last block of the chapter is a small counter-check of a different kind. It lists the correspondents whose ids begin with Pirckheimer’s own, to see whether family members are kept apart from him:

```

SOURCE
```{famulus}
---
id: family
display: tabelle
duckdb: ...
partiturs:
  - id: duckdb-read
    input:
      sql: |
        WITH l AS (
          SELECT CASE WHEN sender_id =
            'ent_pirckheimer'
              THEN recipient_id ELSE
              sender_id END AS
              partner
            FROM letters_resolved
          )
          SELECT e.canonical AS name, l.partner
            AS ent_id, count(*) AS count
          FROM l JOIN ent_canonical AS e ON
            e.ent_id = l.partner
          WHERE l.partner LIKE
            'ent_pirckheimer_%'
          GROUP BY e.canonical, l.partner
          ORDER BY count(*) DESC
    artefacts: ...
---
Which correspondents carry an entity id that
begins with Pirckheimer's own?
```

```

## RESULT

| name                            | ent_id                        | count |
|---------------------------------|-------------------------------|-------|
| Pirckheimer, Klara              | ent_pirckheimer_klara         | 20    |
| Pirckheimer, Sabina             | ent_pirckheimer_sabina        | 10    |
| Pirckheimer,<br>Katharina d. J. | ent_pirckheimer_katharina_d_j | 6     |
| Pirckheimer, Caritas d. J.      | ent_pirckheimer_caritas_d_j   | 6     |
| Pirckheimer, Eufemia            | ent_pirckheimer_eufemia       | 2     |

**Example 4.4.** fam:lehrbuch/ch04/family · v1 · unchecked

They are: five members of the family have ids of their own. None of them is counted as Pirckheimer.

#### In short

- An oracle states an expectation found independently of the run: a number, a range, a substring, or a list.
- Verdicts: passed, unchecked (without oracle), deviates, gap, error. An empty result is an error, never a pass.
- A golden is a question with a known answer; golden: names its source.
- When two readings disagree, a counter-check that changes one thing explains the difference or shows that it is not yet explained.

#### ✍ Exercise 4.1

Give `first-list` an oracle that checks that the list has at least 70 rows and names Erasmus. Which forms of oracle do you need?

#### ✍ Exercise 4.2

Why does `count-golden` write no artefact, and what happens to a block that reads `{ref:count-golden.count}`?

#### ✍ Exercise 4.3

Design a counter-check for the pipeline's 200 letters. What would you change, and what would each possible result tell you?

---

## PART II

# Carrying on

---

## 5 Projects and chapters

One notebook is enough for one question. A study needs several: a chapter on the correspondents, one on places, one on the evidence for a term. Famulus Notebook binds notebooks into a project, the way a LaTeX document binds its chapters in `main.tex`. This chapter shows the parts of a project and how to make one.

### 5.1 The parts of a project

The companion project of this book is a folder with one settings file, one integrating notebook, a folder of chapter notebooks, a lock and a runtime folder:

#### Specimen · The companion project

```
$ find lehrbuch -maxdepth 2 | sort
lehrbuch
lehrbuch/_famulus
lehrbuch/_famulus/store
lehrbuch/famulus.lock
lehrbuch/famulus.yml
lehrbuch/kapitel
lehrbuch/kapitel/ch01.fam
lehrbuch/kapitel/ch02.fam
lehrbuch/kapitel/ch03.fam
lehrbuch/kapitel/ch04.fam
lehrbuch/kapitel/ch06.fam
lehrbuch/kapitel/ch07.fam
lehrbuch/kapitel/ch08.fam
lehrbuch/lehrbuch.fam
```

Each part has one job:

#### **famulus.yml**

The settings of the project: its id and title, defaults for every notebook, short names for other projects, and renamed blocks.

#### **.fam files**

The notebooks. A `.fam` file is a Quarto document in Markdown with `{famulus}` blocks; the extension tells editors and the runner what it is. Notebooks lie in the project folder itself or in `kapitel/`.

#### **lehrbuch.fam**

The integrating notebook: the notebook that lists the chapters.

#### **kapitel/ch01.fam ... ch08.fam**

The chapter notebooks. Chapter 5 of this book has no blocks, so there is no `ch05.fam`.

#### **famulus.lock**

The record of which result was made from which (Chapter 7). The runner writes it; you read it.

**\_famulus/**

The runner's folder: the store of results, one folder per notebook, and the build copies of Chapter 12. Quarto skips folders whose names begin with an underscore, so a Quarto website of the project does not publish it by accident.

You write `famulus.yml` and the `.fam` files. Everything else is written by the runner.

## 5.2 The settings file

### Specimen · `famulus.yml` of the companion project

```
id: lehrbuch
title: 'Famulus Notebook: the examples of the book'
main: lehrbuch
defaults:
 collections: [pirckheimer]
 client: gemini-3.5-flash-lite
 evidence: grounding
 duckdb_root: $PDAI_COLLECTIONS
imports:
 pirck: fam:pirckheimer-briefwechsel/briefpartner-1520-1530
 kepler: fam:kepler-lex-naturae/lex-naturae
 karman: fam:karman-nachlass/korrespondenz
moved:
 ch03/kepler-cards: ch03/kepler-evidence
```

**id**

The project id, the first part of every reference name in the project. It consists of lower-case letters, digits and hyphens and begins with a letter. The id is declared, not derived from the folder name: the folder may be renamed or copied to another machine, and every reference to the project stays valid.

**title**

What the viewer shows in its list of notebooks.

**main**

The integrating notebook, by file name without extension. Without `main`, the first notebook in the project folder that lists chapters is taken.

**defaults**

Settings that every notebook of the project inherits. Here: the collection `pirckheimer`, the language model the query pipeline uses (`client`), the evidence mode of the pipeline, and the root folder of the corpus files.

**imports**

Short names for notebooks of other projects. With `pirck`, a block writes `pirck/briefpartner-roster.roster` instead of the full name `fam:pirckheimer-briefwechsel/briefpartner-1520-1530/briefpartner-roster.roster`. Chapter 6 explains names and short forms.

**moved**

Old names of renamed blocks or notebooks, each with its new name. Chapter 6 shows the rename of this example at work.

## 5.3 Which setting wins

A setting can be stated in three places: in the project's `defaults`, in the front matter of a notebook under `famulus:`, and in the preamble of a block. The nearer statement wins:

1. the block's preamble,
2. the notebook's `famulus:` values,
3. the project's `defaults`.

Chapter 3 of the companion project, for example, inherits the collection `pirckheimer` from `famulus.yml`; its block `kepler-evidence` states `collections: [kepler-prim]` and reads Kepler instead. The rule has one refinement: `id`, `uses` and `chapters` in a notebook's front matter are properties of that notebook and are never inherited.

#### ⌘ For famuli

The settings of a notebook are `project.defaults` updated with the notebook's own `famulus:` mapping minus the keys `id`, `uses` and `chapters`. For a subtask, the keys `language`, `persons`, `lemmata`, `counting_mode`, `evidence`, `reading_doc`, `person_id`, `project`, `terms` and `locked` are taken from the preamble if present, else from these settings. `years` is read from the preamble only. `client` is read from the settings only. Inside the orchestrator, explicit input then wins over a setting file, and a setting file over the Partitur's default.

## 5.4 The integrating notebook

The integrating notebook names the chapters in its front matter, in the order in which they are read:

### Specimen · Front matter of `lehrbuch.fam`

```

title: "Famulus Notebook: the examples of the book"
subtitle: "One chapter notebook for every chapter of the book that has examples"
famulus:
 id: lehrbuch
 chapters:
 - kapitel/ch01.fam
 - kapitel/ch02.fam
 - kapitel/ch03.fam
 - kapitel/ch04.fam
 - kapitel/ch06.fam
 - kapitel/ch07.fam
 - kapitel/ch08.fam

```

The list fixes the order in which the viewer shows the notebooks and in which `famulus-notebook` status reports them: first the integrating notebook, then the chapters as listed, then any other notebook of the folder. The integrating notebook may have blocks of its own. In the companion project it holds only the text that introduces the project.

A notebook's own `id` is declared in its front matter (`famulus: id: ch06`); the file name is only a fallback. The notebook key is the project `id` and the notebook `id` joined by a slash, `lehrbuch/ch06`. It is the address of the notebook across projects and the second part of every reference name.

## 5.5 Making a project

`famulus-notebook project new` makes a project folder with a settings file and one empty notebook, and enters the project in the project register:

**Specimen · A new project**

```
$ famulus-notebook project new briefe --id briefe --title "Letters of 1522"
Projekt briefe in /private/tmp/briefe; Notebook briefe.fam
eingetragen in /tmp/fam-reg.yaml

$ find briefe -type f
briefe/briefe.fam
briefe/famulus.yml

$ cat briefe/famulus.yml
id: briefe
title: Letters of 1522
defaults:
 duckdb_root: $PDAI_COLLECTIONS

$ cat briefe/briefe.fam

title: "Letters of 1522"
famulus:
 id: briefe

```

The register is a list of project ids and folders. It lets the viewer and the runner find a project that lies outside the folders they search anyway, and it lets a block of one project read a result of another by its id. The register normally is `~/.config/famulus/projects.yaml`; the environment variable `FAMULUS_PROJECTS` names another file. The transcript above was made with a scratch register in `/tmp`, so the real register stayed untouched.

Projects under `site/projekte/` and `site/beispiele/` of the Famulus Notebook installation, and under the folders named in the environment variable `FAMULUS_NOTEBOOKS`, are found without registration. A project anywhere else is entered with

```
famulus-notebook project register <folder>
```

**5.6 Old packages**

Before projects, a notebook was a *package*: a folder with `notebook.qmd`, a settings file `_famulus.yml` and a result folder `log/`. Packages still load, so an old package is readable at once. The command

```
famulus-notebook project migrate <package> --to <folder> --id <project> --notebook <id>
```

turns it into a project. It writes `famulus.yml` from `_famulus.yml`, renames `notebook.qmd` to `<notebook>.fam`, moves every result into the store as version 1, wraps each artefact in its header (Chapter 7) and compares the content's checksum with the one the old package recorded. A mismatch is reported, never hidden. A block whose recorded input still matches its text stays current; every other block is marked stale. The old folder is removed only after every file has been copied, and `--keep` keeps it anyway. The six case projects of Chapter 13 were migrated this way.

**In short**

- A project is a folder with `famulus.yml` and one or more `.fam` notebooks, in the folder itself or in `kapitel/`.
- The integrating notebook lists the chapters under `famulus: chapters`.
- Settings: block preamble before notebook `famulus:` before project `defaults`.
- Project id and notebook id are declared; `lehrbuch/ch06` is a notebook key.
- `project new` makes a project, `project register` enters one, `project migrate` converts an old package.

**Exercise 5.1**

Make a project `briefe` with an integrating notebook and two chapter notebooks, `kapitel/a.fam` and `kapitel/b.fam`. Which file lists the chapters, and in which order does `famulus-notebook status briefe` report the notebooks?

**Exercise 5.2**

The project's `defaults` say `collections: [pirckheimer]`, the notebook's front matter says `famulus: collections: [karman-nachlass]`, and a block says nothing about collections. Which collection does the block read? And if the block says `collections: [kepler-prim]`?

## 6 Names and references

A result that another block, another project or a published page uses needs a name that stays valid. This chapter gives the grammar of these names, the short forms a notebook may use, the four ways of choosing a version, and what happens when a block is renamed.

### 6.1 The full name

Every block and every artefact has a reference name. Its full form has four parts and an optional selector:

```
fam:<project>/<notebook>/<block>.<artefact>[@<selector>]
```

For the count of Chapter 1:

```
fam:lehrbuch/ch01/first-count.count
```

`fam:` marks a full name. `lehrbuch` is the project id from `famulus.yml`, `ch01` the notebook id from the notebook's front matter, `first-count` the block id and `count` the artefact name from the block's `artefacts` list. A block as a whole, without an artefact, is named `fam:lehrbuch/ch01/first-count`; that is the form that `depends_on` uses.

None of the four parts is a file path. The name survives when the project folder is moved, when the `.fam` file is renamed, and when the project is copied to another machine, because all four parts are declared in the files themselves.

### 6.2 Short forms

Inside a notebook, most references are short. A short form is completed from the notebook in which it stands:

**Table 5** Short forms of a reference and what they complete to.

| You write                                        | It means                                                       |
|--------------------------------------------------|----------------------------------------------------------------|
| <code>first-count.count</code>                   | the block <code>first-count</code> in this notebook            |
| <code>ch01/first-count.count</code>              | the notebook <code>ch01</code> in this project                 |
| <code>pirck/briefpartner-roster.roster</code>    | the notebook that the short name <code>pirck</code> stands for |
| <code>fam:lehrbuch/ch01/first-count.count</code> | exactly this, from anywhere                                    |

A name with one slash is ambiguous in principle: `ch01/...` could be a notebook of this project or a short name. The rule is that a short name wins. If the notebook has no short name `ch01`, the name is read as a notebook of the same project.

### 6.3 Short names

A short name (alias) is declared in one of two places. `imports` in `famulus.yml` holds for every notebook of the project; `uses` in a notebook's front matter holds for that notebook and wins over `imports`. The companion project imports three case projects; Chapter 6 of it adds one short name of its own:

#### Specimen · Front matter of `kapitel/ch06.fam`

```

title: "Chapter 6: Names and references"
famulus:
 id: ch06
 uses:
 manuscripts: fam:karman-nachlass/korrespondenz@v1

```

A short name may carry a selector, like `manuscripts` here. The selector then applies to every reference through that short name that does not state its own. A short name may also name a project without a notebook, `fam:schoener-saphea`; it then stands for the integrating notebook of that project, or for its only notebook.

### 6.4 Reading another project

The first block of Chapter 6 counts the rows of the Kepler counter-check in another project, through the imported short name `kepler`:

SOURCE

```{famulus}

id: from-kepler
collections: [kepler-prim]
display: kennzahl
partiturs:
- id: duckdb-read
 input:
 sql: |
 SELECT count(*) AS n_sentences,
 count(DISTINCT r.doc_id) AS
 n_documents
 FROM
 read_json_auto('{{ref:kepler/lex-natura-
gegenprobe.gegenprobe}}')
 AS f,
 unnest(f.data.data.rows) AS t(r)
artefacts: ...

How many sentences and documents does the
Kepler counter-check in
{{ref:kepler/lex-natura-gegenprobe.gegenprobe}}
contain?
```

RESULT

44 n\_sentences
16 n\_documents

Example 6.1. fam:lehrbuch/ch06/from-kepler · v1 · unchecked

The counter-check has 44 sentences in 16 documents. The reference has no selector, so it reads the current version and the block will run again when the counter-check gets a new one.

6.5 Choosing a version

Every run that changes a result makes a new version of it, and old versions are kept (Chapter 7). A selector after @ chooses among them:

Table 6 Selectors.

Selector	Chooses	Use it when
@latest (or none)	the current version	the block shall follow the result
@v3	version 3	the block shall keep reading what it read
@sha:3e891ae0	the version whose content has this checksum	a publication cites exactly one content
@locked	the version recorded in famulus.lock	the project shall reproduce its last complete state

A pinned name reads one version and nothing else. The Kármán roster, read at version 1 by its full name:

```

SOURCE
```{famulus}
---
id: from-karman
display: kennzahl
partiturs:
  - id: duckdb-read
    input:
      sql: |
        SELECT count(*) AS n_entries,
               sum(e.count) AS n_letters
        FROM
          read_json_auto('{{ref:fam:karman-
nachlass/korrespondenz/karman-roster.roster@v1}}')
          AS f,
          unnest(f.data.data.entries) AS
            t(e)
artefacts: ...
---
How many correspondents and letters does
version 1 of the Kármán roster list?
```

```

RESULT

**746** n\_entries  
**2447** n\_letters

**Example 6.2.** fam:lehrbuch/ch06/from-karman · v1 · unchecked

The same effect through the short name `manuscripts`, which carries `@v1`:

```

SOURCE
```{famulus}
---
id: via-alias
display: kennzahl
partiturs:
  - id: duckdb-read
    input:
      sql: |
        SELECT count(*) AS n_items
        FROM
          read_json_auto('{{ref:manuscripts/
manuskripte.bestand}}')
          AS f,
          unnest(f.data.data.entries) AS
            t(e)
artefacts: ...
---
How many items does the manuscript inventory
{{ref:manuscripts/manuskripte.bestand}} list?
```

```

RESULT

**191** n\_items

**Example 6.3.** fam:lehrbuch/ch06/via-alias · v1 · unchecked

The roster lists 746 correspondents with 2,447 letters; the manuscript inventory lists 191 items. Neither figure will change when the Kármán project runs again, until someone changes the selector.

#### ⌘ For famuli

A selector matches `latest`, `locked`, `v<digits>` or `sha:<4–64 hex>`; anything else is refused with `unbekannte Version @<x>` (`latest`, `vN`, `sha:...`, `locked`). `@locked` falls back to the current version when the lock has no entry for the name. `@sha:` is refused with `keine Version mit sha:<x>` when no version has that checksum. A short name's selector applies only when the reference itself says `@latest` or nothing. The full grammar is given in Appendix A.

## 6.6 Renaming a block

A block that other blocks, other projects or published pages use should keep its name. When a rename is needed anyway, the old name goes under `moved` in `famulus.yml`, with the new name as its value:

```

moved:
 ch03/kepler-cards: ch03/kepler-evidence

```

A reference under the old name then resolves to the new block. The block `old-name` still says `ch03/kepler-cards.evidence`:

```

SOURCE
```{famulus}
---
id: old-name
collections: [kepler-prim]
display: kennzahl
partiturs:
- id: duckdb-read
  input:
    sql: |
      SELECT count(*) AS n_sentences
      FROM
        read_json_auto('{{ref:ch03/kepler-
cards.evidence}}')
      AS f,
        unnest(f.data.data.rows) AS t(r)
artefacts: ...
---
How many sentences does
{{ref:ch03/kepler-cards.evidence}} hold?
```

```

RESULT

**3** n\_sentences

**Example 6.4.** fam:lehrbuch/ch06/old-name · v1 · unchecked

It reads the three sentences of Chapter 3. The old name works, but it should not stay, and the coherence check says so:

#### Specimen · The coherence check finds the old name

```

$ famulus-notebook check site/projekte/lehrbuch --ohne-termini
Urteil lehrbuch/ch04 · count-golden fail: n_correspondents: got 77, expected 75
Verweis lehrbuch/ch06 · old-name ref ch03/kepler-cards.evidence: ch03/kepler-cards
heißt jetzt fam:lehrbuch/ch03/kepler-evidence.evidence (moved)
8 Notebooks geprüft: 2 Befunde

```

The second finding says that `ch03/kepler-cards` “is now called” (*heißt jetzt*) `fam:lehrbuch/ch03/kepler-evidence.evidence`. The first finding is the intended disagreement of Chapter 4. `--ohne-termini` leaves out the check of terms against LWgrammar (Chapter 10). An entry of `moved` may also rename a whole notebook: `ch03: kapitel3` sends every reference into `ch03` to the notebook `kapitel3`.

## 6.7 Names on other machines

A result on another machine is named by putting the machine’s peer name in front:

```
peer:<peer>/fam:<project>/<notebook>/<block>.<artefact>
```

Chapter 11 shows how a peer is declared and what it offers. The name of the result is the same on both machines; only the prefix says where to fetch it.

## 6.8 When a reference does not resolve

A reference that cannot be read or found stops the block before anything runs. The messages name the reference as written:

**Table 7** Messages for references.

| Message                                                                  | Cause                                                                         |
|--------------------------------------------------------------------------|-------------------------------------------------------------------------------|
| Verweis nicht lesbar: <ref>                                              | the name breaks the grammar                                                   |
| <ref>: Artefaktnamen fehlt<br>(<block>.<artefakt>)                       | a placeholder names a block without an artefact                               |
| <ref>: fam:-Verweis braucht <projekt>/<br><notebook>/<block>.<artefakt>  | a full name with too few parts                                                |
| unbekanntes Projekt <id> (famulus-notebook<br>project register <ordner>) | the project is not found                                                      |
| Projekt <id>: kein Notebook <nb>                                         | the notebook is not in the project                                            |
| Projekt <id> hat <n> Notebooks; uses muss<br><projekt>/<notebook> nennen | a short name names a project with several<br>notebooks and no integrating one |

A reference that resolves to a block without any version is not an error at reading time. The block that uses it waits: `hängt an <ref>, dort liegt noch keine Version.`

**In short**

- Full name: `fam:<projekt>/<notebook>/<block>.<artefakt>`; a block alone omits `.<artefakt>`.
- Short forms are completed from the notebook: same notebook, same project, or a short name from `imports` or `uses`.
- Selectors: `@latest`, `@vN`, `@sha:...`, `@locked`.
- `moved` keeps an old name readable; `check` reports every use of it.
- `peer:<peer>/` in front names the same result on another machine.

**Exercise 6.1**

Write the full names of `first-count.count` as used in `ch02.fam`, of `ch01/first-list.partners` as used in `ch04.fam`, and of `pirck/briefpartner-roster.roster` as used anywhere in the companion project.

**Exercise 6.2**

The block `star` of Chapter 3 draws from `pirck/briefpartner-roster.roster`. Pin it to the version it read. Which selector do you use if you know the version number, and which if you want the version recorded in the lock?

**Exercise 6.3**

Rename the block `letters-by-year` of Chapter 3 to `year-table` without breaking `peak-year`, which reads it, or any page that cites it. What do you change, and what does `famulus-notebook` check report afterwards?

## 7 Versions and smart refresh

Notebooks change. A year range is corrected, a query is sharpened, a register gets a new volume. This chapter explains what the runner keeps when a block runs again, how it decides what must run, and how a reader of a result chooses between following it and staying with what it read.

### 7.1 The header of an artefact

Every artefact file in the store begins with a header, the envelope, that says what the file is and where it came from. The data follow under `data`:

**Specimen · The artefact `span.json` of `ch07/span`, version 2 (data shortened)**

```
{
 "famulus": {
 "ref": "fam:lehrbuch/ch07/span.span",
 "version": 2,
 "sha256": "f9c788f58ae171d848f9db40c9f969df74be20c8e6d7232ae86a5c380a146387",
 "created": "2026-09-23T20:41:23+00:00",
 "produced_by": {
 "notebook": "Lehrbuch/ch07",
 "block": "span",
 "input_hash": "d4f411f233f9811e",
 "partitur": "duckdb-read",
 "model": ""
 },
 "derived_from": []
 },
 "data": {
 "artifact_type": "table",
 "data": { "columns": ["n_letters"], "rows": [{"n_letters": 354}], ... }
 }
}
```

**ref**

The artefact's full name, including the artefact name.

**version, sha256**

The version number and the checksum of the content under `data`.

**created**

When this content was first made.

**produced\_by**

The notebook and block, the hash of the input that produced the content, the Partitur that ran, and the language model it used. A local step such as `duckdb-read` uses no model, so `model` is empty.

**derived\_from**

The artefacts, with version and checksum, that the block read. `span` reads none; `follows` below reads `span` at version 2.

A file that carries its own name and origin can be copied, mailed or published without losing what it is. A reader that finds the file on its own still knows which block made it, from what, and with which model.

**7.2 When a version is made**

A run makes a new version only when the content changes. The content is that of the declared artefacts: their data are compared, checksum against checksum, with those of the current version. A block that declares no artefact has nothing to compare, and every run replaces its one version; declare an artefact for every result that should keep a history. The same holds after a failed run, which writes no artefact (Chapter 4): the next run that passes writes into the version the failure left. The block `span` counts the letters dated between 1520 and 1530:

```

SOURCE
```{famulus}
---
id: span
display: kennzahl
duckdb: ...
partiturs:
- id: duckdb-read
  input:
    sql: |
      -- letters with a year in the
      register's date field
      -- (the register dates letters by
      date_when)
      SELECT count(*) AS n_letters
      FROM letters_resolved
      WHERE TRY_CAST(left(date_when, 4) AS
        INTEGER) BETWEEN 1520 AND 1530
artefacts: ...
---
How many letters does the register date between
1520 and 1530?
```

```

RESULT

**354** n\_letters

**Example 7.1.** fam:lehrbuch/ch07/span · v2 · unchecked

Its history has two versions. Version 1 counted the years 1520 to 1524 and found 132 letters; the range was then widened to 1530, and version 2 found 354. The store keeps both:

```

_famulus/store/ch07/span/current.json
_famulus/store/ch07/span/v0001/...
_famulus/store/ch07/span/v0002/...

```

The file `current.json` says which version is current, and since when:

```
{"version": 2, "since": "2026-09-23T21:07:46+00:00"}
```

The `since` is later than the `created` of the envelope above, because the block has run again since then without changing its content.

Here is such a run. A comment is added to the SQL, which does not change what the query counts:

#### Specimen · A comment is added to ch07/span

```

$ famulus-notebook status site/projekte/lehrbuch/kapitel/ch07.fam --why
veraltet ch07/span v2 pass
 Präambel, Instruktion oder Voreinstellungen verändert
wartet ch07/follows v2 pass
 wartet auf fam:lehrbuch/ch07/span
aktuell ch07/stays v1 pass
lehrbuch: 3 Blöcke, 2 nicht aktuell

$ famulus-notebook refresh site/projekte/lehrbuch
...
How many letters does the register date between 1520 and 1530? – läuft
How many letters does the register date between 1520 and 1530? – ohne Oracle, v2
unverändert
Report the figure in span.span, at its latest version. – aus dem letzten Lauf
Report the figure in span.span@v1, at version 1 only. – aus dem letzten Lauf
...
lehrbuch: 1 Blöcke gelaufen: lehrbuch/ch07/span

```

`status --why` names the reason: the preamble, instruction or settings changed. `span` is stale (*veraltet*); `follows`, which reads it, waits (*wartet*). `refresh` runs `span`, finds the same 354 letters, and keeps version

2 (v2 *unverändert*, “v2 unchanged”). Because the content is the same, `follows` has nothing new to read and is taken over from its last run. The cascade stops where results stop changing. The lines marked ... stand for 23 further blocks, of this project and of the two projects refreshed first, each taken over from its last run.

A second edit changes the range to 1520–1527. It is a real change of the query, and still the result stays the same, because the register has no letter after 1527 (Chapter 3):

**Specimen · The range of ch07/span is narrowed to 1527**

```
$ famulus-notebook refresh site/projekte/lehrbuch
How many letters does the register date between 1520 and 1530? – läuft
How many letters does the register date between 1520 and 1530? – ohne Oracle, v2
unverändert
lehrbuch: 1 Blöcke gelaufen: lehrbuch/ch07/span
```

The instruction still says 1530; the event line quotes it. The edit was taken back afterwards, so the book’s example shows the range 1520–1530.

### 7.3 The four states

`famulus-notebook status` reports every block in one of four states:

**Table 8** States of a block.

| State                    | Meaning                                                                                 | What refresh does                             |
|--------------------------|-----------------------------------------------------------------------------------------|-----------------------------------------------|
| <i>aktuell</i> (current) | preamble, instruction, settings, files read and versions read are those of the last run | nothing                                       |
| <i>veraltet</i> (stale)  | at least one of them differs;<br>--why says which                                       | runs the block                                |
| <i>fehlt</i> (missing)   | the block has never run                                                                 | runs the block                                |
| <i>wartet</i> (waiting)  | the block is current, but a block it reads with <code>@latest</code> is not             | runs it only if the producer’s result changes |

The reasons that `--why` gives are these:

- *noch kein Lauf*: no run yet;
- *letzter Lauf endete mit Fehler*: the last run ended with an error;
- *Präambel, Instruktion oder Voreinstellungen verändert*: preamble, instruction or settings changed;
- *gelesene Datei verändert*: a file the block reads, such as an attached database, changed;
- *neu gelesen*: `<ref>`: the block reads a result it did not read before;
- `<ref>`: `v1` → `v2`: a result the block reads has a new version;
- *nicht mehr gelesen*: `<ref>`: the block no longer reads a result;
- *wartet auf <ref>*: waits for the named block.

A block is current when the hash of all its inputs equals the hash recorded by its last run. The input hash covers the text of the preamble and the instruction, the settings the block inherits, the files it attaches, and the version and checksum of every result it reads.

### 7.4 Following and staying

Two blocks read `span`. `follows` reads it without a selector and so follows every new version; `stays` pins version 1:

```

SOURCE
```{famulus}
---
id: follows
display: kennzahl
partiturs:
  - id: duckdb-read
    input:
      sql: |
        SELECT r.n_letters AS seen_letters
        FROM
          read_json_auto('{{ref:span.span}}')
          AS f,
          unnest(f.data.data.rows) AS t(r)
artefacts: ...
---
Report the figure in {{ref:span.span}}, at its
latest version.
```

```

RESULT

**354** seen\_letters

**Example 7.2.** fam:lehrbuch/ch07/follows · v2 · unchecked

```

SOURCE
```{famulus}
---
id: stays
display: kennzahl
partiturs:
  - id: duckdb-read
    input:
      sql: |
        SELECT r.n_letters AS seen_letters
        FROM
          read_json_auto('{{ref:span.span@v1}}')
          AS f,
          unnest(f.data.data.rows) AS t(r)
artefacts: ...
---
Report the figure in {{ref:span.span@v1}}, at
version 1 only.
```

```

RESULT

**132** seen\_letters

**Example 7.3.** fam:lehrbuch/ch07/stays · v1 · unchecked

When `span` went from 132 to 354 letters, `follows` became stale, ran, and made its own version 2 with 354. `stays` was not touched: it still reads version 1 and still reports 132. A block that pins a version is never stale because of the block it reads, and never waits for it.

Follow a result when your block should always agree with it, as a table of a chapter agrees with the count it is built on. Pin a result when your block quotes a state, as a note that says what the figure was when a colleague reviewed it.

## 7.5 Refresh

`famulus-notebook refresh` brings a project up to date. It runs exactly what is stale, producers before consumers:

1. first, every other local project that the project reads with `@latest` or `@locked`, in the order of their own references;
2. then the project's notebooks, a notebook that another reads before the reader;
3. within a notebook, blocks in the order of their references.

A dry run shows the plan without running anything:

**Specimen · Refresh as a dry run, with ch07/span stale**

```
$ famulus-notebook refresh site/projekte/lehrbuch --dry-run
zuerst Projekt kepler-lex-naturae
zuerst Projekt pirckheimer-briefwechsel
liefere: fam:lehrbuch/ch07/follows
liefere: fam:lehrbuch/ch07/span
lehrbuch: 2 Blöcke liefern
```

The companion project reads the Kepler and Pirckheimer projects with `@latest`, so they come first (*zuerst Projekt*). It reads the Kármán project only at version 1, so the Kármán project is not refreshed. Of the companion project's own blocks, `span` and `follows` would be looked at (*liefere*, “would run”). The dry run lists the waiting block too; whether it actually runs depends on the result of `span`, which a dry run does not compute. `--nur-projekt` (“this project only”) leaves the other projects alone.

The key `rerun` in a block changes the rule for that block:

**rerun: if-stale**

The default: run when stale. `if-missing` is an older spelling of the same.

**rerun: always**

Run on every refresh, stale or not; for a block that reads a source outside the notebook's knowledge.

**rerun: never**

Never run; take the last result over. For a result that took a long time or used a paid model and must not be made again by accident. A block with `rerun: never` and no result fails with `rerun never, aber kein Log`.

`famulus-notebook run ... --force` runs the selected blocks regardless of their state.

**7.6 The lock**

After every run the runner rewrites `famulus.lock` beside `famulus.yml`. It records, for every block, the input hash, the verdict, the version, the results it consumed and the results it produced:

**Specimen · Two entries of famulus.lock**

```
ch07/span:
 input_hash: 9ec37fe13bdebe8f
 status: pass
 version: 2
 consumes: []
 produces:
 - name: span
 version: 2
 sha: f9c788f58ae171d8
ch07/stays:
 ...
 consumes:
 - ref: fam:lehrbuch/ch07/span.span@v1
 version: 1
 sha: 8fe937c252b32a0d
```

The input hash in the lock is that of the latest run; the envelope keeps the input hash of the run that first made its content. Here they differ, because the comment edit ran `span` again with a new input and an unchanged result.

The lock is the project's statement of which result was computed from which. Commit it with the project, and a reader can check every figure against it. A block that reads `@locked` reads the version recorded here, which makes a whole project reproduce its last complete state while newer versions exist.

#### ⌘ For famuli

`current.json` is `{"version": N, "since": <timestamp>}`. A version folder is `vNNNN/` with `manifest.json`, `report.json`, `result.json`, `verdict.json` and `artefacts/`. An unchanged rerun rewrites the manifest's input hash but not the artefact file, so the envelope's `created` and `input_hash` belong to the run that first made the content. Compare `sha256` values, not timestamps, to decide whether two results are the same.

#### In short

- Every artefact carries an envelope: its name, version, checksum and origin.
- A run makes a new version only when the content changes; old versions are kept.
- States: `current`, `stale`, `missing`, `waiting`; `status --why` names the reason.
- `@latest` follows new versions, `@vN` stays.
- `refresh` runs what is stale, producers first, and stops where results stop changing; `--dry-run` shows the plan.
- `famulus.lock` records which result was made from which.

#### ✍ Exercise 7.1

You change the SQL of `ch03/letters-by-year` so that it also counts letters without a direction. Predict the states of `letters-by-year` and `peak-year` after the edit, and after a refresh in which the table changes but the busiest year stays 1525.

#### ✍ Exercise 7.2

Read the lock entry of `ch07/stays`. Which version of which artefact did it read, and how would you check that the file in the store is the one the lock names?

#### ✍ Exercise 7.3

Give one reason for `rerun: never` and one for `rerun: always`, each with an example from this book.

## 8 Scope and data

A count is a count of something: of letters in a register, of sentences in a language, of lemmata in one mode of counting. This chapter shows how a block states what it reads, how it attaches data files, and three rules of counting that decide whether two figures can be compared.

### 8.1 Collections and years

The collection is the corpus a block reads: `pirckheimer` for the Pirckheimer correspondence, `kepler-prim` for Kepler's works, `karman-nachlass` for the Kármán papers. A collection is a folder under the corpus root; the environment variable `PDAI_COLLECTIONS` names that root, and a notebook writes `$PDAI_COLLECTIONS` wherever a path to it is needed. A block names its collections as a list:

```
collections: [kepler-prim]
```

For a subtask, the list tells the query pipeline where to look. For a local step, it is a statement for the reader; the SQL decides what is read. The key `years` states a range, `years: {from: 1520, to: 1530}`, and is passed to the pipeline as the first and last year of the question.

A question can itself name a corpus, as in “How did Kepler use *lex naturae*?”. The key `locked: true` tells the pipeline that the block’s collections win over any corpus the question names; a mismatch is reported, not followed. The other scope keys pass further context to the pipeline unchanged:

**Table 9** Scope keys for a subtask.

| Key                             | Passed as                                                  |
|---------------------------------|------------------------------------------------------------|
| <code>language</code>           | the language of the texts to be read                       |
| <code>persons</code>            | persons the question is about                              |
| <code>lemmata</code>            | lemmata to be counted; requires <code>counting_mode</code> |
| <code>counting_mode</code>      | how lemmata are counted (below)                            |
| <code>terms</code>              | terms the question is about                                |
| <code>evidence</code>           | the kind of evidence the pipeline returns                  |
| <code>reading_doc</code>        | the document the reader has open                           |
| <code>person_id, project</code> | who asks, and in which project                             |
| <code>locked</code>             | whether the collections win over the question              |

A key missing in the preamble is taken from the notebook’s settings or the project’s defaults (Chapter 5). The companion project sets `evidence: grounding` in its defaults, so every subtask of the project passes it.

## 8.2 Data files

A local step reads databases through the key `duckdb`, a list of attachments:

```
duckdb:
- alias: main
 path: $PDAI_COLLECTIONS/kepler-prim/kepler-prim_stanza.duckdb
 read_only: true
```

The attachment named `main` is opened as the default database, so its tables are named without a prefix: `stz_sentences`. Every other attachment is attached under its alias, and its tables are named with it: `stz.stz_sentences`. Files that are not databases, such as the Parquet file of a lemma index, are read in the SQL itself with `read_parquet('...')`, and `$PDAI_COLLECTIONS` is replaced there as well.

Every attachment is opened read-only, and the connection is closed as soon as the query is done. A notebook never writes to the corpus. An attached file that does not exist stops the block with the missing path as the reason, before the query runs.

### For famuli

`duckdb` entries: `alias` (a Python identifier, default `main`), `path` (absolute or with `$PDAI_COLLECTIONS`), `read_only`. Only files ending in `.duckdb` or `.db` are attached; any other entry is skipped without a message, so do not rely on a Parquet attachment: read it with `read_parquet`. The corpus root defaults to `/Volumes/PDAI-1/pdai-collections` when `PDAI_COLLECTIONS` is not set. A remote read (Chapter 11) is stricter: one statement, `SELECT` or `WITH` only, paths inside one collection, no external file access.

## 8.3 Two languages in one collection

The Kepler edition prints Kepler’s Latin together with a German editorial apparatus, and parts in other languages. Stanza, the language analyser that built the sentence table, assigns each sentence a language:

```

SOURCE
```{famulus}
---
id: languages
collections: [kepler-prim]
display: tabelle
duckdb: ...
partiturs:
- id: duckdb-read
  input:
    sql: |
      SELECT lang, count(*) AS sentences
      FROM stz_sentences
      GROUP BY lang
      ORDER BY sentences DESC
artefacts: ...
---
How many sentences of the Kepler edition does
Stanza assign to each language?
```

```

RESULT

| lang | sentences |
|------|-----------|
| la   | 325,702   |
| de   | 137,435   |
| fr   | 14,375    |
| en   | 9209      |

**Example 8.1.** fam:lehrbuch/ch08/languages · v1 · unchecked

Of 486,721 sentences, 325,702 are Latin and 137,435 German. A count of Kepler's use of a word that does not filter by language mixes his text with the edition's apparatus. Every Kepler block of this book therefore restricts its reading to `lang = 'la'`. The language filter is the first rule of comparable counts.

## 8.4 What identifies a sentence

The second rule concerns the sentence key. In the sentence table, a sentence is numbered within its page: `sent_idx` starts again at 0 on every page `pidx` of every document `doc_id`. A sentence is therefore identified by the triple `(doc_id, pidx, sent_idx)`:

```

SOURCE
```{famulus}
---
id: sentence-key
collections: [kepler-prim]
display: kennzahl
duckdb: ...
partiturs:
- id: duckdb-read
  input:
    sql: |
      SELECT count(*) AS n_rows,
             count(DISTINCT (doc_id, pidx,
                             sent_idx)) AS n_by_page_key,
             count(DISTINCT (doc_id,
                             sent_idx)) AS n_without_page
      FROM stz_sentences
      WHERE lang = 'la'
artefacts: ...
---
How many Latin sentences are there, counted by
the key (doc_id, pidx, sent_idx), and how many
remain if the page index pidx is left out of
the key?
```

```

RESULT

**325,702** n\_rows  
**325,702** n\_by\_page\_key  
**5357** n\_without\_page

**Example 8.2.** fam:lehrbuch/ch08/sentence-key · v1 · unchecked

Counted by the triple, the Latin sentences are 325,702, one per row. Counted without the page index they collapse to 5,357, because sentence 50 of every page of a document becomes one and the same "sentence 50" of that document. A join on such a key does worse than undercount: it pairs sentences of different pages and invents co-occurrences that are not in any text. The evidence list of Chapter 3 shows the triple for this reason, `kgw-01 · 190 · 0`.

## 8.5 Counting lemmata

The third rule concerns the counting mode. A lemma is the dictionary form under which the analyser files every inflected form: *legem*, *legis*, *leges* are all counted under *lex*. Whether a related word counts as well is a decision, and it changes the result:

```

SOURCE
```{famulus}
---
id: counting-modes
collections: [kepler-prim]
display: kennzahl
duckdb: ...
partiturs:
- id: duckdb-read
  input:
    sql: |
      WITH la AS (
        SELECT doc_id, pidx, sent_idx FROM
        stz_sentences WHERE lang = 'la'
      ),
      s AS (
        SELECT t.doc_id, t.pidx, t.sent_idx,
        bool_or(t.lemma = 'lex') AS
        has_lex,
        bool_or(t.lemma = 'natura') AS
        has_natura,
        bool_or(t.lemma = 'naturalis')
        AS has_naturalis
      FROM
        read_parquet('$PDAI_COLLECTIONS/kepler-
        prim/lemma_index.parquet')
        AS t
        JOIN la USING (doc_id, pidx,
        sent_idx)
        WHERE t.lemma IN ('lex', 'natura',
        'naturalis')
        GROUP BY t.doc_id, t.pidx, t.sent_idx
      )
      SELECT count(*) FILTER (WHERE has_lex
        AND has_natura) AS canonical,
        count(*) FILTER (WHERE has_lex
        AND (has_natura OR
        has_naturalis))
        AS family_adj
      FROM s
artefacts: ...
---
In how many Latin sentences of Kepler do lex
and natura occur together (counting mode
canonical), and in how many if the adjective
naturalis counts as well (family+adj)?
```

```

## RESULT

44 canonical

53 family\_adj

**Example 8.3.** fam:lehrbuch/ch08/counting-modes · v1 · unchecked

Counted by lemma alone (mode `canonical`), *lex* and *natura* occur together in 44 Latin sentences. If the adjective *naturalis* counts as a member of the family of *natura* (mode `family+adj`), the figure is 53. Neither figure is wrong; they answer different questions. A figure without its mode cannot be compared with any other figure.

The rule is therefore enforced: a block that names `lemmata` must name its `counting_mode`, or it stops before it runs with `<id>: counting_mode fehlt bei der Lemma-Zählung` (“counting mode missing in the lemma count”). The modes in use are:

**canonical**

the lemma only; the analyser’s lemmatisation already covers the inflected forms;

**family**

the lemma and its listed variants;

**family+adj**

the lemma, its variants and the derived adjective.

Prefer `canonical`. Hand-made lists of variants tend to add back what the lemmatiser already covers, together with its errors.

**Specimen · The same count, two routes**

The Kepler project of Chapter 13 counts sentences with *lex* and *natura* in two ways. The query pipeline, asked in mode `canonical`, reports 45 sentences in 16 documents (`fam:kepler-lex-naturae/lex-naturae/lex-natura`). The direct reading of the lemma index, restricted to nouns and to Latin sentences, finds 44 in 16 documents (`fam:kepler-lex-naturae/lex-naturae/lex-natura-gegenprobe`), the same 44 as the block above. Chapter 13 follows the difference of one sentence up; the two blocks keep both figures and their routes side by side.

**In short**

- `collections` names the corpus; `years`, `language`, `persons`, `lemmata`, `terms` and the other scope keys are passed to the query pipeline.
- `locked: true` makes the block's collections win over a corpus named in the question.
- `duckdb` attaches databases read-only; `main` is the default database.
- Filter by language; key sentences by `(doc_id, pid, sent_idx)`; state the counting mode.

**✍ Exercise 8.1**

Change `ch08/languages` so that it counts only the German sentences of the volume `kgw-01`. Which column of `stz_sentences` do you filter, and which value?

**✍ Exercise 8.2**

Explain the figure 5,357: what exactly is counted when the key leaves out `pid`? Write a query that computes it in a second way, document by document.

**PART III**

## Working with others

### ■ 9 Editing and annotating

A notebook is a text before it is a program. Its paragraphs explain what the blocks ask and why, and those paragraphs are revised like any other scholarly prose. This chapter shows how the viewer revises the text of a notebook: how a paragraph is chosen, how an instruction becomes a proposed wording, how the proposal is read and decided, and what reaches the `.fam` file. The blocks themselves are not touched; Chapter 10 treats them.

#### ■ 9.1 The viewer

The viewer of a notebook has three columns (Figure 4). On the left is the list of projects and their notebooks; the current notebook is marked. In the middle is the notebook itself, rendered as it will be read: headings, paragraphs, and for each block its state chip, its version, its instruction, its collapsed Partitur and its result. On the right is the side panel. It opens when a paragraph is chosen and closes with `Esc`.

The side panel shows one step at a time. Before a paragraph is chosen it is empty. When a paragraph is chosen, it shows the paragraph, a row of Partitur buttons, the engine that will write the proposal, a field for the instruction and the button *Ausführen* (run). While the proposal is written it shows the progress of the run. When the proposal is there it shows the review card. Nothing else is shown at any of these steps:

no second list, no statistics, no settings. The rule behind this layout is that every step shows what the next action needs, and one place to act.




**Figure 4** Chapter 4 in the viewer with the first paragraph chosen. The pencil in the margin marks the chosen paragraph; the side panel shows the paragraph, the Partitur buttons, the engine, and the instruction field.

The viewer serves the same notebooks as the command line. It is opened at the address of the notebook service, <http://127.0.0.1:5118/notebook>, and a notebook is chosen in the list or named in the address: `/notebook?nb=lehrbuch/ch08` opens Chapter 8 of the companion project. The revision itself is done by the Lektor, the editorial service `ai-lektorat`; the viewer loads its layer into the page. Both services run on the same machine, and a request from that machine is the owner of every notebook without a login (Chapter 11 treats other readers).

## 9.2 Choosing a paragraph

A paragraph is chosen in one of three ways:

- a click on the paragraph;
- a click on the pencil in its margin;
- a selection of words inside it, followed by *Annotate selection*, the small button that appears above the selection.

The first two choose the whole paragraph. The third chooses the paragraph and remembers the selected words. The instruction then applies to those words only; the viewer puts the selection in front of it,

Nur die Auswahl »A count that adds it answers a different question.« ändern: ...

(“change only the selection”), and the proposal is still written for the whole paragraph, so that the sentence around the selection stays intact.

A paragraph whose review card is still open cannot be chosen a second time for a new annotation. A selection inside it goes into the open card as a further instruction (below), or the viewer asks to close the card first. Two competing proposals for the same paragraph never exist.

Only prose is chosen this way. Headings, the instruction of a block and its result belong to the block and have their own actions (Chapter 10).

### 9.3 Writing an instruction

The row of buttons above the instruction field selects the Partitur card of the revision, the kind of work the Lektor is to do:

#### Überarbeiten (revise)

change what the instruction says and nothing else; the instruction is required;

#### Neu fassen (reformulate)

write a new wording of the paragraph under the style rules of the document;

#### Nachformulieren (reformulate onwards)

apply the style of the document to every later paragraph, from this one to the end;

#### Kommentar (comment)

store a remark without a proposal;

#### Regel (rule)

propose a rule of usage for the language institution LWgrammar (Chapter 10).

Most revisions are *Überarbeiten*. The instruction states what is to change, as an order to a copy editor would: *Replace “mixes both” by “mixes Kepler’s text with the editors’ notes”. Change nothing else.* The chip under the buttons names the engine that writes the proposal, here `gemin` · `gemin-3.8-flash`; a click on it offers the other engine.

An instruction of the owner is a binding directive. The Lektor carries it out; it does not weigh it, soften it, or add a remark about the author or the text. A proposal that adds such a remark is rejected before it is shown (below).

### 9.4 The review card

After *Ausführen* the Lektor writes a proposal, the Lektor’s Fassung (German for “version of a text”; the viewer keeps the word). The side panel turns into the review card (Figure 5).

The screenshot shows the Famulus Notebook interface. On the left is a sidebar with a list of chapters and sections. The main area displays 'Chapter 8: Scope and data' with a paragraph of text. A change is highlighted in green: 'The Kepler edition prints Kepler's Latin together with a German apparatus. A count that does not filter by language mixes ~~both~~ Kepler's text with the editors' notes.' Below the text, there are three decision buttons: 'Neu ausführen', 'Anmerken', and 'Diagnose'. The card also shows the result of the formulation check, the instruction, and the Fassung (version) of the text.

**Figure 5** The review card for the first paragraph of Chapter 8. The paragraph shows the change inline: struck text in red, new text in green. At the top of the card are the three decisions; below them the result of the formulation check, the instruction, and the Fassung chip.

The card reads from top to bottom:

1. The three decisions: *Übernehmen* (accept), *Verwerfen* (discard) and *Weiter* (next open paragraph), with every other action behind . They are at the top, so that a decision never needs scrolling past a long text.
2. A line on the current Fassung: *Aktuelle Fassung · 1 Änderung im Text markiert*, one change marked in the text.
3. The result of the formulation check, the test every Fassung passes before it is shown (below).
4. The instruction, as a message of its author.
5. The Fassung chip: its number, its engine, and whether it is shown in the text (*im Text*).
6. A field for a further instruction, which produces the next Fassung.

The change itself is shown in the paragraph, not in the card. A fine correction marks the struck words and the new words in place, as in Figure 5, where *both* gives way to *Kepler's text with the editors' notes*. A reformulation that changes more than half of the words is shown instead as clean new text, with an Original chip beside it; the chip shows the old wording on hover and opens a window to compare the two. The old wording is never printed a second time in the paragraph.

#### </> For famuli

Fine correction and reformulation are told apart by the share of changed words: above 50 % the Fassung is a reformulation. The share is computed on words, not on characters, so a changed word counts once whatever its length.

## 9.5 The formulation check

Before the card shows a Fassung, the Fassung is checked against its source by LWgrammar, the language institution of the Famulus system. The check compares the statements of the source and the Fassung and reports four figures, visible in the card:

- *Aussagen erhalten*: the share of the source's statements that the Fassung still makes;
- *hinzugefügt*: statements the Fassung makes that the source does not;
- *Bewertungen*: evaluative insertions, such as a judgement of the author or of the text;
- *Register*: the distance in register between source and Fassung.

A Fassung that loses statements, adds evaluations, or adds statements that no instruction asked for is *zurückgewiesen* (rejected). The Lektor gets one round to repair it; if the repair fails as well, the card says so and names the reason. There is no route by which an unchecked Fassung reaches the card.

An instruction can order a change of content, and the check takes the order into account. An order to strike licenses lost statements; an order to add, to complete or to cite licenses new ones; an order to replace one wording by another licenses both. What an order never licenses is an evaluation, a remark about the text, or a new term for an old one.

#### Specimen · A replacement, checked twice

The instruction *Replace "answers a different question" by "counts something else". Change nothing else.* for the paragraph on counting modes of Chapter 8 was first checked by a guard that did not yet know replacements as a kind of order. The Fassung did exactly what was asked, and the check rejected it: *Aussage hinzugefügt: A count that adds it counts something else.* The card then offered *Trotz Befund übernehmen*, accept despite the finding (Figure 6).

After the replacement was added to the orders that license a changed statement, the next Fassung of the same paragraph passed: *Formulierungsprüfung bestanden · Aussagen erhalten 100 % · hinzugefügt 1 · Bewertungen 0.* The added statement is still reported, but it no longer blocks (Figure 7).

en 9209

Neu ausführen Anmerken

Diagnose

What identifies a sentence

aktuell v1

How many Latin sentences are there, counted by the key (doc\_id, pid, sent\_idx), and how many remain if the page index pid is left out of the key?

Partitur

325702 n\_rows, 325702 n\_by\_page\_key, 5357 n\_without\_page.

ohne Oracle

|        |               |                |
|--------|---------------|----------------|
| 325702 | 325702        | 5357           |
| n_rows | n_by_page_key | n_without_page |

Neu ausführen Anmerken

Diagnose

Declaring the counting mode

The adjective *naturalis* is a lemma of its own, not a form of the noun *natura*. A count that adds it **answers accounts different something question else**.

Überarbeiten Prüfung Kommentare Metadaten

< 1/2/2 > 1 offen LISTE

§ Declaring The Counting Mode

✓ Trotz Befund übernehmen ✗ Verwerfen Weiter

Aktuelle Fassung · 4 Änderungen im Text markiert

Formulierungsprüfung: zurückgewiesen

Aussagen erhalten 100 % · hinzugefügt 1 · Bewertungen 0 · Register +0.00

- Aussage hinzugefügt: A count that adds it counts something else.

Nur die Auswahl »The adjective *naturalis* is a lemma of its own, not a form of the noun *natura*. A count that adds it answers a different question.« ändern: Replace "answers a different question" by "counts something else". Change nothing else.

Gerd Graßhoff · stil · gerade eben

Fassung 1 im Text 4 Änderungen

Partitur: ✓ Verallgemeinern Gemini 3.8 Flash

Weitere Anweisung zu § 2 ... — ergänzt die bisherigen und erzeugt Fassung 2

Enter = Fassung 2 · Shift+Enter = Zeilenbruch

Fassung 2

**Figure 6** A rejected Fassung. The card names the finding, and the first decision reads *Trotz Befund übernehmen*.

The instruction is decomposed into its goals as well, and each goal is checked on its own: a phrase to strike must be gone, a phrase to replace must be replaced by the given words, a citation must be present, and a paragraph that ended with a full sentence must still do so. A goal that cannot be checked mechanically, such as *Change nothing else*., is marked as unchecked: the reader of the card checks it.

## 9.6 A second round

The field at the bottom of the card takes a further instruction. It adds to the instructions given so far, and the Lektor writes the next Fassung from all of them (Figure 7). The earlier Fassung stays in the card, collapsed, with its number, its engine and a link *anzeigen* (show). A long chain of rounds shows only the last two; the older ones are reached by paging.

en 9209

Neu ausführen Anmerken

Diagnose

What identifies a sentence

aktuell v1

How many Latin sentences are there, counted by the key (doc\_id, pid, sent\_idx), and how many remain if the page index pid is left out of the key?

Partitur

325702 n\_rows, 325702 n\_by\_page\_key, 5357 n\_without\_page.

ohne Oracle

|        |               |                |
|--------|---------------|----------------|
| 325702 | 325702        | 5357           |
| n_rows | n_by_page_key | n_without_page |

Neu ausführen Anmerken

Diagnose

Declaring the counting mode

The adjective *naturalis* is a lemma **ofin its own, own right**, not a form of the noun *natura*. A count that adds it **answers accounts different something question else**.

Überarbeiten Prüfung Kommentare Metadaten

< 1/2/2 > 1 offen LISTE

§ Declaring The Counting Mode

✓ Übernehmen ✗ Verwerfen Weiter

Aktuelle Fassung · 6 Änderungen im Text markiert

Formulierungsprüfung bestanden

Aussagen erhalten 100 % · hinzugefügt 1 · Bewertungen 0 · Register -0.06

Nur die Auswahl »The adjective *naturalis* is a lemma of its own, not a form of the noun *natura*. A count that adds it answers a different question.« ändern: Replace "answers a different question" by "counts something else". Change nothing else.

Gerd Graßhoff · stil · gerade eben

Fassung 1 4 Änderungen anzeigen

Replace "a lemma of its own" by "a lemma in its own right".

Ö Rückmeldung · Gerd Graßhoff · stil · gerade eben

Fassung 2 im Text 6 Änderungen

Verallgemeinern: nichts über den Absatz hinaus.

Partitur: ✓ Verallgemeinern Gemini 3.8 Flash

Weitere Anweisung zu § 2 ... — ergänzt die bisherigen und erzeugt Fassung 3

Enter = Fassung 3 · Shift+Enter = Zeilenbruch

Fassung 3

**Figure 7** The second round. Under the first instruction and the collapsed Fassung 1 stands the further instruction and Fassung 2, which is now shown in the text; the formulation check passed.

Enter in the field sends the instruction; Shift+Enter breaks the line. The same is reached with the button *Fassung 2*, whose number counts on. A key is never the only way to an action.

## 9.7 Deciding

A Fassung is decided with one of the three buttons.

*Übernehmen* writes the Fassung into the `.fam` file in place of the old paragraph, renders the notebook again, and shows the card as decided (Figure 8): *Übernommen V1*, with a history of the paragraph from *V0 Original* over the instruction and the Fassung to the accepted version. The button *Zurücknehmen* (undo) restores the previous version; *Wieder öffnen* (reopen) makes the paragraph open for a new round. An accepted paragraph carries no open marker in the text, only a small version chip that opens its history.

*Verwerfen* discards the Fassung. The `.fam` file is not changed, and the annotation is stored as rejected.

*Weiter* leaves the card open and moves to the next open paragraph.




**Figure 8** The paragraph of Figure 5 after *Übernehmen*: the card shows the accepted version V1 and the history of the paragraph; the notebook was rendered again.

## 9.8 What reaches the file

Every annotation remembers where its paragraph stands in the `.fam` file: a range of source lines, such as lines 9 to 11 of `kapitel/ch08.fam`. When a Fassung is accepted, the Lektor finds the paragraph again at that place, checks that the text there is still the text the annotation was made on, and replaces exactly those lines. Front matter, other paragraphs and every block stay byte for byte as they were.

Two consequences follow. First, an accepted revision of prose never makes a block stale: the text of a block, its preamble and its instruction are not part of the paragraph, so their checksums do not change, and after the first annotation of Chapter 8 was accepted all three blocks of the chapter were still *aktuell*. Second, a paragraph that was changed in the file since the annotation was made is not overwritten: the Lektor refuses to apply the Fassung and says that the paragraph was not found at its place.

### For famuli

The rendered paragraph carries its source range in the attribute `data-pos` (for example `data-pos="9-11"`), and its identity in `data-seg-id`, the section slug and the ordinal of the paragraph within the section (`two-languages-in-one-collection#2`). An annotation is anchored by the source range and the stored text, never by the identity alone; the identity changes when a paragraph is inserted before it. The Lektor's store is `annotations.duckdb` of `ai-lektorat`, with the tables `annotations`, `revision_runs` and `segment_versions`.

In short

- Choose a paragraph by a click, by its pencil, or by selecting words in it.
- Choose a Partitur card; *Überarbeiten* carries out what the instruction says and nothing else.
- Every Fassung passes the formulation check before it is shown; orders to strike, replace, add, complete or cite license the change they order.
- A further instruction produces the next Fassung.
- *Übernehmen* writes the paragraph into the `.fam` file, at its source lines, and leaves the blocks as they are.

✎ Exercise 9.1

Open Chapter 8 of the companion project in the viewer, select the words *answers a different question* in the paragraph on counting modes, and order a replacement of your own. Which goals does the card list for your instruction, and which of them are checked?

✎ Exercise 9.2

Order *Neu fassen* for the same paragraph. Is the Fassung shown as a fine correction or as a reformulation? What does the Original chip show? Discard the Fassung afterwards and check with `famulus-notebook status lehrbuch` that nothing changed.

10 Refining and correcting

Chapter 9 revised the prose around the blocks. This chapter turns to the blocks themselves: how to see what a run did, how to correct a block that answers wrongly, how to tell the system what the next run should do differently, and how a correction of language becomes a rule for every later text. Three kinds of correction are distinguished, because they reach three different places:

Table 10 Three kinds of correction.

| A correction of    | reaches                    | by                                      |
|--------------------|----------------------------|-----------------------------------------|
| one block          | its <code>.fam</code> file | editing the preamble or the instruction |
| the query pipeline | its instructions           | an annotation and the learning loop     |
| the language       | the rules of LWgrammar     | a rule proposal                         |

10.1 What a run did

Under the result of every block is the fold *Diagnose*. Opened, it shows where the result came from and, for a subtask, the trace of the run (Figure 9). The first line names the Partitur that ran, the language model, the collections and the duration:

ai-query-phasel · gemini-3.5-flash-lite · pirkheimer · 7617 ms

Below it the trace lists every stage of the pipeline in the order in which it ran, indented by its place in the Partitur: its name, the operation that carried it out, its grade and its time in milliseconds. The subtask of Chapter 2 runs about forty stages. Most take a few milliseconds; the time goes into the few that call a language model, here `afm-query-extract` (2370 ms), `normalize` (1268 ms) and `intent-gate` (890 ms).




**Figure 9** The fold *Diagnose* of the subtask `ch02/subtask-count`: origin line and trace. Each row is a stage, with its operation, its grade and its time.

The trace answers two questions that a result alone cannot. The first is *which route the question took*: the row `answer-from-register` with its child `correspondence-roster` shows that the count was read from the register of letters and resolved to persons, not counted from a list of letters. The second is *where time or quality went*: a stage graded below the others, or a stage that took most of the time, is where to look first.

The grades are the pipeline's own judgement of each stage. They are not the verdict of the block. The verdict compares the result with the oracle (Chapter 4); the last stage, `goal-check`, compares it with the pipeline's internal statement of the goal. The two can disagree: in Figure 9 the block passed its oracle of 75, while `goal-check` graded the run only ADEQUATE. The verdict is the one the notebook reports.

**</> For famuli**

The trace is stored with every version of a subtask, as `_famulus/store/<notebook>/<block>/vNNNN/trace.json`, and served at `GET /api/notebooks/<notebook>/trace/<block>`. A local step has no trace; its Diagnose shows only the origin line. The origin line is the field `herkunft` of the artefact envelope: `partitur`, `modell`, `sammlungen`, `dauer_ms`, and `peer` for a block that ran elsewhere (Chapter 11).

**10.2 Correcting a block**

A block that answers wrongly is corrected in its source. Its preamble states scope and plan; its instruction states the question. Either is edited in the `.fam` file, and the next `refresh` runs exactly the blocks whose source changed and the blocks that consume them (Chapter 7).

The most frequent correction is a sharper question. The golden question *How many correspondents did Pirckheimer have between 1520 and 1530?* is, taken alone, ambiguous between two readings: the number of persons in the register, and the number of named partners in the letters the pipeline finds. Asked alone, the pipeline takes the second reading:

**Specimen · The golden's question alone**

The block `count-there` of Chapter 11, with the golden question as its only sentence, routed to the letter list. It found 200 letters with 70 distinct correspondents, and the verdict against the oracle of 75 was *abweichend* (deviating). Its report named the mode of the answer: `letter-list`.

A second sentence states which reading is meant:

```
How many correspondents did Pirckheimer have between 1520 and 1530?
Count distinct persons in letters_resolved, resolved through ent_canonical.
```

With it the same block counts 75 and passes; the report names the mode `roster`. The sentence is part of the instruction, so it changed the block's input; `refresh` re-ran this block and no other (Chapter 11 prints the transcript). The subtask of Chapter 2 carries the second sentence for this reason.

The rule behind the correction is to correct *the question*, not the answer. An oracle is never adjusted to fit a result; a result that deviates is either a wrong answer to a clear question, which is a fault of the pipeline and goes to the learning loop (below), or a right answer to an unclear question, which is a fault of the block and is corrected in its instruction.

**10.3 Running a block again**

The button *Neu ausführen* (run again) under a block runs this block through the same path as `famulus-notebook run` with the block's name. A block that is current is not run a second time: it answers *aus dem letzten Lauf* (from the last run), and its version stays. A block becomes worth running again only when its source, its settings, its input files or a version it consumes has changed. To force a new run of a current block, for instance to see whether a changed pipeline answers differently, use the command line:

```
famulus-notebook run lehrbuch/kapitel/ch02.fam --block subtask-count --force
```

A forced run that yields the same data does not make a new version (Chapter 7); it replaces the log of the current one.

**10.4 Telling the next run**

A block whose answer is wrong though its question is clear points to the pipeline. The button *Anmerken* (annotate) under the block opens a field with the question *Was soll der nächste Lauf anders machen?*, what should the next run do differently (Figure 10). The note is sent with *Senden*.

The screenshot shows a user interface for a learning loop. At the top, there is a tab labeled 'bestanden'. Below it, a large number '75' is displayed, followed by the text 'Briefpartner erwartet = 75'. There are two buttons: 'Neu ausführen' and 'Anmerken'. Below these buttons is a text input field with the placeholder text 'Was soll der nächste Lauf anders machen?'. At the bottom of the input field is a 'Senden' button. Below the 'Senden' button is a dropdown menu labeled '▼ Diagnose'.

**Figure 10** The field *Anmerken* under a block. The note states what the next run should do differently.

A note under a block is not a comment on the notebook. It is an annotation in the learning loop of the query pipeline: it is stored with the block's question, its result and its verdict, and it waits there until the loop takes it up. A good note is therefore written for the pipeline, not for a reader: it names the stage or the step that went wrong and what it should have done.

#### **Specimen · Two notes, one useful**

*The answer is wrong.* — The pipeline learns nothing from it.

*The count must be taken from the register, not from the letters found: the route was letter-list, it should be roster.*  
— The loop can compare this with the trace and propose a change to the instruction of the stage that chose the route.

The loop works on the instruction of each stage, the text that tells a stage what to do. From a group of open annotations on one stage it proposes a changed instruction, an instruction version. The proposal is not taken on trust: an A/B gate runs the goldens once with the current instruction and once with the proposal, and the proposal becomes the new version only if it improves on the goldens and the share of passing goldens does not fall by more than one percentage point. A proposal that fails the gate is kept as rejected, with its reason; an accepted version can be rolled back.

The view *Lernen* (learning), reached from the foot of the notebook list, shows the state of the loop (Figure 11). Its three tabs list the annotations, the learning runs, and the instructions with their versions.

Famulus Notebook

## Lernen

Anmerkungen

Lernläufe

Instruktionen

1042 offen von 1890. Neue Anmerkungen entstehen mit „Anmerken“ an einem Block.

- **goal\_check** auto-flagged by goal\_check: answer did not satisfy goal\_spec · *How many correspondents did Pirckheimer have between 1520 and 1530? Count distinct persons in letters\_resolved, resolved through ent\_canonical.*
- **goal\_check** auto-flagged by goal\_check: answer did not satisfy goal\_spec · *How many correspondents did Pirckheimer have between 1520 and 1530? Count distinct persons in letters\_resolved, resolved through ent\_canonical.*
- **goal\_check** auto-flagged by goal\_check: answer did not satisfy goal\_spec · *How many correspondents did Pirckheimer have between 1520 and 1530? Count distinct persons in letters\_resolved, resolved through ent\_canonical.*
- **goal\_check** auto-flagged by goal\_check: answer did not satisfy goal\_spec · *How many correspondents did Pirckheimer have between 1520 and 1530? Count distinct persons in letters\_resolved, resolved through ent\_canonical.*
- **goal\_check** auto-flagged by goal\_check: answer did not satisfy goal\_spec · *How many correspondents did Pirckheimer have between 1520 and 1530? Count distinct persons in letters\_resolved, resolved through ent\_canonical.*
- **goal\_check** auto-flagged by goal\_check: answer did not satisfy goal\_spec · *How many correspondents did Pirckheimer have between 1520 and 1530? Count distinct persons in letters\_resolved, resolved through ent\_canonical.*
- **goal\_check** auto-flagged by goal\_check: answer did not satisfy goal\_spec · *Wer nennt Einstein in Briefen an Kármán? Gib je Beleg den Brief, den Absender und die Koordinaten doc\_id, pidx, sent\_idx.*
- **goal\_check** auto-flagged by goal\_check: answer did not satisfy goal\_spec · *Wie viele Manuskripte liegen im Kármán-Nachlass? Nenne je Manuskript Datum, Umfang in Seiten, Titel, Gegenstand und Zweck.*

**Figure 11** The view *Lernen*: 1042 of 1890 annotations are open. The first entries are notes that the pipeline's own goal check made automatically.

### Specimen · The learning loop on 24 September 2026

The loop held 1890 annotations, 1042 of them open and 848 resolved. Most were not written by readers: 767 were made automatically by the stage `goal-check` when a run did not satisfy its internal goal, and the six newest of these concern the Pirckheimer count above, a run that passed its oracle. 29 stage instructions existed in 39 versions: 30 active, 6 rejected by the gate, 3 superseded. Of the versions, 21 were written by hand, 8 by an agent, 7 by the learning loop, 3 otherwise. The table of learning iterations, which records a full round of the loop, was empty.

The figures show what the loop is and what it is not. It is a store of notes with a gate that has rejected six of 39 versions. It is not yet a system that improves itself unattended: most open notes are automatic, and some of them contradict the verdict of the notebook.

The notes of this book's companion project were not sent. A note made to try the button is a note the loop has to work through, and it stands beside the notes of real readers. Send a note only when it says what a run should do differently.

## 10.5 From a correction to a rule

Some corrections of language are not about one paragraph. When the owner corrects the same confusion twice, for instance *fact* where a statement is meant, the correction is a rule of usage, and it belongs to LWgrammar, the language institution of the system, where every later text is checked against it.

The Partitur card *Regel* (rule) of the side panel (Chapter 9) takes an accepted revision, the original and the revised wording, and asks for the one general rule the revision enforces. The proposal has a statement, a positive and a negative example, the Lektor that owns it, and a detector that finds the confusion in a text. If no general rule is implied by the revision, the answer says so, and nothing is proposed. A proposal is submitted to the LWgrammar rule store with the annotation as its evidence.

A rule in the store has an identifier, such as R-GG-001 for the rule that only statements, not facts or states of affairs, are true or false, and a status: *active*, *revised* or *revoked*. A rule is never deleted. A correction by the owner revises or revokes it, and a revoked identifier is not given out again. The formulation check of Chapter 9 names the rules it applies: the rejection of the replacement there was reported under R-LG-024, the rule against added statements.

### In short

- *Diagnose* shows the origin of a result and, for a subtask, the trace: every stage, its operation, grade and time.
- The verdict is decided by the oracle, not by the pipeline's own grades.
- Correct a block in its source, and correct the question, never the oracle.
- *Neu ausführen* runs a stale block; *-- force* runs a current one.
- *Anmerken* sends a note to the learning loop; the A/B gate decides which changed instruction is kept.
- *Regel* turns an accepted revision into a rule of LWgrammar, with a lifecycle.

### ✍ Exercise 10.1

Open the Diagnose of `ch02/subtask-count`. Which stage chose the route of the count, and which stage took the most time? Which stages called a language model?

### ✍ Exercise 10.2

Remove the second sentence of the instruction of `ch02/subtask-count` in a copy of the companion project and run `refresh`. What does the Diagnose show as the route, and what is the verdict? Why does `refresh` run this block and no other?

### ✍ Exercise 10.3

Write the note you would send for the run of the first specimen of this chapter. Name the stage, the route it took, and the route it should have taken. Do not send it.

## 11 Coauthors and readers

So far one person worked on one machine. This chapter adds the others: a reader who comments, a coauthor who works on another machine, and the machines themselves, which offer each other their collections, their results and their query pipeline. It ends with a notebook that runs on a machine without any collection at all.

### 11.1 Owner and commentator

The Lektor knows two roles. The owner revises: he chooses paragraphs, gives instructions, and accepts or discards Fassungen. A commentator comments: he chooses a paragraph and writes a remark, and that is all he can do. The side panel shows each role only its own actions. The owner's header offers *Überarbeiten*, *Prüfung* (review) and *Kommentare* (comments); the commentator's offers *Kommentar* and *Meine Notizen* (my notes).

A request from the machine the services run on is the owner, without a login. Every other request, including one that reaches the machine through the platform proxy, must sign in as the owner with a password, or come as a commentator through a share link. The owner creates share links with the chain icon at the top of the side panel: a name for the reader, a period of validity (30 days unless stated otherwise), and a link that opens the shared document as that reader. The link admits to one document and no other; after its period, or once the owner has withdrawn it, it answers that it is no longer valid. A commentator's remark appears in the owner's review as a ground for revision, beside the owner's own instructions.

Share links are made for rendered documents, such as a paper under revision. A chapter of a notebook is not one of them: it is rendered by the notebook viewer, not by the Lektor, and a share link for it is refused with the reason *Kommentatoren-Links gibt es nur für gerenderte Dokumente*. A reader of a notebook reads its rendered site (Chapter 12) or works with it on his own machine, as a coauthor.

## 11.2 Peers

A coauthor works on his own machine, with his own notebook service. The services know each other as peers. A peer is a named Famulus service on another machine, and each machine lists the peers it calls in `~/.config/famulus/peers.yaml`:

```
peers:
 mac-studio:
 kind: notebook
 endpoints:
 - http://100.102.189.23:5118
 - https://mac-studio.tail147011.ts.net/famulus-notebook
 token_env: FAMULUS_TOKEN_MAC_STUDIO
```

The kind says what the service is: `notebook` for a notebook service, `ai-query` for a query pipeline, `lektorat`, `viewer` or `mcp` for the others. The endpoints are the addresses under which the peer may be reached, in the order in which they are tried: the loopback address, the home network, a VPN, the tailnet, a public name. The first endpoint whose probe answers within 1.5 seconds is used, and the choice is kept for 60 seconds. A laptop that moves between networks therefore keeps one file. `token_env` names the environment variable that holds the token for this peer; the token itself is never written into the file.

The command `peers` shows, adds and probes peers:

### Specimen · Probing a peer

```
$ famulus-notebook peers probe mac-studio
mac-studio http://100.102.189.23:5118: [Errno 61] Connection refused
mac-studio https://mac-studio.tail147011.ts.net/famulus-notebook: antwortet
mac-studio: erreichbar über https://mac-studio.tail147011.ts.net/famulus-notebook
```

The first endpoint refused: the peer's service listens on its own machine only, not on its tailnet address. The second, the peer's name on the tailnet behind the platform proxy, answered, and is used.

A peer describes itself at `/api/peer`:

### Specimen · What a peer offers

```
{
 "service": "famulus-notebook",
 "version": "0.1.0",
 "machine": "studio-4.local",
 "engine": true,
 "notebooks": [
 "karman-nachlass/korrespondenz",
 "kepler-anima-vis/anima-vis",
 "kepler-lex-naturae/lex-naturae",
 "lehrbuch/lehrbuch",
 "..."
],
 "collections_root": "/Volumes/PDAI-1/pdai-collections",
 "capabilities": [
 "notebooks",
 "artefacts",
 "collections-read",
 "run-block",
 "partitur"
]
}
```

`capabilities` lists what the peer does for others: list its notebooks (`notebooks`), hand out its artefacts (`artefacts`), read its collections (`collections-read`), run a block (`run-block`), and run a Partitur (`partitur`). `engine: true` says that the query pipeline is installed there, so that subtasks can run.

## 11.3 Tokens

Between machines, every request carries a bearer token. The serving machine reads its token from the environment variable `FAMULUS_TOKEN`, or from the file named by `FAMULUS_TOKEN_FILE`, by default `~/.config/famulus/token`. The calling machine keeps the same token under the variable its `peers.yaml` names. A request without the token, or with a wrong one, is refused:

**Table 11** Access from the second machine to the first, measured on 24 September 2026.

| Request                        | Answer |
|--------------------------------|--------|
| peer description, no token     | 401    |
| peer description, wrong token  | 401    |
| peer description, with token   | 200    |
| read of a collection, no token | 401    |
| annotation, with token         | 403    |
| documentation site, no token   | 200    |

Two lines of Table 11 need a word. The annotation is refused even with the token (403): notes to the learning loop are taken from the owner's own machine only, so that a peer cannot fill the loop. The documentation site needs no token, because it holds no data. A machine inside a trusted tailnet may be admitted without a token by setting `FAMULUS_TRUST_TAILNET=1` on the serving machine; the tailnet's own addresses, 100.64.0.0/10, then pass.

A browser presents the token once, in the fragment of the address, `.../notebook#token=...`. The fragment never reaches a server or a log; the viewer sends it to the service a single time and receives a cookie in return.

**</> For famuli**

Never write a token into a notebook, a `peers.yaml`, a log or a message. Read it from the file where it is kept, put it into the variable that `token_env` names, and pass only the variable's name.

**11.4 Three ways to use a peer**

A block uses a peer in one of three ways. It reads a collection that lies on the peer; it reads an artefact that the peer has produced; or it lets the peer run the whole block. The notebook `zwei` ("two") of the second machine shows all three. The second machine has no collections, no orchestrator and no query pipeline; every block reaches the first machine, the peer `mac-studio`.

**11.4.1 Reading a collection**

A `duckdb` entry with the key `peer` is read on the peer:

```
duckdb:
- alias: main
 path: $PDAI_COLLECTIONS/pirckheimer/pirckheimer.duckdb
 peer: mac-studio
partiturs:
- id: duckdb-read
 input:
 sql: |
 SELECT direction, count(*) AS letters FROM letters_resolved
 GROUP BY direction ORDER BY direction
```

The SQL travels to the peer, the peer runs it on its copy of the database, and the rows come back: 45 letters from Pirckheimer to others (`P_to_X`), 309 to him (`X_to_P`). The peer is strict about what it runs for others. A remote read is one statement, `SELECT` or `WITH`; every file it names lies inside the one collection; external file access is switched off; at most 5000 rows are returned; and a query is stopped after 30 seconds.

**11.4.2 Reading a result**

A reference with the prefix `peer:<peer>/` names an artefact of the peer (a remote reference):

```
peer:mac-studio/fam:pirckheimer-briefwechsel/briefpartner-1520-1530/briefpartner-roster.roster
```

When the block runs, the artefact is fetched and kept in the project, under `_famulus/cache/extern/`, followed by the peer's name and the artefact's reference name:

```
_famulus/cache/extern/mac-studio/pirckheimer-briefwechsel/briefpartner-1520-1530/
briefpartner-roster/
 roster.json
 roster.source.json
```

The copy `roster.json` is the envelope as the peer produced it, with its version and checksum. `roster.source.json` records where it came from: the reference, the endpoint that answered, the time it was fetched, and the envelope's header. The block `roster-size` counts the entries of the copy and finds 75, the correspondents of the Pirckheimer project; the source record names version 1 of the roster.

A remote reference is fetched when the block runs, not when the notebook is checked: `famulus-notebook check` does not follow references to peers. The copy in `cache/extern` is what the block read; its source record is the evidence of which version that was.

### 11.4.3 Running a block

The key `engine` names a peer that runs the whole block (remote execution):

```
id: count-there
engine: mac-studio
subtask: correspondence-count
```

The block is sent to the peer's `/api/run-block`. The peer runs it in a package of its own, made for this one block, and returns the log: result, verdict, report, manifest and trace. The caller stores the log in its own project, under its own reference name, `fam:zwei/zwei/count-there.report`, and records the peer in the report's origin. Two things are not sent: a reference in the text of an instruction (`{ref:...}`), which names a file on the caller's machine, and a Partitur step with a `setting` file. A block that contains either is refused before anything is sent, with the reason.

### 11.5 Two machines at work

The notebook `zwei` was run on the second machine, a Mac mini reached over the tailnet:

#### Specimen · Two machines

```
$ famulus-notebook run zwei/zwei.fam
How many letters of the Pirckheimer register go in each direction? – wartet
How many correspondents does the roster of the Pirckheimer project on t... – wartet
How many correspondents did Pirckheimer have between 1520 and 1530? – wartet
How many letters of the Pirckheimer register go in each direction? – läuft
How many letters of the Pirckheimer register go in each direction? – ohne Oracle, v1
How many correspondents does the roster of the Pirckheimer project on t... – läuft
How many correspondents does the roster of the Pirckheimer project on t... – ohne Oracle
How many correspondents did Pirckheimer have between 1520 and 1530? – läuft auf mac-
studio
How many correspondents did Pirckheimer have between 1520 and 1530? – wartet
How many correspondents did Pirckheimer have between 1520 and 1530? – läuft
How many correspondents did Pirckheimer have between 1520 and 1530? – abweichend
{"blocks": {"by-direction": "pass", "roster-size": "pass", "count-there": "fail"}}

$ famulus-notebook status zwei
aktuell zwei/by-direction v1 pass
aktuell zwei/roster-size v1 pass
aktuell zwei/count-there v1 fail
zwei: 3 Blöcke, 0 nicht aktuell

the instruction of count-there gets its second sentence
$ famulus-notebook refresh zwei
How many letters of the Pirckheimer register go in each direction? – aus dem letzten
Lauf
How many correspondents does the roster of the Pirckheimer project on t... – aus dem
letzten Lauf
How many correspondents did Pirckheimer have between 1520 and 1530? – läuft auf mac-
studio
How many correspondents did Pirckheimer have between 1520 and 1530? – läuft
How many correspondents did Pirckheimer have between 1520 and 1530? – bestanden
zwei: 1 Blöcke gelaufen: zwei/zwei/count-there

$ famulus-notebook status zwei
aktuell zwei/by-direction v1 pass
aktuell zwei/roster-size v1 pass
aktuell zwei/count-there v1 pass
zwei: 3 Blöcke, 0 nicht aktuell
```

The transcript repeats Chapter 10 on a second machine. In the first run, the block `count-there` had the golden's question as its only sentence; it ran on `mac-studio`, answered from the letter list, and deviated from the oracle. The second sentence of the instruction was added, and `refresh` ran exactly this block, again on the peer. It passed. The other two blocks were taken from their last run. Because the failed run had written no artefact, the passing run wrote into version 1 (Chapter 7).

Appendix D gives the complete procedure for setting up a second machine, including the installation, the token, and the checks that must pass before the first remote run.

#### In short

- The owner revises; a commentator comments, through a share link for one rendered document.
- A peer is a named service in `peers.yaml`, with a kind, endpoints in the order they are tried, and the name of the variable holding its token.
- Between machines every request carries a bearer token; notes to the learning loop are taken only on the owner's machine.
- A block reads a peer's collection (`duckdb` with `peer`), a peer's artefact (`peer:` reference, copied to `cache/extern`), or runs on the peer (`engine`).

#### ✍ Exercise 11.1

Add a peer to your own `peers.yaml` with two endpoints, the first of which cannot answer. Run `famulus-notebook peers probe` and read which endpoint is chosen. How long does the probe of the first endpoint take at most?

#### ✍ Exercise 11.2

Write a remote read that returns the number of letters per year from the Pirckheimer register. Which of the following would the peer refuse, and why: a second statement after a semicolon; a `COPY` to a file; a join with a table of another collection?

#### ✍ Exercise 11.3

The block `count-there` ran on the peer. Where on the calling machine is its report stored, and what does the report name as its origin? Which field would change if the block ran locally?

## PART IV

# Publishing

## 12 From notebook to publication

A notebook is written to be run; a publication is written to be read. This chapter explains how the one becomes the other without a second source: how the runner turns a `.fam` file into a Quarto page, what that page knows about its results, how a paper cites a result by name, and what a project must contain when it is handed on.

### 12.1 One source, a shadow copy

The notebook file `ch03.fam` is the only source of Chapter 3's notebook. It is never rendered directly. Quarto would not know where the results of its blocks lie, and a renderer that looked for them itself would have to

repeat the runner's rules for versions and references. Instead the command `build` writes a shadow copy: a `.qmd` file with the same text as the notebook and one addition in its front matter.

#### Specimen · Building the companion project

```
$ cd site/projekte/lehrbuch
$ famulus-notebook build .
./_famulus/build/lehrbuch.qmd
./_famulus/build/ch01.qmd
./_famulus/build/ch02.qmd
./_famulus/build/ch03.qmd
./_famulus/build/ch04.qmd
./_famulus/build/ch06.qmd
./_famulus/build/ch07.qmd
./_famulus/build/ch08.qmd
```

The command names each shadow copy it wrote, one for every notebook of the project. They lie under `_famulus/build/`, beside the store, and are rewritten on every build; nothing in that folder is edited by hand. The addition is the block `famulus-build`:

#### Specimen · The front matter of the shadow copy `ch03.qmd` (paths shortened)

```

title: "Chapter 3: Results and their display"
famulus:
 id: ch03
famulus-build:
 notebook: lehrbuch/ch03
 source: ~/.../site/projekte/lehrbuch/kapitel/ch03.fam
 blocks:
 letters-by-year: ~/.../lehrbuch/_famulus/store/ch03/letters-by-year/v0001
 peak-year: ~/.../lehrbuch/_famulus/store/ch03/peak-year/v0001
 places: ~/.../lehrbuch/_famulus/store/ch03/places/v0003
 star: ~/.../lehrbuch/_famulus/store/ch03/star/v0002
 kepler-evidence: ~/.../lehrbuch/_famulus/store/ch03/kepler-evidence/v0001
 refs: {}

```

#### notebook

The notebook's name, project and notebook, as in a reference.

#### source

The `.fam` file the copy was made from.

#### blocks

For every block, the folder of its *current* version in the store. The block `places` has three versions; the copy points to the third, because `current.json` names it (Chapter 7).

#### refs

Every reference written as a shortcode in the text, resolved to a file. Chapter 3 has none, so the map is empty.

The build decides which version a page shows; the renderer only reads what the build wrote. A page built today and rendered tomorrow therefore shows the versions that were current when it was built, even if a block has run in between. Build again before you render.

The paths are absolute, because Quarto must find the files from wherever it runs. A shadow copy is therefore a product of one machine, like a compiled file. It is not handed on; it is rebuilt.

Relative links in the notebook, such as a link to `famulus.yml`, point from the chapter folder. The shadow copy lies elsewhere, so the build rewrites each relative link to point from the copy's own folder to the same file.

## 12.2 Rendering

The shadow copy is an ordinary Quarto document. It is rendered by the Quarto extension `famulus`, which the site carries under `_extensions/famulus/`. The extension does two things. It replaces every block, a code block of class `famulus`, by the question and the result of the version named in `famulus-build`, and it replaces every shortcode by the artefact it names.

In HTML the block becomes what the viewer shows (Chapter 3): the question, the Partitur folded under a summary line, the answer, the verdict as a chip, and the result in its display format. The formats `kennzahl`, `liste`, `tabelle`, `hierarchische-tabelle`, `belegliste` and `textkarten` are drawn by the extension itself; for `netz` it writes the list of nodes and a note that the network is drawn in the viewer. A block that has never run is not left blank. The page says *Noch kein Lauf*.

In a PDF the extension is more modest. It writes the question and the answer as two paragraphs. The verdict, the Partitur and the table are left out. Rendering the Pirckheimer notebook to Typst on 24 September 2026 produced four pages in which the roster's answer appears with its Markdown marks unconverted, `**75 distinct correspondents**` with the asterisks. This is a limit of the present extension, not of the notebook: the answer is written as plain text where it should be read as Markdown. A PDF that must show verdicts and tables is better made as this book was made (see below).

### For famuli

The extension's filter walks the document once. It reads `famulus-build` from the front matter, finds every code block with the class `famulus` or `{famulus}`, splits its text into preamble and instruction, and reads `result.json` and the first artefact from the block's version folder. The shortcode handler reads the resolved `refs` entry; if the entry is missing it writes *Verweis ... ist nicht aufgelöst (famulus-notebook build)*, rather than guessing a file. Nothing in the filter calls the runner.

## 12.3 The site

The documentation site of Famulus Notebook is itself built from notebooks. Without a target, `build` makes shadow copies of every project the site lists and writes them to `site/lesen/<project>/`:

```
$ famulus-notebook build
14 Schattenkopien unter site/lesen/, _quarto.yml nachgeführt
```

It also keeps the site's `_quarto.yml` in step. Between marker comments it rewrites three lists, the files to render, the entries of the navigation bar and those of the side bar:

```
famulus-notebook build: Anfang render
- lesen/karman-nachlass/korrespondenz.qmd
- lesen/kepler-anima-vis/anima-vis.qmd
...
- lesen/schoener-saphea/saphea.qmd
famulus-notebook build: Ende render
```

Everything outside the markers is left as it is; the site's own pages and settings belong to its author. The command `render` builds the site and then calls `quarto render` in the site folder. If Quarto is not installed it stops with the message *quarto fehlt: <https://quarto.org/docs/get-started/>*.

A single page can be rendered on its own, as any page of a Quarto project:

```
$ cd site
$ quarto render lesen/pirckheimer-briefwechsel/briefpartner-1520-1530.qmd
Output created: ../../_site/lesen/pirckheimer-briefwechsel/briefpartner-1520-1530.html
```

## 12.4 Citing a result

A paper that uses a result should name it so that a reader can find it. The name is the reference of Chapter 6, with the version:

```
fam:lehrbuch/ch07/span.span@v2
```

This names one file whose header (Chapter 7) states its checksum, the block that made it, the hash of that block's input and the model that ran. The version pins the content; without `@v2` the name means whatever is current when the reader looks. In prose, cite the version you read. A reader who finds a later version can compare the two with `diff` (Chapter 7).

A page built by the runner can also *show* a cited artefact. The shortcode `famulus` takes a reference and puts the artefact in its place:

```
{{< famulus briefpartner-roster roster >}}
{{< famulus fam:karman-nachlass/korrespondenz/karman-roster.roster >}}
```

The first form names a block of the same notebook and its artefact; the second names an artefact anywhere by its full reference. The build resolves each shortcode and records the file under `refs` in `famulus-build`. The extension then writes a table for artefacts of the kinds `table`, `roster-table`, `kwic` and `citation-list`, the text for `markdown`, and for every other kind a line with kind, reference, version and a link to the file.

## 12.5 How this book was made

This book does not use the extension. Its examples show the source of a block beside its result, which the extension does not do, and its PDF shows verdicts and tables, which the extension does not either. The book's own filter reads a file `examples.json` that a short program writes from the companion project:

```
$ ~/ai-mac-studio/development/famulus-notebook/.venv/bin/python tools/examples.py
```

The program is run with the notebook's own interpreter and reads the project through the notebook's own modules: the parser for the source lines of each block, the store for the current version, and `status` for whether the block is current. Every entry of `examples.json` carries the state of its block, and the program ends by printing the entries that are *not* current. It does not refuse to write them; the author reads the line before rendering. For this edition the line read *nicht aktuell: keins*, so every number in an example was produced by the run whose version the example names.

## 12.6 Handing on a project

A project is a folder. To hand it on, hand on the folder, with these parts:

**famulus.yml**

The project's name, its notebooks and its defaults (Chapter 5).

**\*.fam and kapitel/**

The notebooks, the only source.

**settings/**

Setting files the blocks name.

**\_famulus/store/**

Every version of every result, with `current.json` per block.

**famulus.lock**

For every block, the hash of its input, its status, its current version, the versions it consumed and the versions it produced.

Leave out `_famulus/build/` and `_famulus/cache/`: the one is rebuilt, the other refilled from peers.

The lock is written by the runner after every run. Its first line says so:

```
famulus.lock: vom Harness geschrieben. Welche Version aus welcher entstand.
project: lehrbuch
written: '2026-09-23T21:16:08+00:00'
blocks:
 ch01/first-list:
 input_hash: 9da2ff307d73ade4
 status: pass
 version: 1
 consumes:
 - ref: fam:lehrbuch/ch01/first-count
 version: 1
 sha: 717a35a74de26986
 produces:
 - name: partners
 version: 1
 sha: c29ff7ae41f4e702
```

What does the lock prove? Less than one might hope, and exactly what it says. It proves that the version it names was computed from an input with the named hash, and from the named versions of other results with the named checksums. It does not prove that the registers still hold the same data: the hash covers the notebook's text and the size and modification time of the local files a block reads, not their contents, and a collection on a peer is not covered at all (Chapter 14). A recipient who runs `famulus-notebook status` on the folder learns which blocks are current *on their own machine*; a block whose register differs, or is missing, is reported stale with the reason. That is the honest use of the lock: not as a certificate, but as the statement against which a second run is compared.

**In short**

- `build` writes a shadow copy per notebook; its `famulus-build` front matter names the current version of every block and resolves every shortcode.
- Build again before rendering; shadow copies are machine-specific and are not handed on.
- The Quarto extension renders blocks and shortcodes; in HTML with verdict and display, in PDF as question and answer only.
- Cite a result by its reference with version, `fam:p/n/b.a@vN`.
- Hand on the project folder without `build/` and `cache/`; the lock states which version came from which, and `status` checks it on the new machine.

**✍ Exercise 12.1**

Run `famulus-notebook build .` in the companion project, then run the block `ch03/places` again with `--force`. Which folder does the shadow copy of `ch03` name for `places` before and after a second build? When would they differ?

### ✎ Exercise 12.2

Write a paragraph for a paper that cites the number of letters of `ch07/span` so that a reader can check it. Which part of the reference would you leave out if you wanted the reader always to see the current count, and why is that a poor choice for a paper?

## 13 A casebook of six projects

The chapters so far used a small companion project written for teaching. This chapter reads six projects that were written for research. Each asks a few related questions of one collection, and most check at least one answer against an oracle. For each project the chapter gives the question, the blocks, the results, and, where they can be had, independent counts made in the registers on the same day. Where the notebook and the register disagree, the disagreement is stated and not resolved by choosing one.

The results are those of `examples.json`, written on 24 September 2026 from the current versions; every block was current when it was read. The six projects are written in German, and their questions are quoted as they stand. The independent counts were made with short read-only DuckDB connections to the same register files.

### 13.1 Pirckheimer's correspondents

The register `letters_resolved` of `pirckheimer.duckdb` holds 354 letters, all dated between 1520 and 1527. Pirckheimer wrote 45 of them (direction `P_to_X`); 309 are addressed to him. The project `pirckheimer-briefwechsel` asks three questions of it: how many correspondents, who they were, and how the letters are distributed among them.

```
SOURCE
```{famulus}
---
id: briefpartner-zahl
years: {from: 1520, to: 1530}
subtask: correspondence-count
golden: golden-c782fab71c
display: kennzahl
oracle:
  n_correspondents: 75
duckdb: ...
artefacts: ...
---
Wie viele Briefpartner hatte Pirckheimer
zwischen 1520 und 1530? Zähle verschiedene
Personen aus letters_resolved, aufgelöst über
ent_canonical.
```
```

#### RESULT

**75** n\_correspondents expected = 75

**Example 13.1.** `fam:pirckheimer-briefwechsel/briefpartner-1520-1530/briefpartner-zahl · v1 · passed`

The golden `golden-c782fab71c` expects 75, and the block passes. The roster that follows lists the same 75 names; the most active correspondent is the town council of Donauwörth with 127 letters, then Erasmus with 21 and Klara Pirckheimer with 20:

SOURCE

```
```{famulus}
---
id: briefpartner-roster
depends_on: [briefpartner-zahl]
years: {from: 1520, to: 1530}
display: tabelle
partiturs:
- id: query/historical/stage-one
  setting:
    settings/pirckheimer-1520-1530.setting.yaml
  input:
    subtask: correspondence-roster
  artefact: roster
artefacts:
- name: roster
  kind: roster-table
  file: roster.json
---
Liste die Briefpartner Pirckheimers von 1520
bis 1530. Jede Zeile nennt den kanonischen
Namen, die Schreibvarianten und die Anzahl der
Briefe.
```
```

RESULT

| name          | canonical | aliases | kind          | count | n_docs    | doc_id | first_date | last_date |
|---------------|-----------|---------|---------------|-------|-----------|--------|------------|-----------|
| Donauwörth    | List      |         | correspondent | 127   | List      | 1525   | 1527       |           |
| Bürgermeister |           |         |               |       | {br965,   |        |            |           |
| und           |           |         |               |       | br970,    |        |            |           |
| Rat           |           |         |               |       | br967,    |        |            |           |
| von           |           |         |               |       | br995,    |        |            |           |
|               |           |         |               |       | br991,    |        |            |           |
|               |           |         |               |       | br985,... |        |            |           |
| Erasmus       | List      |         | correspondent | 21    | List      | 1522   | 1525       |           |
| Desiderius    |           |         |               |       | {br760,   |        |            |           |
|               |           |         |               |       | br762,    |        |            |           |
|               |           |         |               |       | br764,    |        |            |           |
|               |           |         |               |       | br776,    |        |            |           |
|               |           |         |               |       | br778,    |        |            |           |
|               |           |         |               |       | br782,... |        |            |           |
| Pirckheimer   | List      |         | correspondent | 20    | List      | 1523   | 1525       |           |
| Klara         |           |         |               |       | {br779,   |        |            |           |
|               |           |         |               |       | br881,    |        |            |           |
|               |           |         |               |       | br884,    |        |            |           |
|               |           |         |               |       | br918,    |        |            |           |
|               |           |         |               |       | br910,    |        |            |           |
|               |           |         |               |       | br917,... |        |            |           |
| Schönerr      | List      |         | correspondent | 11    | List      | 1524   | 1525       |           |
| Johann        |           |         |               |       | {br814,   |        |            |           |
|               |           |         |               |       | br831,    |        |            |           |
|               |           |         |               |       | br837,    |        |            |           |
|               |           |         |               |       | br840,    |        |            |           |
|               |           |         |               |       | br872,    |        |            |           |
|               |           |         |               |       | br933,... |        |            |           |
| Pirckheimer   | List      |         | correspondent | 10    | List      | 1524   | 1525       |           |
| Sabina        |           |         |               |       | {br830,   |        |            |           |
|               |           |         |               |       | br863,    |        |            |           |
|               |           |         |               |       | br877,    |        |            |           |
|               |           |         |               |       | br925,    |        |            |           |
|               |           |         |               |       | br940,    |        |            |           |
|               |           |         |               |       | br944,... |        |            |           |
| Grieninger    | List      |         | correspondent | 9     | List      | 1522   | 1525       |           |
| Johann        |           |         |               |       | {br765,   |        |            |           |
|               |           |         |               |       | br844,    |        |            |           |
|               |           |         |               |       | br850,    |        |            |           |
|               |           |         |               |       | br879,    |        |            |           |
|               |           |         |               |       | br898,    |        |            |           |
|               |           |         |               |       | br906,... |        |            |           |

... 69 more rows

**\*\*75 distinct correspondents\*\*** between 1520 and 1530 in the `pirckheimer` register (200 dated letters in scope). Most active: - **\*\*Donauwörth, Bürgermeister und Rat von\*\*** — 127 letter(s) (1525–1527) - **\*\*Erasmus, Desiderius\*\*** — 21 letter(s) (1522–1525) - **\*\*Pirckheimer, Klara\*\*** — 20 letter(s) (1523–1...

Example 13.2. fam:pirckheimer-briefwechsel/briefpartner-1520-1530/briefpartner-roster · v1 · unchecked

The third block, `briefpartner-netz`, reads the roster by reference and draws a star around Pirckheimer with the letter count as the weight of each edge. It is a local step, `artifact:d3-graph`, and uses no model. Its answer says that it shows 60 of the 75 correspondents.

**Against the register.** Counting the distinct persons opposite Pirckheimer in all 354 letters (the recipient when he writes, otherwise the sender) gives 77, not 75. No letter lacks the person. Which count underlies the golden’s 75 is not recorded with the golden. Until it is, *bestanden* on this block means agreement with the golden, not with the register.

The roster’s answer names its basis: *200 dated letters in scope*. The register holds 354. The query mapper of the pipeline ends its statements with a limit of 200 rows, and the answer reports the limit as if it were the scope. The register dates its letters by year only, so which 200 letters a limit keeps depends on an order within the year that the register does not fix. Ordered by year and letter number, the first 200 letters have exactly 75 partners. The golden’s 75 may therefore be a product of the limit; the register does not say, and neither does the golden.

## 13.2 Schöner and the *saphea*

The project `schoener-saphea` asks what Johann Schöner’s letters to Pirckheimer are about, which technical terms he uses when he describes sundials, and what the correspondence says about his *Canones Sapheae*. The register has 11 letters from Schöner, all addressed to Pirckheimer.

```
SOURCE
```{famulus}
---
id: schoener-gegenstand
years: {from: 1520, to: 1527}
subtask: letter-subject
golden: golden-b4544be016
display: textkarten
guard: {task: synthesize-answer, lang: de}
oracle:
  n_letters: 11
  subject_contains: saphea
duckdb: ...
artefacts: ...
---
Was ist der Gegenstand der Briefe von Schöner
an Pirckheimer zwischen 1520 und 1527? Gib eine
zusammenhängende Darstellung und die Briefzahl.
```
```

### RESULT

These correspondence excerpts primarily feature letters from Schöner to an influential patron and magistrate (addressed as “herrligkeit,” and identified elsewhere as Willibald Pirckheimer), alongside related monastic and personal communications. A central topic is Schöner’s ongoing pursuit of a church benefice permutation involving Heroldsberg, Erenpach, and Bamberg, accompanied by expressions of anxiety over bureaucratic delays, gossip, and negotiations with local peasants and collators. Schöner also frequently discusses the acquisition, casting, and correction of astronomical and mathematical instrument matrices—specifically concerning a device called a “saphea” and work with Johann Stüchs—as well as the dispatch of related treatises (*canones cylindri* and *Canones Sapheae*). In addition, the letters touch upon scholarly praise for Pirckheimer’s translation of Ptolemy and his civic virtue, personal financial or living arrangements, and concerns regarding religious and monastic hardships during the period, including the plight of nuns at St. Clare and local weather damage to crops.

**Example 13.3.** `fam:schoener-saphea/saphea/schoener-gegenstand · v1 · passed`

The oracle requires 11 letters and a subject that contains the word *saphea*. Both hold, and the block passes. The block is checked by the formulation guard as well (`guard`), because its answer is a written summary.

The block declares an artefact of kind `markdown` in the file `gegenstand.md`. The file contains a roster table with no entries; the summary itself is only in the answer. This has a consequence for versions (Chapter 7). When the block ran again on 24 September, its answer was a different summary, but the artefact was unchanged, and the runner reported *bestanden, v1 unverändert*. A new text under an old version number is what the version rule forbids; here it follows from the block keeping its result where the rule does not look.

```

SOURCE
```{famulus}
---
id: schoener-termini
depends_on: [schoener-gegenstand]
years: {from: 1520, to: 1527}
subtask: terminology-find
golden: golden-schoener-sundial-terms
display: liste
oracle:
  terms: [saphea, horologium]
artefacts:
  - name: termini
    kind: kwic
    file: termini.json
---
Welche technischen Termini gebraucht Schöner in
seinen Briefen, wenn er Sonnenuhren beschreibt?
Lege die Belege als KWIC ab, mit doc_id, pidx
und sent_idx.
```

```

## RESULT

| Name         | Zahl |
|--------------|------|
| horologium   |      |
| saphea       |      |
| instrumentum |      |
| umbra        |      |

\*\*1 document(s)\*\* matched via lemma/stanza index for:  
 Query: Schöner, Johann, Schoner, Léger; lemmata: wenn  
 AND als AND mit; in pirckheimer. - [pirckheimer/  
 korrespondenz] Nam et globos tam celi quam terrae  
 composuit equatoriumque cum planetarum motu  
 inpressit cum multis aliis chilindris, horologii...

**Example 13.4.** fam:schoener-saphea/saphea/schoener-termini · v1 · passed

The terms block passes: of ten candidate terms, four are attested in the letters, and *saphea* and *horologium* are among them. The lemma decomposition that the pipeline records for the question is *wenn AND als AND mit*, three German function words taken from the instruction. The answer is right in spite of its recorded grounds.

The third block asks for statements about the *Canones Sapheae* and instructs the pipeline to report a gap if it extracts none. It has no oracle and runs with `rerun: always`. The pipeline reports 20 statements from 5 authors in 9 letters. The persons it names as its query entities are *Lucke, C. E., Wenner, Frank, Wienn*: the German word *Lücke* of the instruction, matched against a person register of another collection. The viewer shows *ohne Oracle*, which is correct. The answer is not supported by its own grounding, and the notebook shows both side by side.

### 13.3 Kepler: *lex* and *natura*

The project `kepler-lex-naturae` asks in which sentences of Kepler's Latin works the lemmata *lex* and *natura* occur together, in counting mode `canonical`. The notebook records a register truth of 12 August 2026, 45 sentences in 16 documents, and sets the oracle as floors.



The pipeline reports 45 sentences in 16 documents and passes. Its recorded lemma decomposition is *lateinischen AND denen AND lex/legis AND natura/naturae*: two words of the German instruction were taken as Latin lemmata. That the count is nevertheless right shows that a later stage ignores them; the recorded decomposition is still wrong.

The counter-check reads the same sentences without the pipeline. It is a local step that joins the lemma index with the sentence table on the triple (`doc_id`, `pidx`, `sent_idx`), the identity of a sentence, and keeps the Latin ones:

```
SOURCE
```{famulus}
---
id: lex-natura-gegenprobe
depends_on: [lex-natura]
display: tabelle
duckdb:
  - alias: stz
    path:
      $PDAI_COLLECTIONS/kepler-prim/kepler-
prim_stanza.duckdb
    read_only: true
  - alias: lemma
    path:
      $PDAI_COLLECTIONS/kepler-prim/
lemma_index.parquet
    read_only: true
partiturs:
  - id: duckdb-read
    input:
      sql: |
        WITH hits AS (
          SELECT doc_id, pidx, sent_idx
          FROM
            read_parquet('$PDAI_COLLECTIONS/kepler-
prim/lemma_index.parquet')
          WHERE lemma IN ('lex', 'natura') AND
            upos = 'NOUN'
          GROUP BY doc_id, pidx, sent_idx
          HAVING count(DISTINCT lemma) = 2
        )
        SELECT s.doc_id, s.pidx, s.sent_idx,
          s.text
        FROM stz.stz_sentences AS s
        JOIN hits AS h
          USING (doc_id, pidx, sent_idx)
        WHERE s.lang = 'la'
    artefact: gegenprobe
artefacts: ...
oracle:
  n_sentences: {min: 15}
---
Lies dieselben lateinischen Sätze direkt aus
dem Lemma-Index und stz_sentences. Die
Satzidentität ist das Tripel (doc_id, pidx,
sent_idx).
```
```

## RESULT

| doc_id   | pidx | sent_idx | text                                                  |
|----------|------|----------|-------------------------------------------------------|
| kgw-08   | 224  | 0        | 104 Principiò non planè<br>negabo, pestilentiam no... |
| kgw-08   | 253  | 12       | Adeoque non erat opus 30<br>Cometâ ad praesignific... |
| kgw-11-1 | 43   | 2        | Cum igitur harum septem<br>circuli divisionum, res... |
| kgw-11-2 | 364  | 6        | Longè enim abest, vt nos,<br>147 qui sumus homines... |

... 40 more rows

44 Sätze.

**Example 13.6.** `fam:kepler-lex-naturae/lex-naturae/lex-natura-gegenprobe · v1 · passed`

It finds 44 sentences in 16 documents, one fewer than the pipeline and the recorded truth. The counter-check restricts both lemmata to nouns, and one might think that the missing sentence has one of them in another part of speech. It does not: without the condition the lemma index still gives 44, and so does the token table `stz_tokens` of the sentence corpus. On 24 September 2026 the register therefore holds 44 such sentences by two independent routes. Where the pipeline's 45 comes from is not recorded, and the notebook keeps both numbers until it is.

### 13.4 Kepler: from *anima* to *vis*

In the *Mysterium Cosmographicum* of 1596 a soul, the *anima motrix*, moves the planets. In a note to the second edition of 1621 Kepler writes that one should read *Vis* for *Anima*. The project `kepler-anima-vis` uses the language institution LWgrammar, which holds meanings relative to author, work and period, and asks three

questions: which meanings it records, where the change is attested, and whether a passage can be placed by its language alone.

```
SOURCE
```{famulus}
---
id: bedeutungen
display: tabelle
partiturs:
- id: lwgrammar:lw_sense_history
  input:
    term_ids: anima,vis
    author: kepler
artefacts:
- name: bedeutungen
  kind: table
  file: bedeutungen.json
oracle:
  n_rows: {min: 2}
---
Datierte Bedeutungen von anima und vis bei
Kepler mit Werk, Zeitspanne und Zusammenhang
der Diskussion.
```
```

## RESULT

| author | definition        | discussable | stoltest | sense_id | term_id    | work           |
|--------|-------------------|-------------|----------|----------|------------|----------------|
| kepler | The cosmogony     | 1596        | anima    | #kepler  | #Mysterium |                |
|        | moving the        |             |          |          |            | Cosmographicum |
|        | soul cause        |             |          |          |            |                |
|        | (anima of         |             |          |          |            |                |
|        | motrix) planetary |             |          |          |            |                |
|        | as motion         |             |          |          |            |                |
|        | the (Mys...       |             |          |          |            |                |
|        | cause             |             |          |          |            |                |
|        | tha...            |             |          |          |            |                |
| kepler | The celestial     | 1609        | 1621     | vis      | #kepler    | #Astronomia    |
|        | moving physics:   |             |          |          |            | Nova           |
|        | power the         |             |          |          |            |                |
|        | (vis moving       |             |          |          |            |                |
|        | or power          |             |          |          |            |                |
|        | virtus in         |             |          |          |            |                |
|        | motrix) the       |             |          |          |            |                |
|        | in body...        |             |          |          |            |                |
|        | the               |             |          |          |            |                |
|        | ...               |             |          |          |            |                |

2 n\_rows.

**Example 13.7.** fam:kepler-anima-vis/anima-vis/bedeutungen · v1 · passed

The first block is a local step, `lwgrammar:lw_sense_history`, and reads two dated meanings. The second reads the note itself from the sentence corpus:

```
SOURCE
```{famulus}
---
id: anmerkung-1621
depends_on: [bedeutungen]
display: belegliste
duckdb: ...
partiturs:
- id: duckdb-read
  input:
    sql: |
      SELECT doc_id, pidx, sent_idx, text
      FROM stz.stz_sentences
      WHERE doc_id = 'kgw-08' AND pidx = 109
      AND sent_idx BETWEEN 16 AND 22 AND
      lang = 'la'
      ORDER BY sent_idx
artefacts: ...
oracle:
  n_sentences: {min: 7}
---
Lies die lateinischen Sätze 16 bis 22 der Seite
109 von kgw-08.
```
```

## RESULT

kgw-08 · 109 · 16  
(3) Vnam esse motricem animam.]

kgw-08 · 109 · 17  
*Si pro voce Anima, vocem Vim substituas, habes ipsissimum principium, ex quo Physica Coelestis in Comment.*

kgw-08 · 109 · 18  
*Martis 20 est constituta, et lib. IV.*

kgw-08 · 109 · 19  
*Epitomes Astr.*

kgw-08 · 109 · 20  
*exulta.*

kgw-08 · 109 · 21  
*Olim enim causam mouentem Planetas absolute animam esse credebam, quippe imbutus dogmatibus I. C. † SCALIGERI, de Motricibus intelligentiis.*

kgw-08 · 109 · 22  
*At cum perpenderem, hanc causam motricem debilitari cum distantia, lumen Solis etiam attenuari cum distantia à Sole: hinc conclusi, Vim hanc esse corporeum aliquid, si non proprie, saltem aequiuoce; sicut lumen dicimus esse aliquid corporeum, id est, speciem ...*

7 Sätze.

**Example 13.8.** fam:kepler-anima-vis/anima-vis/anmerkung-1621 · v1 · passed

Sentence 17 is the substitution, *Si pro voce Anima, vocem Vim substituas*. The third block gives LWgrammar a passage of the *Astronomia nova* of 1609, the Latin sentences of pages 236 and 237 of kgw-03, without saying where it comes from, and excludes that work from the comparison profiles:

```
SOURCE
```{famulus}
---
id: verortung
depends_on: [anmerkung-1621]
display: tabelle
duckdb: ...
partiturs:
- id: duckdb-read
  input:
    sql: |
      SELECT doc_id, pidx, sent_idx, text
      FROM stz.stz_sentences
      WHERE doc_id = 'kgw-03' AND pidx
        BETWEEN 236 AND 237 AND lang = 'la'
      ORDER BY pidx, sent_idx
- id: lwgrammar:lw_situate_specimen
  input:
    text_from: text
    lang: la
    exclude: kgw-03
artefacts:
- name: verortung
  kind: table
  file: verortung.json
oracle:
  n_tokens: {min: 250}
---
Verorte das Textstück allein über seine
Sprache: nächster Autor, geschätztes Jahr und
Zeitfenster, Zusammenhang der Diskussion und
datierte Bedeutungen.
```
```

## RESULT

| author | validation     | lang | text | tokens | year     | estimate |
|--------|----------------|------|------|--------|----------|----------|
| kepler | correspondence |      |      | 850    | bestimmt | 1605     |

# Situierung – bestimmt - Tokens: 850 - Autor (Delta): kepler 2.6619 → kepler - Jahr (Stil): ~1605, Fenster [1596, 1619] - Diskussionskontext (nächstes Profil): correspondence - Bedeutung vis#kepler#motrix: 2  
Treffer; registrierte Periode 1609–1621; Marker belegt in kgw-01 (1596), kgw-07 (1621), k...

**Example 13.9.** fam:kepler-anima-vis/anima-vis/verortung · v1 · passed

The placement names Kepler as the nearest author and estimates the year as 1605, with a style window from 1596 to 1619; the passage is from 1609. It does not hit the context of the discussion: the nearest profile is a volume of letters (kgw-14, 1599–1603), and the result says *correspondence*. The notebook's own text states why the estimate should be read with care: in a cross-validation over the Kepler works, recorded there, the style estimate is off by 8.8 years on average, against 9.4 years for guessing the mean year of the other works. What carries the dating is the dated meaning vis#kepler#motrix, whose entry records the use from 1609 to 1621.

All three blocks record gemini-3.5-flash-lite as their model under herkunft, although none of them calls a language model. The runner fills the field from the project's default client unless every step is duckdb-read or artifact:<kind>; the LWgrammar steps are not in that exception, so bedeutungen and verortung are named with a model they did not use. anmerkung-1621 is a pure duckdb-read, for which the current code leaves the field empty; its result is from its only run and was taken over since, so it still carries what an earlier runner wrote.

### 13.5 Kármán's correspondence and manuscripts

The papers of Theodore von Kármán (karman-nachlass) hold 15,976 letters in letters\_resolved. The project asks who corresponded with Kármán in the 1930s, who mentions Einstein in letters to him, and what manuscripts the papers contain.

SOURCE

```
```{famulus}
---
id: karman-roster
years: {from: 1930, to: 1940}
subtask: correspondence-roster
golden: ground-K1-karman-correspondents
display: tabelle
oracle:
  n_unique: {min: 200}
duckdb: ...
artefacts:
  - name: roster
    kind: roster-table
    file: roster.json
---
Wer korrespondierte mit Kármán zwischen 1930
und 1940? Liste die kanonischen Namen aus
ent_canonical und die Briefzahl je Person.
```
```

RESULT

| name      | canonical | links | kind          | count | n_docs | doc_id                                   | first_date | last_date  | q |
|-----------|-----------|-------|---------------|-------|--------|------------------------------------------|------------|------------|---|
| Barnes    | true      | List  | correspondent | 98    | 98     | List                                     | 1930-01-19 | 1940-07-08 |   |
| D.        |           | {}    |               |       |        | {106-16_hydraulics_general_correspondent |            |            |   |
| P.        |           |       |               |       |        |                                          |            |            |   |
| Herzfeld  | true      | List  | correspondent | 98    | 98     | List                                     | 1930-02-23 | 1930-02-04 |   |
| H.        |           | {}    |               |       |        | {13-3_herzfeld_h_1921_1933_i/026,        |            |            |   |
|           |           |       |               |       |        | 109-12_p...                              |            |            |   |
| Putnam    | true      | List  | correspondent | 95    | 95     | List                                     | 1935-09-19 | 1940-12-24 |   |
| P.        |           | {}    |               |       |        | {111-9_wind_mills_and_turbines/011,      |            |            |   |
| C.        |           |       |               |       |        | 111-9_...                                |            |            |   |
| Condrone  | true      | List  | correspondent | 75    | 75     | List                                     | 1930-06-19 | 1940-11-20 |   |
| T. L.     |           | {}    |               |       |        | {102-3_bridges_suspension_tacoma_nar     |            |            |   |
| Pettersen | true      | List  | correspondent | 51    | 51     | List                                     | 1940-01-23 | 1940-10-25 |   |
| Sverre    |           | {}    |               |       |        | {111-14_wind_mills_and_turbines/037,     |            |            |   |
|           |           |       |               |       |        | 112-1...                                 |            |            |   |
| Roper     | true      | List  | correspondent | 46    | 46     | List                                     | 1934-08-29 | 1940-11-08 |   |
| James     |           | {}    |               |       |        | {106-10_hydraulics_general_correspondent |            |            |   |
| H.        |           |       |               |       |        |                                          |            |            |   |

... 740 more rows

746 distinct correspondents from the karman-nachlass letters\_resolved register between 1930 and 1940 (200 dated letters).

Example 13.10. fam:karman-nachlass/korrespondenz/karman-roster · v1 · passed

The block passes its floor of 200. Its answer, *746 distinct correspondents ... (200 dated letters)*, cannot describe one set: 746 persons do not fit into 200 letters. The number 200 is the row limit seen above.

**Against the register.** The register has 2,882 letters with a year from 1930 to 1940. How many persons corresponded with Kármán in them depends on a definition the question does not fix:

Table 12 Three readings of the Kármán question in the register, 24 September 2026.

| Reading of <i>correspondent</i>                         | Persons |
|---------------------------------------------------------|---------|
| every person on either side, other than Kármán          | 841     |
| the sender, or the recipient where Kármán is the sender | 747     |
| the other party, in letters of which Kármán is a party  | 490     |

The pipeline’s 746 is close to the second reading, which takes the sender of every letter that Kármán did not write, whether or not it was addressed to him. In 1,253 of the 2,882 letters neither side is the entity 8, Kármán’s entry in the person register. The floor of 200 is met by all three readings and so decides nothing between them. The question should name its reading; the oracle should then state its number.

SOURCE

```{famulus}  

id: einstein-erwaehnung
depends_on: [karman-roster]
persons: ["Albert Einstein"]
subtask: mention-in-letters
golden: ground-K3-karman-einstein
display: belegliste
oracle:
 n_letters: {min: 3}
artefacts: ...

Wer nennt Einstein in Briefen an Kármán? Gib je
Beleg den Brief, den Absender und die
Koordinaten doc_id, pidx, sent_idx.
```

RESULT

0 letter(s) addressed to Koordinaten in the register; 0  
have linked page text; 0 have body mentions of  
'Einstein'; 0 are cited in the person index; 0 distinct  
correspondent(s): —.

Example 13.11. fam:karman-nachlass/korrespondenz/einstein-erwaehnung · v1 · deviates

This block fails, and it fails honestly. The question asks for the coordinates `doc_id`, `pidx`, `sent_idx` of each piece of evidence. The pipeline read the German word *Koordinaten* as the name of a recipient and looked for letters addressed to a person of that name. There are none, so the observed value is empty and the verdict is *abweichend*. In the register, the summary field `regist` names Einstein in 32 letters. In the report of 23 September 2026 the same question passed with 38, which were documents of the whole collection, not letters to Kármán. The present failure tells the reader more about the pipeline than that pass did.

SOURCE

```{famulus}  

id: manuskripte
subtask: manuscript-inventory
golden: golden-karman-manuscripts-inventory
display:
 format: hierarchische-tabelle
 gruppe: kind
 spalten:
 - feld: name
 label: Titel
 - feld: count
 label: Seiten
 art: zahl
oracle:
 n_manuscripts: {min: 190}
 n_pages: {min: 5600}
artefacts:
 - name: bestand
 kind: roster-table
 file: bestand.json

Wie viele Manuskripte liegen im
Kármán-Nachlass? Nenne je Manuskript Datum,
Umfang in Seiten, Titel, Gegenstand und Zweck.
```

RESULT

Book Manuscripts

Titel	Seiten
Cours De Mecanique Des Fluides (I)	70
Cours De Mecanique Des Fluides (I)	70
Cours De Mecanique Des Fluides (II)	70
Cours De Mecanique Des Fluides (II)	70
Cours De Mecanique Des Fluides (III)	29
Cours De Mecanique Des Fluides (III)	8

Manuscripts & Notes (General)

Titel	Seiten
Manuscripts & Notes (General)	7
Manuscripts & Notes (General)	5
Manuscripts & Notes (General)	8
Manuscripts & Notes (General)	7
Manuscripts & Notes (General)	10
Manuscripts & Notes (General)	15

... 177 more rows

191 Manuskripte, 5619 Seiten.

Example 13.12. fam:karman-nachlass/korrespondenz/manuskripte · v1 · passed

The inventory passes its floors of 190 manuscripts and 5,600 pages. The artefact has 191 entries in three groups: 142 technical manuscripts and notes, 41 general ones, 8 book manuscripts. Of the 191 entries only 32 titles are distinct, and 63 entries are exact copies of another entry, title, group and page count alike; the first two rows above show one such pair. Whether 191 counts manuscripts, folders, or rows of a join is not stated by the inventory, and the floor was set from the same count.

13.6 Checking the checker: LWgrammar on a damaged paper

In September 2026 a revision run of the Lektor changed 136 paragraphs of the paper *famulus-plattform*. It inserted judgements, foreign words and new claims. The formulation check of LWgrammar compares each

changed paragraph with its version of 9 September. The project `lwgrammar-evaluation` reads the results of that comparison and runs the check on one paragraph.

```
SOURCE
```{famulus}
---
id: golden-zurueckweisung
display: kennzahl
partiturs: ...
artefacts:
  - name: zurueckweisung
    kind: table
    file: zurueckweisung.json
oracle:
  zurueckgewiesen: {min: 130}
  kontrollen_verfehlt: {max: 0}
---
Veränderte Absätze des Lektoratslaufs, von der
Formulierungsprüfung zurückgewiesene Fassungen
und die Kontrollen: jeder Absatz vom 9.
September, gegen sich selbst geprüft.
```
```

```
RESULT
136 veraendert
133 zurueckgewiesen
0.978 quote
0 kontrollen_verfehlt
```

**Example 13.13.** `fam:lwgrammar-evaluation/famulus-plattform/golden-zurueckweisung · v1 · passed`

The check rejects 133 of the 136 changed paragraphs (97.8 %). The oracle has two parts, and the second matters as much as the first: every paragraph of 9 September, checked against itself, must pass. A check that rejected everything would meet the first part; the second rules it out. None of the controls fails.

```
SOURCE
```{famulus}
---
id: golden-befunde
depends_on: [golden-zurueckweisung]
display: tabelle
partiturs: ...
artefacts:
  - name: befunde
    kind: table
    file: befunde.json
oracle:
  n_sentences: {min: 5}
---
Zahl der Fassungen je Befund. Eine Fassung kann
mehrere Befunde tragen.
```
```

```
RESULT
```

| metrik                 | fassungen |
|------------------------|-----------|
| added_modifiers        | 101       |
| foreign_vocabulary     | 93        |
| logical_particles      | 90        |
| register_lift          | 84        |
| added_claims           | 56        |
| preservation           | 44        |
| intensifier_insertions | 41        |
| length_ratio           | 37        |

... 6 more rows

14 Sätze.

**Example 13.14.** `fam:lwgrammar-evaluation/famulus-plattform/golden-befunde · v1 · passed`

The findings are counted per version, and one version can carry several. Added modifiers are the most frequent finding (101), then foreign vocabulary (93) and changed logical particles (90).

```
SOURCE
```{famulus}
---
id: dreiweg
display: tabelle
partiturs: ...
artefacts:
  - name: dreiweg
    kind: table
    file: dreiweg.json
oracle:
  n_sentences: {min: 2}
---
Wörter, eingefügte Bewertungen und
Verstärkungswörter, zugeordnete und voll
erhaltene Absätze der beschädigten und der
neuen Fassung, jeweils gegenüber der Fassung
vom 9. September.
```
```

```
RESULT
```

| fassung    | woert | bewertungen | erstaerke | zugeordnet | erhalten |
|------------|-------|-------------|-----------|------------|----------|
| beschädigt | 7574  | 7           | 49        | 101        | 70       |
| neu        | 7604  | 0           | 0         | 77         | 16       |

2 Sätze.

**Example 13.15.** `fam:lwgrammar-evaluation/famulus-plattform/dreiweg · v1 · passed`

The three-way comparison sets the damaged version and a later, new version of the paper against the version of 9 September. The damaged version keeps more paragraphs whole (70 against 16) and still carries 7 judgements and 49 intensifiers; the new version carries none. The damage was in the words, not in the claims. The new version is a rewrite with new claims, which is why so few of its paragraphs keep every claim of the old one.

The last two blocks run the check on one paragraph in the notebook itself, through the local step `lwgrammar:lw_evaluate`. The damaged version fails six blocking metrics, among them an added claim (rule R-LG-024) and evaluative insertions (rule R-LG-021); the paragraph checked against itself fails none.

The project's abstract speaks of 137 changed paragraphs; the result of the comparison has 136. The abstract is the author's text and was written before the last run. The notebook puts the two numbers on one page, which is how the difference was found; the abstract is still to be corrected.

### 13.7 What the six projects show

Of the 19 blocks read in this chapter, 16 carry an oracle. Fifteen pass, and one fails (Einstein). Three carry none and are shown as such.

The passes are of three kinds. Some agree with an independent count in the register: Schöner's 11 letters, the Kepler note, the LWgrammar controls. Some agree with an oracle whose relation to the register is not recorded: Pirckheimer's 75 against the register's 77, Kepler's 45 against 44. And some meet a floor that every plausible reading of the question also meets: Kármán's 746 and 191. A pass of the third kind tells the reader that the answer is not absurd, and nothing more.

The failures of the pipeline that these projects make visible are recurring ones. Words of the German instruction enter the lemma decomposition (Kepler, Schöner) or the person search (*Lücke*, *Koordinaten*). A row limit is reported as the scope of an answer (Pirckheimer, Kármán). A block keeps its result in its answer rather than in its artefact, so that a changed result keeps its version (Schöner). And a result names a model that did not run (Kepler *anima/vis*).

None of this would have been visible in a chat window. It became visible because each answer stands next to its oracle, its trace, and, where possible, a second reading of the same data. The notebook does not make the pipeline right. It keeps the grounds for accepting or rejecting an answer in the same place as the answer.

#### In short

- A pass means agreement with the oracle. What that means for the register depends on how the oracle was set.
- A floor that every reading of a question meets decides nothing between the readings.
- A second reading of the same data, by a local step, is the cheapest check a notebook can carry.
- Keep a result in its artefact; the version rule looks only there.

#### ✍ Exercise 13.1

Write the Kármán roster question so that it names the third reading of Table 12. Which oracle would you set, and why is a floor of 200 no longer appropriate?

#### ✍ Exercise 13.2

The Kepler counter-check and the pipeline differ by one sentence. Write a block that lists the sentences the pipeline reports and that the counter-check does not. Which artefact of `lex-natura` would it have to read, and does that artefact carry the sentence coordinates?

## PART V

## Beneath the surface

### 14 How a block is executed

The earlier chapters described what a block does as seen from the notebook: it is current or stale, it passes or deviates, it makes a version or keeps one. This chapter describes how the runner brings that about. You need it when a result surprises you, when you write a Partitur for notebooks, or when you want to know exactly what the lock of Chapter 12 proves. The chapter follows one command, `famulus-notebook run`, from the project folder to the files in the store.

#### 14.1 From a project to its blocks

The command takes a project folder or a single `.fam` file. The runner finds the project by walking up from the path to the nearest `famulus.yml`, and takes the project's notebooks from it. A project with one notebook runs that notebook. A project with several runs them in the order of their references: a notebook that reads a result of another notebook of the same project, with `@latest` or `@locked`, runs after it. A cycle between notebooks is refused before anything runs, with the message *Zyklus zwischen Notebooks: ....*

The command `refresh` adds one step. Before the project's own notebooks it runs every other local project whose results the project reads with `@latest`, producers first. A reference to a peer is not followed: the peer's results are fetched when a block reads them, and they are not run from here.

Within a notebook the runner first checks that no block id occurs twice (*doppelte Block-id*). It then determines which blocks to consider: all of them, or, with `--block`, the named block together with every block it needs through `depends_on` that has no manifest yet. Each of these is announced as waiting; the viewer shows the sentence *wartet*. The runner then works in rounds. In each round it takes every waiting block whose dependencies have finished or already have a manifest, and starts them together. At most two blocks run at the same time. When no waiting block is ready, either the dependencies form a cycle (*Zyklus in depends\_on:  $a \rightarrow b \rightarrow a$* ) or a block waits for one that cannot run; in both cases the runner stops with a message.

#### ⌘ For famuli

The two-at-a-time limit is a semaphore in `run_notebook`. A block that plays a Partitur makes several model calls and opens several DuckDB connections, one after the other; the limit keeps the number of such runs in flight small. Local steps finish in milliseconds, so the limit does not slow them in practice.

#### 14.2 Whether a block runs

For each block the runner computes the block's input in three parts:

##### text

A hash of the preamble without `rerun`, the instruction, and the notebook's `famulus` settings. `rerun` is left out because it says when to run, not what to compute.

##### inputs

For every local file the block reads, its path, size and modification time. The files are the `duckdb` attachments, paths read in a Partitur step's input, and, for a block with `guard` or an `lwgrammar: step`, the LWgrammar store.

**upstream**

Every result the block reads, through `depends_on` or a reference, with the version and checksum it has now. A result on a peer is listed without a version.

The hash of the three parts is compared with the hash in the block's manifest. If they agree and the last run did not end in an error, the block is current. Under the default `rerun: if-stale` a current block is not run; its last result is taken over, and the event says *übernommen*, which the viewer shows as *aus dem letzten Lauf*. `rerun: always` runs the block every time; `rerun: never` never runs it: without a result it fails with *rerun never, aber kein Log*, and with a stale result it keeps that result and reports the block as *veraltet (rerun: never)*. `--force` acts as `always` for every block.

The parts are compared one by one, and the differences give the reasons that `status --why` prints (Chapter 7). Because the file part uses size and modification time, not content, a file that is written without being changed makes its readers stale. This happened while this book was being written. In the night of 24 September the file of the LWgrammar store was written at 03:42. Its modification time changed, and every block that reads the store became stale, whether or not the part it reads had changed:

**Specimen · A changed file time, and the cascade that stops**

```
$ famulus-notebook status --why schoener-saphea
veraltet saphea/schoener-gegenstand v1 pass
 gelesene Datei verändert
wartet saphea/schoener-termini v1 pass
 wartet auf fam:schoener-saphea/saphea/schoener-gegenstand
wartet saphea/canones-sapheae v1 pass
 wartet auf fam:schoener-saphea/saphea/schoener-termini
schoener-saphea: 3 Blöcke, 3 nicht aktuell

$ famulus-notebook refresh schoener-saphea
Was ist der Gegenstand der Briefe von Schöner an Pirckheimer zwischen 1... – läuft
Welche technischen Termini gebraucht Schöner in seinen Briefen, – aus dem letzten Lauf
Welche Aussagen werden im Briefwechsel über eine Canones Sapheae gemach... – läuft
Welche Aussagen werden im Briefwechsel über eine Canones Sapheae gemach... – ohne Oracle
Was ist der Gegenstand der Briefe von Schöner an Pirckheimer zwischen 1... – bestanden, v1
unverändert
schoener-saphea: 2 Blöcke gelaufen: schoener-saphea/saphea/canones-sapheae, schoener-
saphea/saphea/schoener-gegenstand
```

The first block read the changed file and was stale. The two blocks after it were not stale themselves; they *waited*, because a block they read was stale and might change. `refresh` ran the first block. Its artefact came out unchanged, so its version stayed at 1, and the block `schoener-termini`, which reads version 1, was current again and was taken over. The cascade stopped where results stopped changing. The third block ran anyway, because it has `rerun: always`.

The rule is safe in one direction: a file whose content changed has a new modification time, so no change goes unnoticed. It costs runs in the other direction, when a file is touched but not changed. Registers on a peer are not covered at all. A remote read or remote run sees the peer's register as it is when the block runs, but the hash does not record it, so a change on the peer does not make the block stale. Run such a block with `--force` when you know the peer's data changed.

**14.3 Where a block runs**

A block whose preamble names a peer under `engine` is sent to that peer (Chapter 11). The runner resolves the block's input references locally, sends preamble and instruction, and receives the peer's complete log, which it stores as the block's version. Everything else in this chapter then happens on the peer. All other blocks run here.

Before a local block runs, the runner checks what the block needs:

1. The preamble has an `id`, exactly one of `subtask` and `partiturs`, a known subtask if it names one, and a `counting_mode` if it names `lemmata`.
2. Every block named in `depends_on` has a manifest.
3. Every result the block reads resolves, and has a version.

Then every text reference in the instruction, `{ref:...}`, is replaced by the path of the file it names. A reference to a peer's artefact is fetched first and copied to `_famulus/cache/extern/`.

## 14.4 What a block executes

A block with a `subtask` plays the query pipeline's Partitur `ai-query-phase1` once. A block with `partiturs` plays its steps in order. Each step's `input` is resolved first: a value `{ref:...}` becomes the content of the artefact it names, and a text reference becomes a path.

### `duckdb-read`

Opens the block's `duckdb` attachments read-only in a connection that lives for this one statement, runs the statement, and closes the connection. The result is a table. If it has exactly one row, every numeric column becomes an observed value that an oracle can check.

### `lwgrammar:<tool>`

Calls a tool of the language institution LWgrammar in the same process, with the step's input and, where the tool reads text, a column of the previous step's table.

### `artifact:<kind>`

Builds an artefact of the named kind, such as a network, from its input. No model is called.

### any other id

Is looked up in the register of Partituren and played through the execution harness.

The observed values and the artefact of a block are those of its last step. After a harness step the runner judges the step's result against the block's oracle; if the step reports a gap or does not pass, the chain stops there. Local steps do not stop the chain: a table with no rows is passed on to the next step like any other.

## 14.5 The harness and the order of binding

A harness step, and every subtask, becomes a *run request* to the orchestrator's execution harness. The request names the Partitur, the goal, the model, and the inputs; its `goal_id` is the block's id, its source is `famulus-notebook`, and it asks the harness to persist the run, so that the pipeline's own records show which notebook asked.

The goal is the instruction. The inputs are assembled in a fixed order, and a later source wins over an earlier one only where it names the same key:

1. The Partitur's own defaults, applied by the harness.
2. The setting file named by the step, if any.
3. The block's explicit inputs: the instruction, the collections, the client, and the keys `language`, `persons`, `lemmata`, `counting_mode`, `evidence`, `reading_doc`, `person_id`, `project`, `terms`, `locked` and the years, each from the preamble or, if the preamble does not name it, from the project's defaults.
4. The step's `input`, which wins over everything else.

The model is the project's `client`, written as the harness expects it: a Gemini model with the prefix `gemini:`, a model of the families `glm`, `qwen` or `kimi`, or any model ending in `:cloud`, with the prefix `ollama:`.

**</> For famuli**

A subtask name is carried twice. The request's `subtask` input is overwritten by the Partitur's decomposition stage with a structured value, so the runner also passes the name as `notebook_subtask`, which no stage writes. The pipeline's routing reads it there and chooses the specialist for the named subtask over the one its classifier would choose; the lemma stage reads it to take the preamble's `lemmata` as given for a co-occurrence.

**14.6 Judging and writing**

The block's result is judged against its oracle (Chapter 4). When the orchestrator is installed, its judge is used; without it, a block with an oracle cannot be judged and is recorded as an error, and a block without one is judged by a small local rule. A block with `guard` then has its answer, or its artefact, checked by the formulation guard, which may turn a pass into a failure.

Only a passing result writes artefacts. The runner computes a checksum of the data of each declared artefact and compares it with those of the current version. If they agree, the run writes into the current version; if not, it opens the next one (Chapter 7). A run whose result does not pass writes no artefact, and the next passing run fills the version it left. The runner then writes, in the version folder:

**report.json**

The question, the answer, the status, and the numeric counts.

**verdict.json**

The oracle, the observed values, the status, and a note.

**result.json**

What the viewer shows: question, answer, verdict, measured values, display format, origin (*herkunft*), and the list of artefacts.

**trace.json**

The harness's trace of the run, for harness steps and subtasks.

**manifest.json**

The block's id, version, input hash and its three parts, the versions it consumed, the status, start and end, the number of runs, and the artefacts.

Last, `current.json` names the version, and the notebook's `index.json` records the block's status. When every notebook of the command has run, the runner writes the project's `famulus.lock` from the manifests.

A run that ends in an error is recorded in the current version, not in a new one. Its artefacts, if an earlier run wrote them, stay where they are; the verdict and result say *Fehler* and give the message. The manifest records the error and the input hash, so the block is stale on the next run for the reason *letzter Lauf endete mit Fehler*.

**In short**

- Notebooks run in the order of their references; `refresh` runs foreign local producers first.
- A block runs when the hash of its text, its local files and its upstream versions differs from its manifest, or when `rerun` or `--force` says so.
- Files are compared by size and time; a peer's data are not compared.
- A subtask plays `ai-query-phase1`; a chain plays local steps in the process and other steps through the harness.
- Inputs bind in the order Partitur default, setting file, preamble, step input.
- Only a passing result writes artefacts; an error is recorded in the current version.

### ✎ Exercise 14.1

A block reads a DuckDB file that another program rewrites every night with the same content. What does `status` report the next morning, and what does `refresh` do? Which of the three input parts would you have to change so that the block stays current?

### ✎ Exercise 14.2

A chain has three steps: `duckdb-read`, a harness step, and `artifact:d3-graph`. The harness step does not pass its oracle. Which artefact does the block store, and what does its `result.json` show?

## 15 When something goes wrong

The runner speaks German, and it says what went wrong in one sentence. This chapter collects those sentences. Each is quoted as the program prints it, followed by its cause and its remedy. The catalogue is taken from the source of `famulus_notebook`; the messages in the first specimen were produced by running a notebook written to fail.

### 15.1 Where a message appears

A message appears in one of three places.

**On the command line**, when the command cannot start: the project is not found, a block does not exist, the notebooks form a cycle. The message is printed after the program's name, and the command ends with exit code 1:

```
famulus-notebook: /private/tmp/fn-lose/x.fam liegt in keinem Projekt
```

**At the block**, when one block cannot run or its run fails. The other blocks run on. The message is the block's answer; it is prefixed with the kind of error, its verdict is *Fehler*, and it stands in the block's `result.json` and in the manifest. On the command line it replaces the block's closing line.

**In the viewer or the HTTP response**, when the server refuses a request. The response carries a status code and the message under `detail`.

The following notebook was written to fail. Each of its eight blocks contains one mistake:

#### Specimen · Eight blocks, eight mistakes

```
$ famulus-notebook run .
Beides zugleich. – läuft
NotebookError: beides: genau eines von subtask und partiturs
Ein Subtask, den es nicht gibt. – läuft
NotebookError: falscher-subtask: unbekannter subtask 'letter-count'
Lemmata ohne Zählmodus. – läuft
NotebookError: ohne-modus: counting_mode fehlt bei der Lemma-Zählung
Eine Lesung, die schreiben will. – läuft
InvalidInputException: Invalid Input Error: Cannot execute statement of type "DELETE" on
database "pirckheimer" which is attached in read-only mode!
Zwei Anweisungen. – läuft
Zwei Anweisungen. – ohne Oracle
Eine Lesung ohne Zeile. – läuft
Eine Lesung ohne Zeile. – ohne Oracle
Ein Verweis ins Leere. – läuft
NotebookError: hängt an fam:fehler/fehler/gibt-es-nicht.x, dort liegt noch keine Version
Eine Partitur, die nicht im Register steht. – läuft
NotebookError: Partitur nicht im Register: gibt-es-nicht
```

Six of the blocks fail as they should. Two do not, and they are the instructive ones. The block `zwei-anweisungen` reads `SELECT 1; SELECT 2`, and the block `leer` reads a table with no rows; both are recorded as *ohne Oracle*, which the display shows as an unchecked pass. The first shows that a local reading is not held to the rules of a served reading (see below). The second shows a gap in the verdict rule: a table with columns but no rows counts as a result, because the observed values include the column names and a row count of zero. A pass on an empty result is exactly what the verdict rule of Chapter 4 is meant to prevent. Until the rule is corrected, give every reading an oracle, if only a floor of one row.

## ■ 15.2 Projects, notebooks and files

### *... liegt in keinem Projekt*

The path is not inside a folder with a `famulus.yml`, and no folder above it has one. Create the project with `famulus-notebook project new <ordner> --id <projekt>`, or move the notebook into a project.

### *kein Projekt in ... (famulus.yml fehlt)*

A folder was named as a project, but has no `famulus.yml`.

### *Projekt ... : kein Notebook ...*

The project exists but lists no notebook of that id. Check `famulus.yml` and the file's front matter, where `famulus: id:` must agree.

### *unbekanntes Projekt ... (famulus-notebook project register <ordner>)*

A reference names a project that is not in the register of this machine. Register the project's folder, as the message says.

### *Projekt ... hat N Notebooks; <projekt>/<notebook> angeben*

A command or a `uses` entry named a project with several notebooks where one notebook was meant. Name the notebook as well.

### *kein Notebook in ...*

The folder has a `famulus.yml` but no notebook the runner can read.

### *pandoc fehlt: der Parser braucht pandoc im PATH*

The parser reads notebooks through Pandoc, which is not installed or not on the search path. Install Pandoc, or put its folder on the path.

### *Error parsing YAML metadata at "... (line 1, column 1): ...*

The front matter is not valid YAML. The message is Pandoc's and names the line within the front matter. The viewer shows the same failure as *Die Front Matter ist kein gültiges YAML.*, with the file and the line.

### *Zyklus zwischen Notebooks: $a \rightarrow b \rightarrow a$*

Two notebooks of a project read each other's results with `@latest`. One of them must read a fixed version (`@v1`), or the shared part must move into a third notebook.

### *Zyklus zwischen Projekten: ...*

The same, between projects, found by `refresh`.

### *...: Markierung '# famulus-notebook build: Anfang ...' fehlt*

`build` could not find its marker comments in the site's `_quarto.yml`. Restore the pair of markers; the build writes only between them.

### *quarto fehlt: <https://quarto.org/docs/get-started/>*

`render` needs Quarto. `build` does not.

## 15.3 The preamble

### *Präambel ohne id*

The block's preamble has no `id`. Every block needs one; it names the block's folder in the store and its reference.

### *doppelte Block-id*

Two blocks of one notebook have the same id. The notebook does not run at all, because the second block would overwrite the first one's results.

### *...: genau eines von subtask und partiturs*

The block names both, or neither. A block asks the pipeline one question ( `subtask` ) or plays its own chain ( `partiturs` ), not both.

### *...: unbekannter subtask '...'*

The subtask is not one of the thirteen the pipeline knows. Appendix A lists them.

### *...: counting\_mode fehlt bei der Lemma-Zählung*

The block names `lemmata` but no counting mode. A count of lemmata means nothing without its mode (Chapter 8); add `counting_mode: canonical` or the mode you mean.

### *...: Partitur-Schritt ohne id*

An entry of `partiturs` has no `id`.

### *...: duckdb-read ohne sql*

A `duckdb-read` step has no statement under `input: sql: .`

## 15.4 References and dependencies

### *unbekannter Block: ...*

`--block` or a request named a block that the notebook does not have.

### *hängt an ..., dort liegt kein manifest.json*

A block named in `depends_on` has never run. Run it first; `run --block` does this by itself for blocks of the same notebook.

### *hängt an ..., dort liegt noch keine Version*

The block reads a result that has no version yet: the block exists but has not passed, or the reference names a block that does not exist. `check` tells the two apart.

### *Zyklus in depends\_on: $a \rightarrow b \rightarrow a$*

The blocks of a notebook wait for each other.

### *Abhängigkeit ohne Manifest: ...*

The named blocks wait for a block that is not in this run and has no manifest, so they can never start.

### *unaufgelöster Verweis ...*

A reference in the instruction or in a step's input names a file that is not there. With a colon the message adds the reason from the resolver.

### *Verweis nicht lesbar: ...*

The reference is not written in the form of Chapter 6.

### *...: Artefaktnamen fehlt (<block>.<artefakt>)*

The reference names a block where an artefact is needed.

### *...: fam:-Verweis braucht <projekt>/<notebook>/<block>.<artefakt>*

A full reference lacks one of its four parts.

...: *unbekannte Version @... (latest, vN, sha:..., locked)*

The selector after @ is not one of the four.

...: *keine Version mit ...*

The selector is valid, but no version matches it, for example @sha: with a prefix no artefact has.

...: *Kurzform braucht ein Notebook, in dem sie steht*

A short reference, block.artefact, was used where no notebook gives it a context, for example on the command line.

## 15.5 Reading data

Two messages of the local reading are in English, because they come from a lower layer:

*bad attachment alias ‘...’*

An attachment's alias is not a plain name.

*unknown artefact kind ‘...’*

An artifact: step names a kind the builder does not know. The kinds are listed in Appendix A.

...: *eine entfernte Lesung braucht genau einen Peer für alle Anhänge*

Some attachments of a block name a peer and some do not, or they name different peers. A remote read happens in one place.

...: *entfernter Pfad muss mit \$PDAI\_COLLECTIONS/<sammlung>/ beginnen*

The peer resolves paths inside its own collections; a remote attachment must name one.

...: *eine entfernte Lesung liest genau eine Sammlung*

The attachments lie in two collections. Split the reading into two blocks.

The peer checks a served reading before it runs it, and refuses it with one of these messages:

**Table 13** The refusals of a served reading.

| Message                                  | Cause                                   |
|------------------------------------------|-----------------------------------------|
| <i>nur eine Anweisung</i>                | a semicolon outside a string            |
| <i>nur SELECT oder WITH</i>              | the statement begins with another word  |
| <i>nicht erlaubt: DELETE</i>             | a writing or file verb outside a string |
| <i>Pfad außerhalb der Sammlung: ...</i>  | an attachment outside the collection    |
| <i>nur DuckDB-Dateien: ...</i>           | an attachment that is not a DuckDB file |
| <i>Alias nicht zulässig: ...</i>         | an alias that is not a plain name       |
| <i>Sammlungsname nicht zulässig: ...</i> | a collection name with a slash or dot   |
| <i>Sammlung fehlt: ...</i>               | no such collection on the peer          |
| <i>Abfrage nach 30 s abgebrochen</i>     | the reading ran longer than 30 seconds  |

A local reading is not checked in this way. It opens its files read-only, so that a writing statement is refused by DuckDB itself, as the specimen shows, but it does not refuse a second statement or a table function that reads another file. On your own machine this is your own responsibility; a reading that should later run on a peer should be written as if it were served.

## 15.6 Peers and remote runs

*Peer nicht in ...: ...*

The block names a peer that is not in peers.yaml.

**Peer ohne Endpunkt: ...**

The peer's entry lists no endpoint.

**...: unbekannte Art '...'**

The peer's kind is not one the program knows.

**... nicht erreichbar — ...**

No endpoint of the peer answered. The message lists, for each endpoint, what happened. Run `famulus-notebook peers probe <name>`.

**... POST ...: HTTP 401 Token fehlt oder falsch**

The peer has a token and this machine sent none, or the wrong one. Check the variable named under `token_env` (Chapter 11). A peer without a token answers *Dieser Server ist nur lokal freigegeben* instead.

**...: ein Textverweis {{ref:...}} zeigt auf eine lokale Datei; als input-Verweis übergeben**

A block that runs on a peer uses a text reference, which would become a path on this machine. Pass the artefact as `{ref: ...}` in a step's input; its content is then sent.

**...: setting-Dateien laufen nicht entfernt**

A setting file lies in the calling project, which the peer does not see.

**Peer lieferte kein vollständiges Log and ... beendete den Lauf ohne Log**

The peer ran the block but its answer was incomplete. The peer's own store has the run; look there.

**15.7 The engine and the Partitur****Ausführung braucht ai-agent-orchestrator und ai-query. Installieren mit: `uv sync --extra run` (... fehlt)**

The machine has no query pipeline. Blocks with a subtask or a harness step cannot run here; run them on a peer with `engine`, or install the extra.

**Oracle-Prüfung: ...**

A block has an oracle, but the orchestrator, whose judge compares it, is not installed. The block is recorded as an error rather than as a pass.

**Partitur nicht im Register: ...**

A step names a Partitur the register does not know.

**Partitur nicht gefunden: ...**

The query pipeline's own score is not at its expected place. The variable `PARTITUR_SCORE` names another place.

**Lauf ohne Ergebnis**

The harness ran the Partitur, which neither succeeded nor published any result. Otherwise the message is the harness's own final grade. The trace, under Diagnose, shows which stage stopped (Chapter 10).

**lwgrammar:....: vorheriger Schritt liefert keine Spalte '...'**

An LWgrammar step reads text from a column of the previous step, and that step's table has no such column.

**15.8 The formulation guard**

A block with `guard` has its text checked after the verdict. The guard writes its findings into `verdict.json` under `guard` and may change the verdict:

**Formulierung: ...**

The text failed the named blocking metrics, and the pass became a deviation.

**kein erzeugter Text zu prüfen**

The block produced no text for the guard. The verdict is unchanged, and the guard's entry records that nothing was checked.

**LWgrammar nicht erreichbar; der Text bleibt ungeprüft**

The language institution could not be reached. The verdict becomes an error: an unchecked text is not passed as checked.

**15.9 The server****Token fehlt oder falsch (401)**

The request came from outside and carried no valid token.

**Dieser Server ist nur lokal freigegeben (401)**

The server has no token and so admits only its own machine.

**Anmerkungen nur am eigenen Rechner (403)**

A note to the learning loop was sent through a peer. Notes are taken only on the owner's machine.

**Dateizugriff außerhalb der Sammlung ist gesperrt (403)**

A served reading tried to read a file outside the collection.

**Lektorat nicht erreichbar: ... and Lernloop nicht erreichbar: ... (502)**

The Lektor on port 5114, or the ai-query service, did not answer.

**Viewer nicht gebaut: cd web && npm run build (503)**

The server runs, but the viewer's files are missing.

*Notebook nicht gefunden: ... (404), ...: noch keine Version (404), Artefakt nicht im Manifest (404), Artefaktdatei fehlt (404)* : A request named something the store does not have.

**In short**

- A message that stops a command is printed as `famulus-notebook: ...`, with exit code 1; a message that stops one block becomes that block's answer.
- Read the message literally: it names the block, the key, or the file.
- A served reading is checked; a local one is only opened read-only.
- A reading without an oracle can pass on an empty table; give it a floor.

**✍ Exercise 15.1**

Write a block that fails with *hängt an ..., dort liegt noch keine Version* although the block it reads exists. What must be true of that block?

**✍ Exercise 15.2**

Which of the refusals of Table 13 would a local reading also give, and which would it not? Try one of each.

**16 Design decisions, related work, limits**

Several choices in this book could have been made otherwise. This chapter names seven of them, the alternative that was set aside, and the reason. It then places the notebook among its ancestors and lists what it cannot do, by design and for now.

**16.1 A declared preamble instead of code**

A block states its scope and its plan as data, not as a program. The alternative, familiar from computational notebooks, is a cell of code that calls the pipeline. A code cell can do anything, and for that reason its reader

cannot tell from the cell alone what it will read and which rule it will follow. The preamble is closed: every key is listed in Appendix A, and every key has one place in the run request (Chapter 14). A reader can judge the scope of a question before the question is answered, and the runner can refuse a block whose scope is incomplete, such as a lemma count without a counting mode.

The price is that a question the preamble cannot state cannot be asked. It has to become a subtask or a Partitur first. The local steps are the one opening the preamble leaves: a register may be read with SQL, but only read, only through a connection that lives for one statement, and, on a peer, only inside one collection.

## ■ 16.2 A store beside the notebook

The results of a run are written into a store next to the notebook, not into the notebook and not into a database. Writing them into the notebook, as computational notebooks keep the output of a cell, would mix the author's text with the machine's product: a revision of the text would touch the result, and a new result would change the file the author edits. A database would separate them, but the project could then no longer be handed on as a folder. The store is plain JSON in numbered version folders. It can be read without the viewer, compared with `diff`, and archived with the notebook.

## ■ 16.3 Versions by content, not by run

A run makes a new version only when the content of an artefact changes (Chapter 7). The alternative, a version per run, would record every repetition and make the history as long as the number of runs. A version per content makes the history as long as the number of different results, which is what a reader who cites a result needs. It also makes the cascade of Chapter 14 stop: a block that reads an unchanged result is still current. The Schöner project of Chapter 13 shows the condition this places on the author. A result that is kept in the answer rather than in an artefact is not versioned, and a changed answer keeps its old version.

## ■ 16.4 No kernel

A computational notebook keeps a process, the kernel, whose state carries from cell to cell. A Famulus notebook has no such state. Each block is played from its preamble, its instruction, and the results it names; nothing else passes between blocks. The order in which blocks were run has no effect on their results, provided the results they name exist, which the runner checks. What a kernel would provide, a value computed once and used many times, the notebook provides as an artefact that a later block names by reference, with the version it read recorded in the manifest.

## ■ 16.5 Peers instead of copies

A notebook on a machine without collections reads the registers of another machine through that machine's service; it does not receive a copy of them. Copying the collections would give every machine the full data, but the collections are large, change when a stage of their pipeline runs again, and would then exist in several states at once. A reading through the peer always reads the register in the state the peer holds, and the result names the peer. The price is that the reading machine depends on the peer being reachable, and that the input hash does not see a change on the peer (Chapter 14). A remote reference keeps a copy of the one artefact that a notebook took over, with its source recorded beside it.

## ■ 16.6 A token in a file, passed once

Every caller who is not the machine itself presents a token. The token lies in a file on the serving machine and in a named variable on the calling machine; it appears neither in `peers.yaml` nor in a notebook. A browser receives it once, in the part of an address after `#`, which a browser does not send to a server and which therefore reaches no log. The viewer posts it to `/api/session` and receives a cookie in return. An account system would allow several users with different rights. The notebook serves one owner and the machines the owner admits, and for that one secret per machine is enough. Rights that differ by person, such as commenting without revising, are left to the Lektor.

## ■ 16.7 A pass without oracle is not a pass

The verdict rule of Chapter 4 could have treated a block without an oracle as passed. It does not, because the display would then show the same mark for a checked and an unchecked answer, and a reader would take

both as checked. The words *ohne Oracle* cost one chip on the sheet and prevent that confusion. Chapter 15 showed where the rule is still incomplete: a table with no rows counts as a result.

## 16.8 Related work

The notebook has three ancestors. Literate programming joined program and explanation in one document, written for a human reader and mechanically turned into a program [2]. Reproducible research demanded that a publication carry the means of regenerating its results. Claerbout and Karrenbach made the electronic document the carrier of those means [3], and Peng described a spectrum from publication alone to full replication, with code and data as the steps between [4]. Computational notebooks, of which Jupyter is the most widely used, made the interleaving of prose, code and output an everyday form and proposed it as a form of publication [5]. Quarto renders such documents to HTML and PDF from one source [6]; Famulus Notebook uses it for exactly that, and defines its block as a code block of its own language.

Famulus Notebook differs from these in three respects. First, the executable unit is not code but a declaration: the preamble names scope and plan, and the instruction is a question in ordinary language. The code that answers it lies in the register of Partituren and in the pipeline, not in the notebook. Second, every block can carry its expected result, and the display separates a checked result from an unchecked one. A Jupyter cell has an output; a Famulus block has an output and a verdict. Third, execution can be delegated to a named peer while the collection stays where it lies. Hosted notebook services move the notebook to the data; Famulus Notebook keeps the notebook where it is written and sends the question.

The notebook reads its collections through DuckDB, an embedded analytical database that opens a file read-only in the process that needs it [7]. The short-lived read-only connection is what makes it safe for a peer to serve readings. The network layer relies on the transports of the local network and of Tailscale, whose tunnels are WireGuard [8]; it adds only the ordered endpoints, the probe, and the token.

The query pipeline, the register of Partituren and the execution harness are described in the companion papers [1], [9], [10], and the Famulus platform as a whole in [11]. The idea that a question is answered well when it is answered according to a publicly checkable standard has a philosophical side that the paper on LWgrammar develops [12]. Following a rule is a practice [13, PU §202]. An oracle in a block is the written form of the standard against which a particular answer is judged, and the store is the record of the practice.

The form of this book follows Leslie Lamport's manual for LaTeX, which teaches a system by examples that show the source beside what it produces, with the reference manual in an appendix [citation gap: the bibliographic entry for Lamport's LaTeX manual is not yet in the bibliography and awaits the author's confirmation].

## 16.9 Limits

The design has limits that follow from it.

1. A block with `engine` cannot use a text reference to a local artefact or a setting file, because the peer does not see the calling project. Such blocks are refused before they are sent.
2. A remote reading reads one collection on one peer, with one statement, at most 5,000 rows, and at most 30 seconds.
3. Comparing a result with an oracle needs the orchestrator. A machine without it runs blocks without an oracle, and blocks with one only on a peer.
4. The key `golden` names a golden; it does not load its oracle. A block that is to be checked against a golden must carry the oracle in its preamble.
5. Local files are compared by size and modification time, not by content, and a peer's registers are not compared at all.

## 16.10 Open gaps

The following gaps were open when this book was written. Each was found by running the examples of this book.

1. A reading without an oracle that returns no rows passes as *ohne Oracle* (Chapter 15).
2. A local reading is not held to the rules of a served reading; it may contain several statements (Chapter 15).
3. The field `modell` of `herkunft` names the project's client for `lwgrammar`: steps, which call no model (Chapter 13).
4. The PDF rendering of the Quarto extension writes the answer without converting its Markdown and leaves out verdict and table (Chapter 12).
5. The artefact kind `timeline` has no builder of its own and falls back to Markdown.
6. The local steps are implemented in the runner and are not Partituren in the register.
7. The share links of the Lektor work for rendered documents only, not for the chapters of a notebook (Chapter 11).
8. The findings of Chapter 13 about the query pipeline are open: the row limit reported as scope, words of the instruction in the lemma decomposition and the person search, and the counts that the register does not reproduce (Pirkheimer 75 against 77, Kepler 45 against 44).
9. The query pipeline's own goal check flags runs that pass their oracle and writes a note into the learning loop for each of them (Appendix D).

#### In short

- The preamble is closed, so that scope can be judged before the answer.
- Results live in a versioned store beside the notebook, one version per content.
- There is no kernel; results pass between blocks as named artefacts.
- Peers are asked, not copied; a token per machine admits them.
- An unchecked answer is shown as unchecked.

## Appendices

### Appendix A: Reference manual

This appendix states every rule once. The chapters taught the rules by example; here they are listed without examples, in the order a reader looks them up. Names in German are those of the program.

#### A.1 Files of a project

A project is a folder with these files:

`famulus.yml`

The project file (A.3).

`<notebook>.fam`

A notebook (A.2). The project's integrating notebook may list chapters that lie in subfolders, such as `kapitel/ch01.fam`.

`settings/*.setting.yaml`

Setting files named by Partitur steps.

`famulus.lock`

Written by the runner (A.6).

`_famulus/store/<notebook>/<block>/`

The store: `current.json` and one folder `v0001`, `v0002`, ... per version (A.7).

**\_famulus/build/<notebook>.qmd**

Shadow copies written by `build` (Chapter 12).

**\_famulus/cache/extern/<peer>/...**

Copies of artefacts fetched from peers, each with a `.source.json`.

Two files outside the project belong to the machine:

**~/.config/famulus/projects.yaml**

The register of projects, `projects: {<id>: <folder>}`. The variable `FAMULUS_PROJECTS` names another file.

**~/.config/famulus/peers.yaml**

The peers (A.9). The variable `FAMULUS_PEERS` names another file.

An identifier of a project or a notebook consists of lower-case letters, digits and hyphens and begins with a letter. A block id or artefact name consists of letters, digits, underscores and hyphens and does not begin with a hyphen.

## A.2 A notebook

A notebook is a Quarto document with the extension `.fam`. Its front matter holds the ordinary Quarto keys (`title`, `subtitle`, `author`, `date`, `abstract`, ...) and one mapping `famulus`:

**id**

The notebook's id. Required.

**uses**

Aliases for other notebooks, `<alias>: fam:<projekt>/<notebook>[@selector]`. They win over the project's `imports`.

**chapters**

In the integrating notebook only: the chapter files, in order.

**any other key**

A setting of this notebook, overriding the project's default of the same name (A.3).

A block is a fenced code block of the class `{famulus}`. Its text is a preamble between two lines `---`, followed by the instruction:

```
```{famulus}
---
id: first-count
""
---
How many correspondents did Pirckheimer have between 1520 and 1530?
```
```

The instruction is a question or a task in ordinary language. It may contain placeholders `{{ref:<reference>}}` (A.10), which the runner replaces by the path of the named artefact before the plan is played.

## A.3 The project file

**id**

The project's id. Required.

**title**

The project's title.

**main**

The integrating notebook, by file name with or without `.fam`. Without it the runner takes the first notebook that names `chapters`.

**defaults**

Settings every notebook inherits: `collections`, `client` (the model), `evidence`, `language`, `locked`, and any preamble key of the scope group (A.4). A notebook's `famulus` mapping overrides them. `project new` also writes `duckdb_root: $PDAI_COLLECTIONS`; this version of the runner does not read it, and a path in `duckdb` names the variable itself.

**imports**

Aliases that hold for every notebook, `<alias>: fam:<projekt>/<notebook>`.

**moved**

Old block names and their new names, `<notebook>/<old>: <notebook>/<new>`. A reference to the old name is resolved to the new one, and `check` reports it.

**A.4 The preamble**

The keys fall into the eight groups of Chapter 2. A key not listed here reaches no step; it is part of the preamble's text, so changing it makes the block stale, but the runner neither checks nor passes it.

**Identity****id**

The block's id, unique in the notebook. Required.

**Order****depends\_on**

A list of block ids of the same notebook, or references to blocks elsewhere, that must have a result before this block runs.

**rerun**

`if-stale` (default; `if-missing` is read as the same), `always`, or `never` (Chapter 7). Changing `rerun` does not make a block stale.

**engine**

The name of a peer that runs the block, or `local`.

**Scope****collections**

The collections the block may read.

**years**

`{from: <jahr>, to: <jahr>}`; either bound may be missing.

`language`, `persons`, `terms`, `reading_doc`, `person_id`, `project`, `evidence` : Passed to the query pipeline as inputs of the same name.

**lemmata**

A list of lemmata. Requires `counting_mode`.

**counting\_mode**

`canonical`, `family` or `family+adj` (Chapter 8).

**locked**

`true`: the block's collections win over a corpus named in the question.

**Data**

**duckdb**

A list of attachments, each {`alias`, `path`, `read_only`, `peer`}. `alias` is `main` for the default database; `path` may begin with `$PDAI_COLLECTIONS`; `peer` makes the reading remote.

**Plan** (exactly one of the two)

**subtask**

A question for the query pipeline, one of: `correspondence-count`, `correspondence-roster`, `letter-subject`, `mention-in-letters`, `terminology-find`, `concept-statements`, `statement-mention`, `source-attestation`, `sentence-mention`, `cooccurrence`, `manuscript-inventory`, `register-inventory`, `entity-mention-count`.

**partiturs**

A list of steps, each {`id`, `input`, `setting`}. `id` is `duckdb-read`, `lwgrammar:<tool>`, `artifact:<kind>`, or the id of a Partitur in the register. `input` is a mapping whose values may be references {`ref`: `<reference>`}. `setting` names a setting file of the project.

**Artefacts****artefacts**

A list of {`name`, `kind`, `file`}. `kind` is one of `table`, `report`, `roster-table`, `kwic`, `citation-list`, `markdown`, `timeline`, `d3-graph`, `proof-structure`, `json`, `figure`.

**Display****display**

A form name, or a mapping {`format`, `gruppe`, `spalten`, `sortierung`, `zeilen_sichtbar`}. Forms: `kennzahl`, `liste`, `tabelle`, `hierarchische-tabelle`, `belegliste`, `textkarten`, `netz`. `spalten` is a list of {`feld`, `label`, `art`}, `art`: `zahl` for a numeric column; `sortierung` is {`feld`, `richtung`}, `richtung` `auf` or `ab`.

**Checking****oracle**

A mapping from observed names to expectations: a number (equality), a range {`min`, `max`} with either bound, a string (the observed value of the same name contains it, ignoring case), a boolean, or a list (every item is found in the observed value of the same name). A key the run did not observe fails. A reading of several rows observes `columns`, `rows`, `n_sentences` (the number of rows) and `n_documents`; a reading of one row also observes each numeric column.

**golden**

The id of the golden the oracle was taken from. It does not load the oracle.

**guard**

A task form of LWgrammar, or a mapping {`task`, `lang`, `author`, `family`, `text`, `evidence`}. `text` names the observed field to check (default: the answer); `evidence` replaces the block's own result as the evidence that numbers and citations of the text must occur in.

**A.5 Rules the runner enforces**

1. A preamble has an `id`.
2. It has exactly one of `subtask` and `partiturs`.
3. A `subtask` is one of the names in A.4.
4. `lemmata` requires `counting_mode`.
5. Every step of `partiturs` has an `id`; `duckdb-read` has `input`: `sql`.
6. Block ids are unique in a notebook; `depends_on` forms no cycle.
7. Every block in `depends_on` has a manifest before the block runs.
8. Every reference the block reads resolves to a version before it runs.

9. A block with `engine` uses no text placeholder to a local artefact and no setting file.
10. A remote reading has one peer and one collection for all attachments.

A violation of rules 1 to 5, 9 and 10 is an error of the block: it gets a version with status `error`, and the other blocks run. A block without `id` is filed under the slug of its section, such as `anfang#1`. A duplicate id or a cycle (rule 6) stops the notebook before any block runs; a missing manifest (rule 7) stops it with `Abhängigkeit ohne Manifest: <block>` when that block's turn comes. A reference that does not resolve (rule 8) makes the block wait (`hängt an <ref>, dort liegt noch keine Version`); it runs when the reference has a version.

## A.6 The lock

`famulus.lock` is YAML, written by the runner after every command that ran blocks. Its keys:

### project, written

The project's id and the time of writing.

### blocks

For every `<notebook>/<block>`: `input_hash`, `status`, `version`, `consumes` (a list of `{ref, version, sha}`), and `produces` (a list of `{name, version, sha}`).

The selector `@locked` resolves a reference to the version the lock names.

## A.7 The store

Each block has a folder `_famulus/store/<notebook>/<block>/` with `current.json`, `{"version": N, "since": "<time>"}`, and one folder per version. A version folder holds:

### manifest.json

`id`, `version`, `input_hash`, `input_parts` (`text`, `inputs`, `upstream`), `consumes`, `status`, `started`, `finished`, `runs`, `artefacts`, and `error` after a failed run.

### result.json

`id`, `frage`, `antwort`, `urteil` (`pass`, `unchecked`, `fail`, `gap`, `error`), `messwerte` (a list of `{name, label, beobachtet, erwartet}`), `artefakte`, `herkunft` (`partitur`, `modell`, `sammlungen`, `dauer_ms`, and `peer` for a remote run), and `display`.

### verdict.json

`status`, `oracle`, `observed`, `note`, `id`, `golden`, and `guard` for a guarded block.

### report.json

`id`, `question`, `answer`, `status`, `counts`.

### trace.json

The trace of the harness, for subtasks and harness steps.

### artefacts/<file>

The declared artefacts, each an envelope (A.8).

A manifest entry of an artefact names `name`, `kind`, `file`, `ref`, `version`, `sha256`, and `written_at`.

## A.8 The envelope

Every artefact file is a JSON object with two keys:

```
{
 "famulus": {
 "ref": "fam:<projekt>/<notebook>/<block>.<artefakt>",
 "version": 2,
 "sha256": "<checksum of data>",
 "created": "<time>",
```

```

 "produced_by": {
 "notebook": "<projekt>/<notebook>",
 "block": "<block>",
 "input_hash": "<hash>",
 "partitur": "<first step>",
 "model": "<model, empty for local steps>"
 },
 "derived_from": [{ "ref": "...", "version": 1, "sha": "..."}],
 },
 "data": { "artifact_type": "...", "title": "...", "data": { ... } }
}

```

The checksum is taken over `data` alone, so the header can change without changing the version. A table's rows lie at `data.data.rows`; a roster's entries at `data.data.entries`.

## A.9 Peers

`peers.yaml` holds one entry per peer:

```

peers:
 mac-studio:
 kind: notebook
 endpoints:
 - http://100.102.189.23:5118
 - https://mac-studio.tail147011.ts.net/famulus-notebook
 token_env: FAMULUS_TOKEN_MAC_STUDIO

```

### kind

`notebook`, `ai-query`, `lektorat`, `viewer` or `mcp`.

### endpoints

Tried in order. A probe waits at most 1.5 s for each; the first that answers is used for 60 s.

### token\_env

The variable that holds the peer's token. Without it, `FAMULUS_PEER_TOKEN` is used.

## A.10 The grammar of references

A reference names a block, or an artefact of a block, and optionally a version:

```

reference = [peer] , (full | short) , ["@" , selector] ;
peer = "peer:" , id , "/" ;
full = "fam:" , id , "/" , id , "/" , target ;
short = target
 | id , "/" , target ; (* notebook, or alias *)
target = name , ["." , name] ; (* block, or block.artefact *)
selector = "latest" | "locked"
 | "v" , digit , { digit }
 | "sha:" , hex , hex , hex , hex , { hex } ;
id = lower , { lower | digit | "-" } ;
name = (letter | digit | "_") , { letter | digit | "_" | "-" } ;
placeholder = "{{ref:" , reference , "}}" ;

```

A short reference is resolved against the notebook it stands in: `name.name` in the same notebook, `id/name.name` in a notebook of the same project or through an alias of `uses` or `imports`. Without a selector a reference means `@latest`. A `sha:` prefix has 4 to 64 hexadecimal digits. The form `peer:<peer>/<notebook>/<block>.<artefakt>` of older peers is still read.

## A.11 Environment variables

Table 14 Environment variables.

| Variable                                                        | Meaning                                                         | Default                                       |
|-----------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------------------------|
| <code>PDAI_COLLECTIONS</code>                                   | folder of the collections                                       | <code>/Volumes/PDAI-1/pdai-collections</code> |
| <code>FAMULUS_NOTEBOOKS</code>                                  | further folders with projects, separated by <code>:</code>      | none                                          |
| <code>FAMULUS_NOTEBOOK_HOME</code>                              | the installation folder                                         | the package's folder                          |
| <code>FAMULUS_JOURNAL</code>                                    | folder of one's own projects, the journal and generated goldens | <code>~/Documents/Famulus/Notebooks</code>    |
| <code>FAMULUS_NOTEBOOK_PORT</code>                              | the server's port                                               | 5118                                          |
| <code>FAMULUS_PROJECTS</code>                                   | the register of projects                                        | <code>~/.config/famulus/projects.yaml</code>  |
| <code>FAMULUS_PEERS</code>                                      | the peers                                                       | <code>~/.config/famulus/peers.yaml</code>     |
| <code>FAMULUS_TOKEN</code> ,<br><code>FAMULUS_TOKEN_FILE</code> | this server's token                                             | <code>~/.config/famulus/token</code>          |
| <code>FAMULUS_TRUST_TAILNET</code>                              | admit the tailnet without token                                 | off                                           |
| <code>FAMULUS_PEER_TOKEN</code>                                 | token for peers without <code>token_env</code>                  | none                                          |
| <code>LEKTORAT_URL</code>                                       | the Lektor                                                      | <code>http://127.0.0.1:5114</code>            |
| <code>AIQUERY_URL</code>                                        | the query service                                               | <code>http://127.0.0.1:5113</code>            |
| <code>PARTITUR_SCORE</code>                                     | the query pipeline's score                                      | found from the installation                   |

## Appendix B: The command line

All commands are subcommands of one program:

```
famulus-notebook <command> [options] [target]
```

The program is installed into the virtual environment of the installation; `install.sh` puts nothing on the search path, so a reader either activates that environment or calls `.venv/bin/famulus-notebook`. A *target* is a project folder or a `.fam` file; where it may be left out, the current folder is meant. The program's own messages are in German, as in the rest of the book.

Every command ends with a status: 0 for success, 1 when a block did not pass, a check found something, or a peer was unreachable, and 2 when the command itself was used wrongly. A mistake the program recognises (a preamble, a reference, a peer, a project) is printed as one line `famulus-notebook: <message>` with status 1; Chapter 15 lists the messages.

## Installing

The workspace is installed from its folder with one script:

```
$ cd ~/ai-mac-studio/development/famulus-notebook
$./install.sh [--run] [--launchd] [--token] [--host <address>] [--trust-tailnet]
```

Without options the script installs the parser, the viewer, the command line and the Quarto site; it needs `uv`, `npm` and `pandoc`. The options add:

**--run**

block execution, through the agent orchestrator and ai-query, which must lie beside the workspace;

**--launchd**

the service `com.ai-platform.famulus-notebook`, started at login;

**--token**

a token in `~/ .config/famulus/token`, mode 0600, if there is none;

**--host <address>**

an address beyond loopback to listen on; it requires a token or `--trust-tailnet`;

**--trust-tailnet**

admission of the tailnet's addresses without a token.

A machine that only reads and writes notebooks, and sends its blocks to a peer, needs no option (Appendix D).

## Running

**run <target> [--block <id>] [--force]**

Runs a notebook, or every notebook of a project. Blocks whose inputs are unchanged are not played again (Chapter 7). `--block` runs only that block and the blocks it depends on; `--force` plays every block, changed or not. While the run lasts, one sentence per event is printed; at the end, one line of JSON with the status of each block. Status 1 if a block ended neither in `pass` nor in `gap`.

**refresh [<target>] [--dry-run] [--nur-projekt]**

Runs exactly the blocks that are not current, producers first; before that, the other local projects this one reads with `@latest` (Chapter 14). `--dry-run` only prints what would run; `--nur-projekt` leaves the other projects alone.

**status [<target>] [--why] [--json]**

Prints one line per block: its state (`aktuell`, `veraltet`, `wartet`, `fehlt`), its name, its version and its verdict. `--why` adds the reason for each block that is not current. Status 1 if any block is not current.

## Checking

**check [<project> ...] [--ohne-termini] [--json]**

Checks the notebooks of the named projects, or of all projects found, and reports five kinds of finding: a block whose inputs changed since its run (`veraltet`), a block without a run or without a passing verdict (`Urteil`), a reference whose target does not exist or that still uses a name listed under `moved` (`Verweis`), a paragraph that conflicts with a rule of LWgrammar (`Termini`), and two blocks that make the same reading and report different values (`Zahlen`) (Chapter 6). `--ohne-termini` leaves out LWgrammar; an unreachable LWgrammar is itself a finding. Status 1 if anything was found.

## Projects

**list**

Prints every project the program finds, with its folder and its notebooks, and marks the integrating notebook.

**project new <folder> [--id <id>] [--notebook <id>] [--title <text>]**

Creates the folder with a `famulus.yml` and one empty notebook, and enters the project into the register. The id defaults to the folder's name.

**project register <folder>**

Enters an existing project into the register.

**project migrate** <package> --to <folder> --id <id> --notebook <id> [--keep]

Moves a package of the older form ( `notebook.qmd` with a `log/` folder) into a project. For each block it reports whether the old result is still current. `--keep` leaves the old package in place.

## Building

**build** [<project>]

Writes the shadow copies of the project's notebooks (Chapter 12). Without a project it writes those of every project of the site and updates the site's `_quarto.yml`.

**render**

Builds the shadow copies of the site and renders the site with Quarto.

**goldens** [--out <folder>] [--manifest-only]

Writes a notebook with one block per golden query of the query pipeline (Chapter 9). By default it also takes the ground truth kept in the pipeline's memory; `--manifest-only` takes only the manifest.

## Peers

**peers list** [<name>]

Prints each peer with its kind and its endpoints.

**peers probe** [<name>]

Tries each endpoint of each peer and prints whether it answers. Status 1 if a peer answers on no endpoint.

**peers add** <name> --endpoint <url> [--endpoint <url> ...] [--kind <kind>] [--token-env <variable>]

Enters a peer; the endpoints are tried in the order given.

## Serving

**serve** [--host <address>] [--port <n>]

Starts the viewer and the interface of Appendix C. The address defaults to `127.0.0.1`, the port to `5118`. The access log never keeps a token given in an address. An installation started by `install.sh --launchd` runs as the service `com.ai-platform.famulus-notebook` and is restarted with `launchctl kickstart -k gui/$(id -u)/com.ai-platform.famulus-notebook` rather than by a second `serve`.

## Appendix C: The HTTP interface

`famulus-notebook serve` answers on port `5118`. The viewer uses the same interface as a peer does; nothing in it is reserved for the browser. Paths are relative to the server's root, so the interface also works behind a proxy that adds a prefix, such as `/famulus-notebook`.

### C.1 Admission

Three kinds of request are admitted:

1. a `GET` of the viewer's page, its assets and the rendered site (`/notebook`, `/assets/...`, `/docs/...`), from anywhere;
2. any request from the machine itself, made directly and not through a proxy;
3. any request that presents the server's token, as `Authorization: Bearer <token>` or as the cookie `famulus_token`.

With `FAMULUS_TRUST_TAILNET` set, requests from the tailnet's addresses are admitted as well. Every other request is refused with status `401` and one of two reasons: `Token fehlt oder falsch` if the server has a token, `Dieser Server ist nur lokal freigegeben` if it has none. A server without a token therefore serves only its own machine.

`POST /api/session` turns a token presented once into the cookie, so that a browser need not present it again.

## C.2 Notebooks and projects

### GET /api/projects

Every project found: `id`, `title`, `root`, `legacy`, `main`, and its `notebooks` (`id`, `key`, `title`, `file`).

### GET /api/notebooks

Every notebook: `id` (the key `<projekt>/<notebook>`), `project`, `project_title`, `notebook`, `title`, and `main`.

### GET /api/notebooks/<key>

One notebook as the viewer shows it: its sections, each a list of text segments and blocks. A block carries its instruction, its preamble as YAML, its state and the reasons for it, its version, its verdict note, its declared artefacts and its result. A front matter that is not valid YAML gives status 422 with the file and the line.

### POST /api/notebooks/<key>/blocks

Appends a question as a new block; the body is `{question, collections}`. The journal is created on first use.

### GET /api/notebooks/<key>/artefact/<block>/<name>

The current version of an artefact. 404 if the manifest does not name it or the file is missing.

### GET /api/notebooks/<key>/trace/<block>

The stages of the block's trace, one row per stage with its duration, its attempts and its error.

## C.3 State and running

### GET /api/status?nb=<key>

The state of every block of the notebook's project, as `status --json` prints it.

### POST /api/notebooks/<key>/run[?block=<id>]

Runs the notebook, or one block with its dependencies. The answer is a stream of server-sent events, one JSON object per event, ending with `notebook_done`.

### POST /api/refresh?nb=<key>[&dry\_run=true]

Runs the stale blocks of the notebook's project, producers first. The stream ends with `refresh_done`.

### GET /api/coherence[?nb=<key>][&termini=false]

The report of `check`, for one notebook or for all.

### GET /api/health

`service`, `version`, the number of notebooks, the folders searched, whether the engine is available, and whether the viewer is built.

## C.4 Artefacts by reference

### GET /api/artefacts/<reference>[?head=true]

The artefact a canonical reference `fam:... names`, as its envelope (Appendix A.8). With `head=true` only the header. Status 400 for any other form of reference, 404 if the reference does not resolve or the version has no file.

This is the call a peer makes when a notebook elsewhere reads `peer:<name>/fam:...` .

## C.5 Collections

### GET /api/collections

The folder of the collections, whether it is mounted, and for each collection its `name`, its state from `status.json`, its number of documents and its databases.

**POST /api/collections/<name>/read**

A read confined to one collection. The body is `{sql, duckdb, limit}`: one `SELECT` or `WITH` statement, the attachments (paths relative to the collection, or beginning with `$PDAI_COLLECTIONS/<name>/`), and a row limit of at most 5000. The databases are opened read-only; then access to other files and changes of configuration are locked, and the read is interrupted after 30 seconds. The answer is `{columns, rows, n_sentences, n_documents, truncated}`. A refused statement or path gives 400, a missing file 404, an attempt to reach another file 403.

These checks hold only for a read served to a peer. A read a notebook makes on its own machine is not checked in this way (Chapter 15).

**C.6 Running a block for a peer****GET /api/peer**

What this server is: `service`, `version`, `machine`, whether the engine is available, its notebooks, its collections folder, and its `capabilities` (`notebooks`, `artefacts`, `collections-read`, `run-block`, and `partitur` when the engine is present).

**POST /api/run-block**

Runs one block sent by a peer. The body is `{block: {preamble, instruction}, famulus}`; the preamble's `engine` is removed, so the block runs here. The server runs it in a scratch folder, streams its events, and ends with `remote_done`, whose `log` carries the block's files and artefacts. The scratch folder is deleted afterwards; the caller writes the result into its own store and names the answering endpoint in `herkunft.peer`.

**C.7 Neighbours****/lektorat/...**

Passed to the Lektor (port 5114) under the same origin. Only a direct request from the machine itself is passed as the owner; every other request is passed with its address, and the Lektor asks for its own login.

**POST /api/annotations**

A note on a block, passed to the learning loop of the query pipeline (port 5113). Only from the machine itself; otherwise 403.

**GET /api/learn**

The notes, learning runs and instruction versions of that loop, as the viewer's learning pane shows them.

**Appendix D: Setting up a second machine**

This appendix gives the procedure Chapter 11 left out: how a second machine is made a coauthor of the first. It is the procedure by which the transcript of Chapter 11 was produced, on 23 September 2026, between the author's Mac Studio and a Mac mini of the same tailnet. The Mac Studio holds the collections, the orchestrator and the query pipeline; the Mac mini holds none of them.

**D.1 The machine that serves**

On the serving machine the notebook service needs a token, and it must be reachable from the other machine.

1. Create the token once:

```
$./install.sh --run --launchd --token
```

The token is written to `~/.config/famulus/token` with mode 0600. It is read from there by the service and is never printed.

2. Decide how the service is reached. The service listens on the loopback address unless `install.sh --host` says otherwise. On the Mac Studio it stays on loopback and is reached through the platform's proxy under Tailscale Serve, as `https://mac-studio.tail147011.ts.net/famulus-notebook`. A request through the

proxy carries a forwarded address, so it is never taken for a request of the machine itself and must present the token.

3. Check from the serving machine that the service answers:

```
$ nc -z 127.0.0.1 5118; echo $?
0
```

## D.2 The machine that calls

1. Install the workspace without `--run`: the calling machine needs the parser, the viewer and the command line, not the orchestrator.

```
$./install.sh
```

The installer requires `uv`, `npm` and `pandoc`. `pandoc` must also be on the search path of every later command; a shell opened by `ssh` without a login profile may lack it, and every command that reads a notebook then ends with `pandoc fehlt: der Parser braucht pandoc im PATH`.

2. Copy the serving machine's token into a file only the user can read, such as `~/.config/famulus/mac-studio.token` with mode 0600, by a channel that keeps it out of any log. Export it into a variable before each session:

```
$ export FAMULUS_TOKEN_MAC_STUDIO=$(cat ~/.config/famulus/mac-studio.token)
```

3. Enter the peer, with its endpoints in the order they are to be tried:

```
$ famulus-notebook peers add mac-studio \
 --endpoint http://100.102.189.23:5118 \
 --endpoint https://mac-studio.tail147011.ts.net/famulus-notebook \
 --token-env FAMULUS_TOKEN_MAC_STUDIO
```

The first endpoint is refused, because the service listens on loopback only. It is kept in the list on purpose: the test shows that the probe falls through to the next endpoint.

## D.3 The checks before the first run

Three checks must pass before a block is sent. The first is the probe:

### Specimen · The probe from the Mac mini

```
$ famulus-notebook peers probe mac-studio
mac-studio http://100.102.189.23:5118: [Errno 61] Connection refused
mac-studio https://mac-studio.tail147011.ts.net/famulus-notebook: antwortet
mac-studio: erreichbar über https://mac-studio.tail147011.ts.net/famulus-notebook
```

The second is admission. Each request below was sent from the Mac mini to the Mac Studio's tailnet address; the right column gives the status and the total time `curl` measured:

**Specimen · Admission from the Mac mini**

```
GET /api/peer without token: 401 0.095721s
GET /api/peer wrong token: 401 0.091659s
GET /api/peer with token: 200 0.230602s
POST /api/collections/pirckheimer/read without token: 401 0.096313s
POST /api/annotations with token: 403 0.095811s
GET /docs/ without token: 200 0.171632s
```

A request without the token and one with a wrong token are refused alike; a note to the learning loop is refused even with the token, because notes are taken only on the owner's machine; the rendered site is public.

The third check is the peer's description, `GET /api/peer` with the token. Its `capabilities` must name what the blocks will ask for: `collections-read` for a remote read, `artefacts` for a remote reference, `run-block` and `partitur` for a remote run. The Mac Studio names all five.

**D.4 The test notebook**

The notebook `zwei` of Chapter 11 has one block for each way of using a peer:

**by-direction**

reads the Pirckheimer register on the peer, through a `duckdb` attachment with `peer: mac-studio`;

**roster-size**

reads the roster of the Pirckheimer project on the peer, through a placeholder  
`{ref:peer:mac-studio/fam:pirckheimer-briefwechsel/briefpartner-1520-1530/briefpartner- ; roster.roster}`

**count-there**

plays the question of Chapter 1 on the peer, with `engine: mac-studio` and the oracle 75.

Chapter 11 shows the transcript of its first run and of the refresh after the instruction of `count-there` was completed. On 24 September 2026 the status on the Mac mini was unchanged:

**Specimen · Status on the Mac mini**

```
$ famulus-notebook status zwei --why
aktuell zwei/by-direction v1 pass
aktuell zwei/roster-size v1 pass
aktuell zwei/count-there v1 pass
zwei: 3 Blöcke, 0 nicht aktuell
```

**D.5 What the test found**

The test did not pass at the first attempt. Each failure was a defect of the program, not of the network, and each was corrected before the transcript of Chapter 11 was taken:

1. The remote read and the remote reference ended as errors on the Mac mini, because every verdict, even one without an oracle, went through the orchestrator, which the Mac mini does not have. A block without an oracle is now judged without it; a block with an oracle still needs it, which is why `count-there` runs on the peer (Chapter 16).
2. A fetched artefact was stored under a name derived from the whole reference, which destroyed the artefact's name. Fetched artefacts now lie under `_famulus/cache/extern/<peer>/...`, one folder per peer, notebook and block, each with a `.source.json`.

3. The installer failed on the machine without `--run`, because the lock file of the environment names the orchestrator and the query pipeline as neighbouring folders. Without `--run` the installer no longer resolves them.
4. The probe of a Lektor peer asked for the wrong path and got 404.

One observation concerns the query pipeline rather than the notebook. The remote run that passed its oracle was, at the same time, flagged by the pipeline's own goal check as not reaching its goal, and the check wrote a note into the learning loop. The notebook shows the oracle's verdict; the disagreement is listed among the open gaps of Chapter 16 and returns in Appendix E.

## ■ Appendix E: A baseline of the query pipeline

Famulus Notebook changes nothing in the query pipeline that answers its subtasks. It replaces the pipeline's user interface, and it reads the pipeline's goldens (Chapter 9). To show that the pipeline was not disturbed by the notebook, its standing delivery gate was run on 23 September 2026, against the query service on port 5113:

```
$.venv/bin/python scripts/chat_golden_loop.py --parallel 2
```

The gate drives every golden through the function the pipeline's chat answers with, and sorts the outcomes into four verdicts:

### **DELIVERED**

an answer reached the caller and did not fail its oracle;

### **WRONG**

an answer reached the caller and failed its oracle;

### **EMPTY**

no answer reached the caller;

### **ERROR**

the run broke off before an answer could be taken.

It also prints the pipeline's own grade of each run. That grade is taken before the answer is delivered, and it is not the oracle's verdict.

**Specimen · The gate on 23 September 2026**

29/41 DELIVERED 9 WRONG 3 EMPTY 0 ERROR

engine: gemini-3.5-flash-lite=41

EMPTY (synthesis not delivered to caller):

gnd-pirck-b-schoener-subject empty synthesis; last stage: goal-check  
 ground-kepler-sec-kepler empty synthesis; last stage: goal-check  
 ground-sundial-geometry-1 empty synthesis; last stage: goal-check

WRONG (delivered but oracle check failed):

R1 n\_sentences: 0 < min 30  
 R5 n\_sentences: 2 < min 50  
 K4 n\_letters: 200 > max 25  
 K5 n\_sentences: 0 < min 100  
 ground-diaries-translit-1 n\_sentences: 0 < min 1  
 ground-euler-iva-letters-1 n\_letters: 0 < min 1  
 ground-euler00-vis-motus n\_sentences: 0 < min 30  
 ground-pirckheimer-3 matches: missing (expected ['Savorgnanus', 'Schöner'])  
 ground-pirckheimer-4 n\_letters: 200 > max 80; n\_unique\_correspondents: ...

The last line is shortened here; the gate goes on to list the filters of topic and direction that the answer did not apply.

The gate's threshold is 28 delivered goldens; the run meets it. Every golden was answered by `gemini-3.5-flash-lite`.

**What the numbers say**

The figure 29 must be read with the four verdicts in mind, because they are not all of one kind.

1. **Two of the 29 have no oracle.** `gnd-pirck-a-corr-count` and `gnd-pirck-c-hartmann-mention` are counted as delivered because an answer reached the caller; there was nothing to compare it with. In the terms of this book they are *ohne Oracle*, not *bestanden* (Chapter 4).
2. **Two WRONG goldens fail on one limit.** K4 reports 200 letters against a maximum of 25, `ground-pirckheimer-4` 200 letters against a maximum of 80. 200 is the row limit of the pipeline's query step, reported as if it were the scope of the answer; Chapter 13 met the same limit in the Kármán project.
3. **Five WRONG goldens found no sentences or letters at all**, where the oracle expects at least one: R1, K5, `ground-diaries-translit-1`, `ground-euler-iva-letters-1`, `ground-euler00-vis-motus`.
4. **The three EMPTY goldens end at the goal check.** The pipeline produced an answer and its own check withheld it.
5. **The pipeline's grade and the oracle disagree in both directions.** Two goldens are delivered, with a passing oracle, and graded "incorrect" by the pipeline: `euler-goldbach`, whose correct answer is a gap, and `golden-karman-manuscripts-inventory`. Nine goldens are WRONG, and the pipeline graded seven of them "correct". Appendix D met the first direction on the second machine.

The notebook shows the oracle's verdict and never the pipeline's grade. The baseline is the reason: on these 41 questions the grade would have said "correct" of seven answers that were wrong.

**How the baseline is repeated**

The gate writes every WRONG and EMPTY outcome into the pipeline's register of delivery gaps, and its runs go through the same goal check that writes notes into the learning loop. It is therefore not repeated for the sake of a figure in a book; it is to be repeated after each change to the pipeline, and its summary then replaces the one above. That rule has not been kept for this edition: two files of the pipeline, `guard.py` and `pipeline/synthesis.py`, were changed at 16:14 on the same day, after the run ended at 12:54; the summary above describes the pipeline before that change, and whether the change moved any verdict is open.

## ■ Appendix F: For famuli

A famulus is a software agent that reads and writes notebooks. This appendix collects the boxes **For famuli** of the chapters, ordered by what a famulus does, and adds the rules of conduct that follow from them. The formal contracts of the files are in Appendix A; this appendix says what a famulus may conclude from them and what it must not do.

### ■ F.1 Rules of conduct

1. **Report the verdict the result states, not a better one.** Report `result.json.urteil`, not `verdict.json.status`. A block with `urteil: unchecked` has not been checked; saying “passed” of it is false (Chapter 1).
2. **Do not retry a gap.** A `gap` is an answer: the data cannot answer the question. Retry an `error` only after the cause named in `verdict.json` is removed; do not retry either with another model in the hope of a pass (Chapter 4).
3. **Change the question, not the answer.** When a verdict is wrong, change the preamble or the instruction and run again; never edit a result, an artefact or a manifest. A result that was not produced by a run is not a result (Chapters 7 and 10).
4. **Decide identity by checksum.** Two results are the same when their `sha256` values are equal, whatever their timestamps (Chapter 7).
5. **Never write a token.** Not into a notebook, a `peers.yaml`, a log or a message. Read it from the file where it is kept, put it into the variable that `token_env` names, and pass only the variable’s name (Chapter 11).
6. **Leave notes to the owner.** A note on a block goes into the learning loop of the query pipeline and changes its instructions. A famulus does not send notes on its own account; it proposes them.
7. **Take every number of the prose from a result.** `check` compares two blocks that make the same reading, but it does not compare the prose with the results. A famulus that writes prose takes each number from a result and names the reference it comes from, so that a reader can check it (Chapters 6 and 12).
8. **Add no judgement of the author.** An instruction of the owner is a directive about the text. A famulus that revises carries it out and does not add remarks about the author, the text or the instruction (Chapter 9).

### ■ F.2 Verdicts

`verdict.json` field `status` is one of `pass`, `fail`, `gap`, `error`. `result.json` field `urteil` equals `status`, except that `status: pass` with an empty or missing `oracle` becomes `urteil: unchecked` (Chapter 1).

A `fail` writes no artefact files; the manifest’s `artefacts` list is empty, and a block that reads the artefact through a placeholder waits with `hängt an <ref>, dort liegt noch keine Version`, “depends on `<ref>`, which has no version yet” (Chapter 4).

### ■ F.3 The preamble

Precedence for every scope key: the block’s preamble, then the notebook’s settings, then nothing. No key is inferred from the instruction. The instruction becomes `goal`, `inputs.instruction` and `inputs.raw_query` of the run request; `years` becomes `inputs.year_from`, `inputs.year_to` and `inputs.years` (Chapter 2).

The settings of a notebook are the project’s `defaults`, updated with the notebook’s own `famulus: mapping` minus `id`, `uses` and `chapters`. For a subtask, `language`, `persons`, `lemmata`, `counting_mode`, `evidence`, `reading_doc`, `person_id`, `project`, `terms` and `locked` are taken from the preamble if present, else from the settings. `years` is read from the preamble only, `client` from the settings only. Inside the orchestrator, explicit input wins over a setting file, and a setting file over the Partitur’s default (Chapter 5).

The accepted `subtask` values are listed in Appendix A. Any other value is refused before the run with `unbekannter subtask '<value>'` (Chapter 2).

A subtask name is carried twice. The request’s `subtask` input is overwritten by the Partitur’s decomposition stage, so the runner also passes the name as `notebook_subtask`, which no stage writes. The pipeline’s routing chooses the specialist for that name over the one its classifier would choose; the lemma stage takes the preamble’s `lemmata` as given for a co-occurrence (Chapter 14).

## F.4 Reading data

`duckdb` entries: `alias` (a Python identifier, default `main`), `path` (absolute or with `$PDAI_COLLECTIONS`), `read_only`. Only files ending in `.duckdb` or `.db` are attached; any other entry is skipped without a message, so a Parquet file is read with `read_parquet`, not attached. The corpus root is `/Volumes/PDAI-1/pdai-collections` when `PDAI_COLLECTIONS` is not set (Chapter 8).

A read served to a peer is stricter: one statement, `SELECT` or `WITH` only, paths inside one collection, no external file access, at most 5000 rows and 30 seconds (Appendix C). A read on the famulus's own machine is not held to these rules; a famulus holds itself to them.

A sentence of a collection is identified by the triple `(doc_id, pidx, sent_idx)`, because `sent_idx` starts again on every page. A count of lemmata states its mode, `canonical`, `family` or `family+adj`; a count in a bilingual edition states its language (Chapter 8).

## F.5 Results and versions

`result.json.display` is always a mapping with at least `format`. Rows are read from `data.entries` or `data.rows` of the artefact's payload. For `kennzahl`, `result.json.messwerte` lists one entry per figure with `name`, `label`, `beobachtet` (observed) and `erwartet` (expected; empty when no oracle names the figure) (Chapter 3).

`current.json` is `{"version": N, "since": <time>}`. A version folder `vNNNN/` holds `manifest.json`, `report.json`, `result.json`, `verdict.json` and `artefacts/`, and `trace.json` for a subtask. An unchanged rerun rewrites the manifest's input hash but not the artefact file, so the envelope's `created` and `input_hash` belong to the run that first made the content (Chapter 7).

The trace is served at `GET /api/notebooks/<notebook>/trace/<block>`. A local step has no trace. The origin of a result is the field `herkunft: partitur, modell, sammlungen, dauer_ms`, and `peer` for a block that ran elsewhere (Chapter 10). For `lwgrammar: steps modell` names the project's client although no model was called (Chapter 16).

## F.6 References

A selector matches `latest`, `locked`, `v<digits>` or `sha:<4–64 hex>`; anything else is refused with `unbekannte Version @<x>` (`latest`, `vN`, `sha:...`, `locked`). `@locked` falls back to the current version when the lock has no entry for the name. `@sha:` is refused with `keine Version mit sha:<x>` when no version has that checksum. A short name's selector applies only when the reference itself says `@latest` or nothing (Chapter 6). The grammar is in Appendix A.

## F.7 Annotation

Fine correction and reformulation are told apart by the share of changed words: above 50 % the Fassung is a reformulation. The share is computed on words, so a changed word counts once whatever its length (Chapter 9).

A rendered paragraph carries its source range in `data-pos` (for example `data-pos="9-11"`) and its identity in `data-seg-id`, the section's slug and the ordinal of the paragraph within the section. An annotation is anchored by the source range and the stored text, never by the identity alone; the identity changes when a paragraph is inserted before it. The Lektor's store is `annotations.duckdb` of `ai-lektorat`, with the tables `annotations`, `revision_runs` and `segment_versions` (Chapter 9).

## F.8 Rendering and running

The Quarto extension reads `famulus-build` from the shadow copy's front matter, finds every block, and reads `result.json` and the first artefact from the block's version folder. A shortcode whose reference was not resolved writes *Verweis ... ist nicht aufgelöst (famulus-notebook build)*, rather than guessing a file. Nothing in the extension calls the runner (Chapter 12).

At most two blocks of a notebook run at a time. A block that plays a Partitur makes several model calls and opens several DuckDB connections, one after the other; local steps finish in milliseconds (Chapter 14).

## Appendix G: Solutions to the exercises

The solutions were worked in a copy of the companion project on 24 September 2026; figures are those of that copy. Where an exercise asks you to try something, the solution says what happened when it was tried.

### Chapter 1

1.1 Both blocks run, but only `first-count` gets a new version. Its preamble changed, so it is stale (*veraltet*). `first-list` depends on it and waits for it (*wartet*), then runs; its own statement still reads 1520–1530, so its table is the same as before and it keeps its version (*v1 unverändert*). A block runs again when something it depends on changed; it gets a new version only when its result changed.

1.2 The viewer shows ten rows and no button for more, because ten rows are fewer than the twelve a table shows. `partners.json` holds exactly ten rows as well: `LIMIT` belongs to the reading, not to the display, so the other 67 correspondents are not in the artefact at all.

1.3 `urteil: unchecked`. With an oracle, `urteil` would become `pass` or `fail`, and each figure the oracle names would get its expectation in `erwartet`, which is empty now.

### Chapter 2

2.1 `id: identity`. `years: scope`. `subtask: plan`. `golden` and `oracle: checking`. `display: display`. `duckdb: data`. `artefacts: artefacts`. The block has no key of the order group; its collection comes from the project's defaults.

2.2

```
id: letters-1522
display: kennzahl
duckdb:
 - {alias: main, path: $PDAI_COLLECTIONS/pirckheimer/pirckheimer.duckdb, read_only:
true}
partiturs:
 - id: duckdb-read
 input:
 sql: |
 SELECT count(*) AS n_letters FROM letters_resolved
 WHERE TRY_CAST(left(date_when, 4) AS INTEGER) = 1522
artefacts:
 - {name: count, kind: table, file: count.json}
```

`collections` can be left out; a `duckdb-read` does not use it at all, because the attachment names the file. `duckdb` cannot be left out: the defaults name no database. `artefacts` can be left out if the result need not be read by another block.

2.3 The runner files the block under the slug of its section, such as `anfang#1`, and ends it as an error: *Präambel ohne id*. The other blocks of the notebook still run. No block can name it in `depends_on`, because it has no name; a `depends_on` with a name that no block has is reported by `check` (*kein solcher Block*) and stops the run when that block's turn comes (*Abhängigkeit ohne Manifest*).

### Chapter 3

3.1

```
display:
 format: liste
 spalten:
 - {feld: name, label: Correspondent}
 - {feld: count, label: Letters, art: zahl}
```

The row limit stays twelve, the default of the table's form, because the mapping does not set `zeilen_sichtbar`. All 77 rows remain in the artefact; the list shows twelve and the rest behind the button.

3.2 `gruppe: name`, with `spalten` for `kind` and `count`. The statement already returns the column `name`, the place, which now forms the groups; it need not change. Because `HAVING count(*) >= 5` applies to each pair of direction and place, a place may appear with only one direction.

### 3.3

The register dates most letters to 1525, 105 of the 354. The letters of each year, by direction:

```
{{< famulus letters-by-year.years >}}
```

The year and the number are taken from `ch03/peak-year`; a page that is to stay right after a later run should insert that result too, rather than repeating the figure in prose.

## Chapter 4

### 4.1

```
oracle:
 n_sentences: {min: 70}
 rows: [Erasmus]
```

A range and a list. A reading of several rows observes its number of rows as `n_sentences` and the rows themselves as `rows`; the list form looks for *Erasmus* in them and finds *Erasmus, Desiderius*. The verdict is *bestanden*. A substring on the answer (`answer_contains: Erasmus`) does not work: the answer of a table is only *77 Sätze*, and the key would have to name an observed value.

4.2 Its oracle 75 does not hold (77 were observed), and a block that does not pass writes no artefact. A block that reads `{ref:count-golden.count}` waits: *hängt an ..., dort liegt noch keine Version*.

4.3 Change one thing: widen the years, or narrow them, and ask the same question again. If the pipeline still reports 200, the figure is a limit, not a count; if it changes with the scope, compare it with the register's count for the same scope, letter by letter. Chapter 13 made this check: 200 is the row limit of the pipeline's query step.

## Chapter 5

5.1 The integrating notebook lists the chapters, in `famulus: chapters: [kapitel/a.fam, kapitel/b.fam]`; `famulus.yml` names it with `main.status` reports the notebooks in the order of that list, producers before consumers when one chapter reads another.

5.2 `karman-nachlass`: the notebook's `famulus:` mapping overrides the project's defaults. With `collections: [kepler-prim]` in the block, the block reads `kepler-prim`; the preamble wins over both. A list replaces the list below it; it is not joined with it.

## Chapter 6

6.1 In `ch02.fam`, `first-count.count` means `fam:lehrbuch/ch02/first-count.count`, a block of the same notebook. There is none; `first-count` lives in `ch01`, so the short name must be `ch01/first-count.count`, and `check` reports the wrong one. In `ch04.fam`, `ch01/first-list.partners` means `fam:lehrbuch/ch01/first-list.partners`. `pirck/briefpartner-roster.roster` means `fam:pirckheimer-briefwechsel/briefpartner-1520-1530/briefpartner-roster.roster` everywhere in the project, because `pirck` is an alias of `imports`.

6.2 The lock records that `star` read version 1 of the roster. With the version number: `pirck/briefpartner-roster.roster@v1`. With the lock: `@locked`.

6.3 Change the `id` to `year-table` and add `ch03/letters-by-year: ch03/year-table` under `moved` in `famulus.yml`. The reference `letters-by-year.years` in `peak-year` is then resolved to the new name, but `moved` does not apply to `depends_on`: change that entry to `year-table`. The results of the old name stay under its folder; the renamed block has no result until it runs, so run it. Until you also write the new name into `peak-year`, check reports *heißt jetzt fam:lehrbuch/ch03/year-table.years (moved)*.

## Chapter 7

7.1 After the edit, `letters-by-year` is *veraltet* and `peak-year` *wartet*. After the refresh the table has a new version; `peak-year` runs because what it read changed, finds 1525 with the same number of letters, and keeps its version. It is current, and the blocks that read it do not run.

7.2 It read `fam:lehrbuch/ch07/span.span@v1`, version 1, with the checksum `8fe937c252b32a0d`. Open `_famulus/store/ch07/span/v0001/artefacts/span.json` and compare the first sixteen digits of `famulus.sha256` with the lock's `sha`. They agree.

7.3 `rerun: never` for a result that must not be made again by accident, such as a run of a paid model whose answer the text cites. `rerun: always` for a block whose answer can change without any change of its input, such as the statements about the *Canones Sapheae* in Chapter 13, which a language model extracts.

## Chapter 8

8.1 `WHERE lang = 'de' AND doc_id = 'kgw-01'`. The volume has 2,917 German sentences.

8.2 Without `pidx` the key counts, in each of the 26 Latin volumes, the distinct sentence numbers that occur on any page: a volume counts as many sentences as its longest page has. Document by document:

```
SELECT sum(n) FROM (
 SELECT doc_id, count(DISTINCT sent_idx) AS n
 FROM stz_sentences WHERE lang = 'la' GROUP BY doc_id)
```

It returns 5,357.

## Chapter 9

9.1 The card lists one goal, the replacement: the old phrase must be gone and the new phrase present. It is checked mechanically. *Change nothing else.*, if you added it, is listed as unchecked. The formulation check reports the replaced statement as added; since the replacement was recognised as an order, that finding no longer blocks.

9.2 A reformulation, if more than half of the words changed; a fine correction otherwise. The Original chip shows the old wording on hover and opens a window to compare the two. After *Verwerfen*, `status lehrbuch` reports every block as before: the `.fam` file was not changed, and prose is not an input of any block.

## Chapter 10

10.1 `choose-specialist` chose the route; the row `answer-from-register` with its child `correspondence-roster` shows it. `afm-query-extract` took the most time, 2,370 ms. The stages that call a language model are the few that take long: `afm-query-extract`, `normalize` and `intent-gate`.

10.2 The route is the letter list (`letter-list`): 200 letters with 70 correspondents, and the verdict *abweichend* against 75. `refresh` runs this block alone because only its instruction changed and no other block reads it.

10.3 For example: Stage `choose-specialist`: for “How many correspondents did Pirckheimer have between 1520 and 1530?” it took the letter list and counted the partners of the letters it found (200 letters, 70 persons). It should have taken `correspondence-roster`, which reads the register of letters and resolves the persons. Keep the note; the owner decides whether it goes into the learning loop.

## Chapter 11

11.1 The first endpoint that answers within the probe's time is chosen. A probe waits at most 1.5 seconds for an endpoint; a refused connection returns at once.

## 11.2

```
SELECT TRY_CAST(left(date_when, 4) AS INTEGER) AS year, count(*) AS letters
FROM letters_resolved GROUP BY year ORDER BY year
```

with the attachment `$PDAI_COLLECTIONS/pirckheimer/pirckheimer.duckdb` and `peer: mac-studio`. The peer refuses a second statement (*nur eine Anweisung*) and a `COPY` (*nur SELECT oder WITH, or nicht erlaubt: COPY inside a WITH*). A join with a table of another collection needs an attachment outside the collection (*Pfad außerhalb der Sammlung*) or a table function that reads another file, which the locked configuration refuses. The caller already refuses attachments in two collections (*eine entfernte Lesung liest genau eine Sammlung*).

11.3 In `_famulus/store/zwei/count-there/v0001/report.json` on the calling machine. `result.json` names the origin in `herkunft.peer: https://mac-studio.tail147011.ts.net/famulus-notebook`. Run locally, the field `peer` would be missing.

## Chapter 12

12.1 Both builds name the same version folder of `places`: a forced run that produces the same table keeps the version. They differ only when the forced run produces a different result, which then gets a new version, and the second build names the new folder.

## 12.2

```
The register dates 354 letters between 1520 and 1530
(`fam:lehrbuch/ch07/span.span@v2`).
```

Leaving out `@v2` makes the reference name the current version. A paper does not change after it is printed; its figure would then disagree with the result a reader finds as soon as the result changes.

## Chapter 13

13.1 Between 1930 and 1940, with how many persons did Kármán exchange letters, counting as his correspondent the other party of every letter he wrote or received? The oracle `n_correspondents: 490` states the count of that reading in the register. A floor of 200 is met by all three readings and so decides nothing; it is also the row limit of the pipeline, so a result capped at the limit passes it.

13.2 It would have to read `lex-natura.kwic`. That artefact is a text: a line per sentence with its volume and a shortened wording, without `pidx` or `sent_idx`. The block cannot be written against it; the comparison needs a result that carries the coordinates, which the pipeline does not deliver for this question.

## Chapter 14

14.1 `status` reports the block as *veraltet*, because the file's modification time changed. `refresh` runs it; the result is the same, the version stays, and the blocks that read it do not run. The part concerned is `inputs`, which takes size and modification time of each file read. The notebook cannot change it; the block stays current only if the other program keeps the file's time when the content is unchanged.

14.2 None. The chain stops after the harness step, which did not pass, and a block that does not pass writes no artefact. `result.json` shows the verdict `fail` and the harness step's answer and figures.

## Chapter 15

15.1 The block it reads must have no version of the artefact: it has never run, or all its runs failed. A `fail` writes no artefact, so a block that has only failed has none.

15.2 A local reading refuses none of them with these messages. An alias that is not a plain name fails locally as well, with *bad attachment alias 'a-b'*, and a writing statement is refused by DuckDB, because the files are opened read-only. A second statement is not refused: the block `SELECT 1 AS a; SELECT count(*) AS n FROM letters_resolved` passed, with the row of the last state-

ment (354). A path outside a collection, a table function reading another file, and a long reading are not refused either.

## Index

### A

A/B gate, 55, 57  
 admission, 97, 98, 99, 102  
 ai-query-phase1, 13, 81  
 alias, 32, 43, 86, 92, 109  
 anima and vis, 72  
 annotation, 9, 47, 52, 55, 59, 107  
 annotations.duckdb, 107  
 artefact, 8  
   kind, 12, 15, 87, 94, 109  
 artifact:<kind>, 13, 18, 74, 94

### B

baseline, 1, 104  
 bearer token, 59, 62  
 bibliography, 5, 90  
 block, 7  
   completeness, 11  
   instruction, 7, 11  
   preamble, 7, 11  
 build (command), 63

### C

Canones Sapheae, 20, 69, 110  
 cascade, 39, 80, 89  
 casebook, 1  
 chapter notebook, 10, 12, 27  
 checksum, 1, 30, 33, 37, 51, 60, 65, 80, 95, 106, 110  
 citation, 5, 50, 90, 94  
 co-occurrence, 44, 106  
 collection, 7, 42  
   folder, 101  
 command line, 1, 8, 47, 54, 83, 98, 102  
 commentator, 1, 57  
 counter-check, 20, 25, 32, 72  
 counting mode, 44, 45, 70, 85, 89  
   canonical, 45, 70, 93, 107  
   family, 93, 107  
   family+adj, 45, 93, 107  
 current.json, 9, 38, 63, 82, 91, 107

### D

data-pos, 51, 107  
 data-seg-id, 107  
 dependency, 11, 79, 100  
   cycle, 1, 79, 83, 94  
 derived from, 37  
 design decisions, 5  
 Diagnose, 9, 52, 87  
 display, 8, 15  
   belegliste, 15, 64, 94  
   columns, 9, 16, 22, 46, 81, 84, 94, 102, 109  
   gruppe, 17  
   hierarchische-tabelle, 15, 64, 94  
   kennzahl, 8, 15, 64, 94, 107  
   liste, 15, 64, 94  
   netz, 13, 15, 58, 64, 81, 90, 94, 103  
   sortierung, 94  
   spalten, 17, 94, 109  
   tabelle, 15, 64, 94  
   textkarten, 15, 64, 94  
   zeilen\_sichtbar, 16, 109  
 dry run, 40  
 DuckDB, 6, 8, 12, 39, 43, 60, 89, 94, 100, 108  
   attachment, 43, 79, 86, 94, 101, 103, 108  
   read-only, 8, 12, 43, 67, 81, 86, 90, 101, 111  
 duckdb (key), 8, 12, 43, 46, 60, 79, 93, 103, 107, 108  
 duckdb-read, 8, 13, 23, 37, 74, 85, 94, 108

### E

Einstein, Albert, 74  
 empty result, 23, 84  
 endpoint, 58, 87, 90, 99, 101, 102, 110  
 engine, 46, 100  
 ent\_canonical, 7  
 entity, 70

### id, 7

placeholder id, 24  
 envelope, 36, 38, 60, 95, 100, 107  
 Erasmus, Desiderius, 10, 12, 67, 109

### F

.fam file, 27  
 famulus (Quarto extension), 64, 91, 107  
 famulus-build, 63, 64, 107  
 famulus-notebook  
   build, 64, 84, 92  
   check, 35, 60, 85, 93, 98, 100, 106, 108  
   refresh, 38, 54, 62, 79, 84, 98, 110  
   run, 8, 54, 79, 98  
   serve, 9, 99  
   status, 29, 39, 65, 95, 98, 106, 109  
 famulus.lock, 27, 33, 41, 66, 79, 95, 104, 107, 109  
 famulus.yml, 10, 27, 28, 31, 41, 64, 79, 84, 91, 98, 109  
   defaults, 28, 43, 106  
   imports, 28, 32, 92, 109  
   main, 28, 43, 94, 100, 107, 109  
   moved, 28, 34, 98, 110  
 \_famulus/, 8, 28  
   cache/extern, 60  
 Fassung, 48, 77, 107  
 fine correction, 49, 107, 110  
 formulation check, 13, 48, 49, 57, 76, 110  
   evaluation, 49, 78  
 front matter, 28, 31, 51, 63, 84, 92, 100, 107

### G

goal check, 53, 91, 104, 105  
 golden, 13, 16, 21, 23, 54, 62, 67, 90, 94, 99, 104  
   ground truth, 99  
 grade, 52, 87, 104  
 guard, 69, 82, 87

### H

harness, 81, 87, 90, 95, 111  
 HTTP interface  
   /api/peer, 58  
   /api/run-block, 61  
   events, 100

### I

input hash, 39, 41, 82, 89, 95, 107  
   modification time, 66, 79, 90, 111  
   parts, 95  
 install.sh, 97  
 installation, 6, 30, 62, 97  
 instruction (of a stage), 55  
 instruction version, 55, 101  
 integrating notebook, 27, 32, 91, 98, 109

### J

journal, 97, 100  
 Jupyter, 90

### K

Kepler, Johannes, 1, 11, 20, 25, 29, 32, 41, 42, 48, 70, 91  
 kernel, 89  
 Kármán, Theodore von, 1, 33, 41, 42, 74, 105, 111

### L

Lamport, Leslie, 5, 90  
 language filter, 43, 44, 107  
 language model, 13, 28, 37, 52, 74, 110  
   gemini-3.5-flash-lite, 74, 105  
 learning loop, 52, 55, 59, 88, 91, 101, 103, 105, 106, 110  
 Lektor, 1, 47, 48, 57, 76, 88, 89, 97, 101, 104, 107  
 lemma, 14, 25, 42, 70, 85, 89, 93, 106  
 letters\_resolved, 7, 67  
 lex naturae, 43  
 literate programming, 90  
 local step, 13, 18, 37, 42, 68, 81, 89, 107  
 loopback, 58, 98, 101  
 LWgrammar, 1, 35, 48, 52, 72, 79, 87, 90, 94, 98  
   rule, 48, 57  
   rule proposal, 52

task form, 94  
lwgrammar:<tool>, 94

**M**

Mac mini, 61, 101  
Mac Studio, 101  
manifest.json, 9, 11, 61, 79, 83, 89, 94, 99, 100, 106, 108  
manuscript inventory, 34, 74

**N**

notebook front matter  
  chapters, 29, 93, 106  
  uses, 29, 32, 84, 96, 106  
notebook key, 29  
notebook\_subtask, 106

**O**

open gaps, 104  
oracle, 10, 21  
  floor, 71, 84, 111  
  range, 22  
  substring, 22, 109  
orchestrator, 6, 13, 60, 81, 87, 90, 98, 101, 106  
Original chip, 49, 110  
owner, 47, 57, 88, 89, 101, 103, 106, 110

**P**

part of speech, 72  
Partitur, 13  
Partitur card, 48, 52, 57  
PDAI, 6, 7  
PDAI\_COLLECTIONS, 8, 42, 94, 107  
peer, 35, 58, 66, 79, 86, 89, 92, 97, 99, 102, 107, 111  
  kinds, 58  
  probe, 58, 90, 96, 102, 110  
peers.yaml, 59, 86, 89, 92, 106  
  token\_env, 58, 87, 97, 106  
Pirckheimer, Willibald, 1, 7, 12, 18, 23, 41, 42, 54, 60, 64, 67, 91,  
  103, 110  
placeholder, 11, 13, 17, 24, 36, 92, 103, 106  
port, 9, 88, 97, 99, 104  
preamble keys  
  artefacts, 8, 12, 15, 31, 59, 95, 101, 103, 106, 108  
  collections, 12, 46, 93, 108  
  counting\_mode, 12, 43, 81, 93, 106  
  depends\_on, 12, 31, 79, 85, 94, 108  
  display, 12, 20, 95, 108  
  duckdb, 12, 60, 86, 94, 107, 111  
  engine, 61, 80, 87, 90, 95, 101  
  evidence, 12, 43, 81, 93, 106  
  golden, 13, 23, 90, 95, 108  
  guard, 13, 69, 79, 87, 95  
  id, 12, 29, 81, 85, 94, 100, 106, 108  
  language, 12, 43, 81, 93, 106  
  lemmata, 12, 43, 81, 85, 94, 106  
  locked, 12, 43, 81, 93, 106  
  oracle, 13, 95, 106, 108  
  partiturs, 8, 12, 61, 81, 85, 94  
  persons, 12, 43, 81, 93, 106  
  reading\_doc, 12, 43, 81, 93, 106  
  rerun, 12, 41, 70, 79, 93, 110  
  subtask, 12, 81, 85, 94, 106, 108  
  terms, 43, 81, 93, 106  
  years, 12, 42, 106, 108  
produced\_by, 37  
producer and consumer, 39, 79, 98, 100, 109  
project, 10, 27  
project id, 28  
project register, 29, 30, 92  
publication, 5, 33, 62, 90

**Q**

Quarto, 10, 21, 27, 62, 84, 90, 92, 98

**R**

read\_json\_auto, 13  
read\_parquet, 107  
reference  
  canonical form, 65, 85, 100  
  short form, 18, 27, 32, 107, 109  
reference name, 1, 28, 31, 60, 84, 96, 111  
reformulation, 49, 107, 110  
refresh, 13, 39, 103, 110  
register, 7

persons, 70  
remote execution, 61, 62, 80, 95, 103  
remote read, 60, 80, 84, 90, 95, 103  
  refusals, 86  
remote reference, 60, 89, 103  
render (command), 64  
report.json, 107  
reproducible research, 90  
result.json, 9, 15, 83, 106, 111  
  herkunft, 74, 82, 91, 95, 107  
  messwerte, 95  
  urteil, 95, 106, 108  
review card, 46, 47  
route, 25, 49, 53, 72, 110  
row limit, 75, 91, 101, 105, 109  
rule store, 57

**S**

Schöner, Johannes, 1, 10, 12, 20, 68, 89  
selector, 31, 33, 39, 86, 95, 107  
  latest, 33, 39, 79, 84, 96, 98, 107  
  locked, 33, 40, 79, 95, 107, 109  
sentence key, 20, 44, 72, 107, 110  
setting, 65, 81, 87, 90, 91, 106  
shadow copy, 63, 92, 99, 107  
share link, 58, 91  
shortcode, 15, 21, 63, 65, 107  
side panel, 46, 57  
site, 21, 58, 64, 84, 98, 99, 103  
specialist, 106  
stage, 52, 72, 87, 89, 100, 106, 110  
Stanza, 43  
state, 39  
  veraltet, 1, 13, 30, 38, 51, 57, 66, 79, 93, 100, 108  
status.json, 100  
step  
  chain, 12, 50, 58, 81, 85, 111  
stz\_sentences, 43  
subtask, 13, 23, 42, 52, 59, 81, 85, 89, 95, 104, 106  
  concept-statements, 94  
  cooccurrence, 94  
  correspondence-count, 14, 23, 94  
  correspondence-roster, 53, 94, 110  
  letter-subject, 94  
  manuscript-inventory, 94  
  mention-in-letters, 94  
  terminology-find, 94

**T**

tailnet, 58, 90, 97, 98, 99, 101  
timestamp, 106  
token, 58, 72, 87, 89, 96, 98, 99, 101, 106  
trace, 52, 61, 78, 82, 87, 95, 100, 107

**V**

verdict, 9  
  fail, 23, 54, 79  
  gap, 5, 13, 23, 70, 81, 84, 90, 105, 106  
  passed, 22  
  unchecked, 10, 11, 23, 49, 84, 89, 110  
verdict.json, 9, 87, 106  
version, 8, 33  
  current, 33, 37, 65, 67, 82, 100, 107, 111  
  folder, 82, 89, 95, 107, 111

## ■ Bibliography

- [1] G. Graßhoff, “Golden Queries in AI Erasmus: A Testbed for Scholarly Inquiry — Query Forms, Grounding, and the Monitor Log,” 2026.
- [2] D. E. Knuth, “Literate Programming,” *The Computer Journal*, vol. 27, no. 2, pp. 97–111, 1984, doi: 10.1093/comjnl/27.2.97.
- [3] J. F. Claerbout and M. Karrenbach, “Electronic Documents Give Reproducible Research a New Meaning,” *SEG Technical Program Expanded Abstracts*, pp. 601–604, 1992, doi: 10.1190/1.1822162.
- [4] R. D. Peng, “Reproducible Research in Computational Science,” *Science*, vol. 334, no. 6060, pp. 1226–1227, 2011, doi: 10.1126/science.1213847.
- [5] T. Kluyver *et al.*, “Jupyter Notebooks – a publishing format for reproducible computational workflows,” in *Positioning and Power in Academic Publishing: Players, Agents and Agendas*, IOS Press, 2016. doi: 10.3233/978-1-61499-649-1-87.
- [6] J. J. Allaire, C. Teague, Y. Xie, and C. Dervieux, “Quarto.” Zenodo, 2022. doi: 10.5281/zenodo.5960048.
- [7] M. Raasveldt and H. Mühleisen, “DuckDB: an Embeddable Analytical Database,” in *Proceedings of the 2019 International Conference on Management of Data (SIGMOD '19)*, ACM, 2019, pp. 1981–1984. doi: 10.1145/3299869.3320212.
- [8] J. A. Donenfeld, “WireGuard: Next Generation Kernel Network Tunnel,” in *Network and Distributed System Security Symposium (NDSS 2017)*, Internet Society, 2017. doi: 10.14722/ndss.2017.23160.
- [9] G. Graßhoff, “The AI Partitur — A Score Language for the Humanities,” 2026.
- [10] G. Graßhoff, “The AI Agent Orchestrator: Partitur, Conductor, and Harvest.” 2026.
- [11] G. Graßhoff, “Famulus. Eine verteilte lokale Plattform für professionelle Forschung,” 2026.
- [12] G. Graßhoff, “Wittgensteinian Grammar and OED Dictionaries for AI,” 2026.
- [13] L. Wittgenstein, *Philosophische Untersuchungen*, 11th ed. Frankfurt am Main: Suhrkamp, 2022.